



The State of New Hampshire
Department of Environmental Services



Robert R. Scott, Commissioner

WETLANDS AND NON-SITE SPECIFIC PERMIT 2021-00163

NOTE CONDITIONS

PERMITTEE: NH DEPT OF TRANSPORTATION
C/O TIMOTHY BOODEY
PO BOX 483
CONCORD NH 03302

PROJECT LOCATION NH 114 OVER GORHAM POND BROOK, GOFFSTOWN
TAX MAP #ROW, LOT #ROW

WATERBODY: NH 114 OVER GORHAM POND BROOK

APPROVAL DATE: OCTOBER 04, 2021 **EXPIRATION DATE:** OCTOBER 04, 2026

Based upon review of permit application 2021-00163 in accordance with RSA 482-A and RSA 485-A:17, the New Hampshire Department of Environmental Services (NHDES) hereby issues this Wetlands and Non-Site Specific Permit. To validate this Permit, signatures of the Permittee and the Principal Contractor are required.

PERMIT DESCRIPTION:

Dredge and fill a total of 830 square feet/70 linear feet of perennial stream bed and banks (Gorham Brook) to perform installation of a reinforced concrete invert in the bottom of the existing corrugated metal culvert, installation of a 2-foot deep cut off/curtain wall at both the inlet and outlet, and repair of the existing mortar rubble masonry wing walls. Impacts include 27 square feet/ 5 linear feet of permanent impacts and 803 square feet/65 linear feet of temporary impacts to perennial stream bed and banks to be restored.

THIS PERMIT IS SUBJECT TO THE FOLLOWING PROJECT-SPECIFIC CONDITIONS:

1. In accordance with Env-Wt 307.16, all work shall be done in accordance with the plans for NHDOT NH Project No. 42840, NH 114 Over Gorham Pond Brook, Town of Goffstown, NH dated October 2020, PE stamped on July 16, 2021 as received by the NH Department of Environmental Services (NHDES) on September 14, 2021.
2. In accordance with Env-Wt 527.05(a) In addition to complying with all applicable conditions in Env-Wt 307, the permit shall be contingent on review and approval by the department of final stream diversion and erosion control plans that detail the timing and method of stream flow diversion during construction and show temporary siltation, erosion, and turbidity control measures to be implemented.
3. In accordance with Env-Wt 527.05(b), The contractor responsible for completion of the work shall use techniques described in Env-Wq 1504.06, Env-Wq 1504.16, Env-Wq 1505.02, Env-Wq 1506, and Env-Wq 1508.
4. In accordance with Env-Wt 314.03, (a) The permittee shall notify the department in writing at least one week prior to commencing any work under the permit.
5. In accordance with Env-Wt 307.10(g), the permittee shall specifically coordinate with New Hampshire Fish & Game regarding any in-stream project activities to occur between October 1 and March 31 for avoidance to any fish migration or larval settling area of cold water fish.
6. In accordance with Env-Wt 307.07, all development activities associated with any project shall be conducted in compliance with applicable requirements of RSA 483-B and Env-Wq 1400 during and after construction.

www.des.nh.gov

29 Hazen Drive • PO Box 95 • Concord, NH 03302-0095

NHDES Main Line: (603) 271-3503 • Subsurface Fax: (603) 271-6683 • Wetlands Fax: (603) 271-6588

TDD Access: Relay NH 1 (800) 735-2964

7. In accordance with Env-Wt 307.03(a), no activity shall be conducted in such a way as to cause or contribute to any violation of surface water quality standards specified in RSA 485-A:8 or Env-Wq 1700; ambient groundwater quality standards established under RSA 485-C; limitations on activities in a sanitary protective area established under Env-Dw 302.10 or Env-Dw 305.10; or any provision of RSA 485-A, Env-Wq 1000, RSA 483-B, or Env-Wq 1400 that protects water quality.
8. All work shall be conducted and maintained in such a way as to protect water quality as required by Rule Env-Wt 307.03(a) through (h).
9. In accordance with Env-Wt 307.03(c)(4), water quality control measures shall be capable of minimizing erosion; collecting sediment and suspended and floating materials; and filtering fine sediment.
10. In accordance with Env-Wt 307.03(c)(3), water quality control measures shall be installed prior to start of work and in accordance with the manufacturer's recommended specifications or, if none, the applicable requirements of Env-Wq 1506 or Env-Wq 1508.
11. In accordance with Env-Wt 307.03(c)(5), water quality control measures shall be maintained so as to ensure continued effectiveness in minimizing erosion and retaining sediment on-site during and after construction.
12. In accordance with Env-Wt 307.03(c)(6), water quality control measures shall remain in place until all disturbed surfaces are stabilized to a condition in which soils on the site will not experience accelerated or unnatural erosion by achieving and maintaining a minimum of 85% vegetative cover using an erosion control seed mix, whether applied in a blanket or otherwise, that is certified by its manufacturer as not containing any invasive species; or placing and maintaining a minimum of 3 inches of non-erosive material such as stone.
13. In accordance with Env-Wt 307.03(d), any sediment collected by water quality control measures shall be removed with sufficient frequency to prevent the discharge of sediment; and placed in an upland location in a manner that prevents its erosion into a surface water or wetland.
14. In accordance with Env-Wt 307.03(c)(7), temporary water quality control methods shall be removed upon completion of work when compliance with Env-Wt 307.03(c)(6) is achieved.
15. In accordance with Env-Wt 307.03(h), equipment shall be staged and refueled outside of jurisdictional areas (unless allowed) and in accordance with Env-Wt 307.15.
16. In accordance with Env-Wt 307.05(e), to prevent the use of soil or seed stock containing nuisance or invasive species, the contractor responsible for work shall follow Best Management Practices for the Control of Invasive and Noxious Plant Species (Invasive Plant BMPs).
17. Restoration of all temporary impacts shall meet all of the conditions listed in Rule Env-Wt 307.12(a) through (i).
18. In accordance with Env-Wt 307.12(f), if any temporary impact area that is stabilized with seeding or plantings does not have at least 75% successful establishment of wetlands vegetation after 2 growing seasons, the area shall be replanted or reseeded, as applicable.
19. In accordance with Env-Wt 307.12(i), wetland areas where permanent impacts are not authorized shall be restored to their pre-impact conditions and elevation by replacing the removed soil and vegetation in their pre-construction location and elevation such that post-construction soil layering and vegetation schemes are as close as practicable to pre-construction conditions.
20. In accordance with Env-Wt 307.12(a), within 3 days of final grading or temporary suspension of work in an area that is in or adjacent to surface waters, all exposed soil areas shall be stabilized by seeding and mulching, if during the growing season; or mulching with tackifiers on slopes less than 3:1 or netting and pinning on slopes steeper than 3:1 if not within the growing season.
21. In accordance with Env-Wt 307.12(f), if any temporary impact area that is stabilized with seeding or plantings does not have at least 75% successful establishment of wetlands vegetation after 2 growing seasons, the area shall be replanted or reseeded, as applicable.
22. In accordance with Env-Wt 307.03(g)(1), the person in charge of construction equipment shall inspect such equipment for leaking fuel, oil, and hydraulic fluid each day prior to entering surface waters or wetlands or operating in an area where such fluids could reach groundwater, surface waters, or wetlands.
23. In accordance with Env-Wt 307.03(g)(2), the person in charge of construction equipment shall repair any leaks prior to using the equipment in an area where such fluids could reach groundwater, surface waters, or wetlands.
24. In accordance with Env-Wt 307.03(g)(3) and (4), the person in charge of construction equipment shall maintain oil spill kits and diesel fuel spill kits, as applicable to the type(s) and amount(s) of oil and diesel fuel used, on site so as to be readily accessible at all times during construction; and train each equipment operator in the use of the spill kits.

25. In accordance with Env-Wt 307.03(e), all exposed soils and other fills shall be permanently stabilized within 3 days following final grading.
26. In accordance with Env-Wt 514.05(h), within 60 days of completion of construction, the applicant shall submit a post-construction report that has been prepared by a professional engineer, certified wetland scientist, or qualified professional, as applicable, and contains narrative, exhibits, and photographs, as necessary to report the status of the project area and restored jurisdictional area. The report should summarize any impacts to fish passage post-construction.

THIS PERMIT IS SUBJECT TO THE FOLLOWING GENERAL CONDITIONS:

1. Pursuant to RSA 482-A:12, a copy of this permit shall be posted in a secure manner in a prominent place at the site of the approved project.
2. In accordance with Env-Wt 313.01(a)(5), and as required by RSA 482-A:11, II, work shall not infringe on the property rights or unreasonably affect the value or enjoyment of property of abutting owners.
3. In accordance with Env-Wt 314.01, a standard permit shall be signed by the permittee, and the principal contractor who will build or install the project prior to start of construction, and will not be valid until signed.
4. In accordance with Env-Wt 314.03(a), the permittee shall notify the department in writing at least one week prior to commencing any work under this permit.
5. In accordance with Env-Wt 314.08(a), the permittee shall file a completed notice of completion of work and certificate of compliance with the department within 10 working days of completing the work authorized by this permit.
6. In accordance with Env-Wt 314.06, transfer of this permit to a new owner shall require notification to, and approval of, the NHDES.
7. The permit holder shall ensure that work is done in a way that protects water quality per Env-Wt 307.03; protects fisheries and breeding areas per Env-Wt 307.04; protects against invasive species per Env-Wt 307.05; meets dredging activity conditions in Env-Wt 307.10; and meets filling activity conditions in Env-Wt 307.11.
8. This project has been screened for potential impact to known occurrences of protected species and exemplary natural communities in the immediate area. Since many areas have never been surveyed, or only cursory surveys have been performed, unidentified sensitive species or communities may be present. This permit does not absolve the permittee from due diligence in regard to state, local or federal laws regarding such communities or species. This permit does not authorize in any way the take of threatened or endangered species, as defined by RSA 212-A:2, or of any protected species or exemplary natural communities, as defined in RSA 217-A:3.
9. In accordance with Env-Wt 307.06(a) through (c), no activity shall jeopardize the continued existence of a threatened or endangered species, a species proposed for listing as threatened or endangered, or a designated or proposed critical habitat under the Federal Endangered Species Act, 16 U.S.C. §1531 et seq.; State Endangered Species Conservation Act, RSA 212-A; or New Hampshire Native Plant Protection Act, RSA 217-A.
10. In accordance with Env-Wt 307.02, and in accordance with federal requirements, all work in areas under the jurisdiction of the U.S. Army Corps of Engineers (USACE) shall comply with all conditions of the applicable state general permit.

APPROVED:



Karl D. Benedict
Public Works Supervisor, Wetlands Bureau
Land Resources Management, Water Division

THE SIGNATURES BELOW ARE REQUIRED TO VALIDATE THIS PERMIT (Env-Wt 314.01).

PERMITTEE SIGNATURE (required)

PRINCIPAL CONTRACTOR SIGNATURE (required)