



THE STATE OF NEW HAMPSHIRE
DEPARTMENT OF TRANSPORTATION



William Cass, P.E.
Commissioner

David Rodrigue, P.E.
Assistant Commissioner

Andre Briere, Colonel, USAF (RET)
Deputy Commissioner

March 21, 2024

Mr. Karl Benedict
Public Works Supervisor, Wetlands Bureau
Land Resources Management, Water Division
NH Department of Environmental Services
29 Hazen Drive, PO Box 483
Concord, NH 03302

RE: NHDES File Number: 2023-00858/ NHDOT Project # Jaffrey 16307
Standard Dredge and Fill Wetlands Permit Application (RSA 482-A)
US 202/ NH 124/ NH 137 Intersection Improvements Project, Downtown Jaffrey, NH

This memorandum follows your December 7, 2023, *Request for More Information* (RFMI) regarding the proposed construction of roadway improvements in downtown Jaffrey (“the Project”). Please see our responses to your comments below, as well as the attachments to this letter which provide revised plans and additional information. These responses incorporate NHDES feedback from the meeting on January 3, 2024.


Attachment A includes updated wetland impact plans to account for the updates reflected in the May 2023 RFMI, along with the additional updates requested in this RFMI. With the current impact areas, the wetlands permit application fee is \$5,271.60. Since NHDOT previously paid \$4,989.20, a voucher for the remaining \$282.40 balance is provided with this response (Voucher #: 750726).

Revised Suggested Permit Description: The NHDOT proposes to permanently impact 2,540 sq ft (225 lin ft) within the bed and 1,955 sq ft (316 lin ft) within the banks of the Contoocook River to construct a new bridge with associated riprap stabilization and simulated streambed material, and to fill 4,396 sq ft of palustrine wetlands to construct a new connector road, stormwater infrastructure, and relocated parking. Temporary impacts include 3,504 sq ft (484 lin ft) within the bed and 592 sq ft (164 lin ft) within the banks of the Contoocook River, along with 192 sq ft within a palustrine wetland (Wetland 1) to install proposed erosion controls (i.e., steel sheet pile cofferdams, sandbag cofferdams, silt fence/sock, etc.).

In response to the NHDES technical comments on the application, we offer the following:

Comment 1: Review of TOB jurisdiction was reviewed at 202+40±R over to proposed parking area. NHDES has identified TOB location should be located consistent with flagging and elevations shown throughout the rest of the project area and would be consistent with contour elevations identified per plan. Existing flagging location excludes portions of jurisdictional bank areas.

Revise the TOB location on plans and quantify associated square feet and linear feet of bank areas within this project impact area location. The TOB elevations at Wetland impact areas TH and TC are confirmed and boundary should extend between these points.



Response: The top of bank (TOB) line was revised to extend farther upslope in this area (but not to include Wetland 1), as decided in a meeting with NHDES. Since this line revision was not field delineated by a NH Certified Wetland Scientist, a note was added to the Existing Conditions Plan (Sheet 5 of 19) to clarify that the TOB line in this area was the result of NHDES comments. Due to this line modification, the permanent bank Impact G was expanded, new permanent bank Impacts I and J were added, new temporary bank Impacts TL and TN were added, and a new temporary bed Impact TM was added.

Comment 2: Please quantify all linear feet of impacts along Contocoock River to include bank impact along areas TC and A.

Response: The revised TOB line goes around Wetland 1 (along the previously shown TOB/OHW line) and no impacts were previously proposed below that line. Per recent coordination with NHDES, Impact TC was merged with Impact A, and we added an additional temporary impact parallel to Wetland 1 (labeled as Impact TM on the plans) to be consistent with how temporary impacts were calculated elsewhere for this project (a five-foot buffer off the proposed slope lines). This temporary impact is below the TOB/OHW line and was therefore calculated as temporary riverbed impact in square feet and linear feet. The corresponding NB/PC line on the Erosion Control Plan (Sheet 11 of 19) was also updated to reflect this change.

Comment 3: Please review proposed Impact Areas TC, TA, and TF for confirmation as proposed temporary impacts. Noting activity in the vicinity to include wall removal, grading, and outlet construction. There are no permanent impacts to bank proposed at outlet construction Sta. 200+74 to river outlet or vicinity at the west abutment.


Response: Since the temporary impact areas TC and TA are relatively small, we have merged those areas with permanent Impact A, as requested.

Temporary Impact TF is intended to show some potential workspace within the riverbank that may be required during the retaining wall removal (which is represented with permanent Impact H). Both Impacts H and TF

are associated with the proposed removal of the existing stone retaining wall that retains the backyard of a residential property at 15 River Street (NHDOT Parcel #11) and regrading of this area to even out the topography. This property has been acquired as part of this Project between the Jaffrey War Memorial parcel to the north and the proposed new bridge crossing to the south. This retaining wall is proposed to be removed to allow this area to be regraded to support the bridge abutment installation, eliminate any future maintenance requirements for this wall if it were left in place. The slopes adjacent to the river will be regraded to a 2:1 slope to provide the maximum relatively flat, usable area for potential expansion of the adjacent War Memorial Park use. Refer to the Erosion Control Plan (Sheet 11 of 19) for the proposed grading around the bridge. This area would be stabilized using standard techniques such as loaming, seeding, and erosion control blanket per NHDOT standard specification. Appropriate perimeter controls would be in place until stable.

The last part of this comment relates to the proposed outfall (located at approximately Station 201+10) that originates from a pipe at approximately Station 200+74. This outfall and associated riprap apron are located greater than two feet away from the delineated top of bank line and do not constitute a jurisdictional impact. Additionally, given the limited anticipated flow velocities, there is no design need to extend the riprap all the way to the river. Furthermore, the proposed riprap apron has been sized appropriately to provide outlet protection from erosion at the 10-year design storm in accordance with the NHDOT Drainage Design Manual (2023) and the Federal Highway Administration Hydraulic Engineering Circular No. 14 (HEC-14).

Comment 4: *Please clarify whether rip rap will be extended from the outlet of proposed bioretention basin over slope with outlet to Contoocook River. The extent appears to extend below OHW (and through areas identified as jurisdictional banks per Item 1). Please clarify proposed impact if rip rap, quantify associated impact area, and consider limiting extent to above OHW.*



Response: The northern most highlighted line is a proposed ROW line for the US Route 202 roadway and the southernmost line is a stray construction line that was mistakenly included on the plan set (and has since been removed). The riprap for the spillway will only extend to the area shown with a stone hatch on the plans and will not extend below the OHW. We believe the riprap area shown on the plans is sufficient to account for the flow velocities (less than 2 feet per second at the 50-year design storm). The riprap area for the bridge has already been included in the impact area calculations.

Comment 5: *Please review extent of jurisdictional bank limit along impact area at Blake Street Pipe Sta. 30+41 to River Outlet (between impact areas TC-A). Note this area is identified as above OHW, and below site contour elevation break associated with TOB throughout the site although no jurisdictional impacts are identified adjacent to Contoocook River (ID bank of Contoocook River at consistent elevation with vicinity project determination through impact area A).*

Response: Impact A correctly follows the delineated wetland boundary of Wetland 1. The small break in the wetland along the bank (where a portion of the outlet stone extends) represents a small non-jurisdictional upland inclusion within Wetland 1 adjacent to the riverbank. This upland inclusion was confirmed in the field by Kris Wilkes, NH Certified Wetland Scientist and does not meet the three wetland parameters per the Army Corps Wetland Delineation Manual and Regional Supplement.

Comment 6: *Please provide revised ARM mitigation calculator reflecting updated bank impact areas and excluding the proposed reduction for credit associated with wildlife shelf construction. Calculate square feet*

of impacts for priority resource areas and calculate total linear feet of permanent impact to bed and banks of the Contoocook River.

Response: The revised ARM Fund mitigation payment for this project is \$119,454.51. This accounts for the updated bank areas and removes the previously proposed wildlife shelf credit. The updated mitigation documentation is provided as **Attachment B**.

Comment 7: *Please confirm whether revised plans and RFMI response to the CNBRLAC and Town of Jaffrey project comments have been forwarded to each agency with responses identifying any concerns have been addressed.*

Response: The revised plans and previous RFMI response were not sent to the CNBRLAC and Town of Jaffrey. However, this RFMI response and all corresponding attachments will be sent to them. Refer to the cc list at the end of this letter.

As always, please don't hesitate to call or email if you have any additional questions or concerns.

Sincerely,

Andrew O'Sullivan
Wetlands Program Manager
Room 109 – Tel (603) 271-0556
E-mail – andrew.m.osullivan@dot.nh.gov

Attachments

cc: Tobey Reynolds, NHDOT
Marc Laurin, NHDOT
Chuck Gregory, VHB
Greg Goodrich, VHB
Peter J. Walker, VHB
Town of Jaffrey Conservation Commission
CNBRLAC

Attachment A

**Wetland Impact Plans, dated November 7, 2023
(updated March 6, 2024)
(half-scale)**



STATE OF NEW HAMPSHIRE
DEPARTMENT OF TRANSPORTATION
**WETLANDS IMPACT PLANS
FEDERAL AID PROJECT**

X-(A001)234
N.H. PROJECT NO. 16307
US 202, NH 124, NH 137, STRATTON ROAD

US 202	
AVERAGE DAILY TRAFFIC 20_26	14,200
AVERAGE DAILY TRAFFIC 20_46	18,500
PERCENT OF TRUCKS	2%
DESIGN SPEED	30 MPH
LENGTH OF PROJECT	1295

NH 124 (MAIN STREET / TURNPIKE STREET)	
AVERAGE DAILY TRAFFIC 20_26	7,300
AVERAGE DAILY TRAFFIC 20_46	9,700
PERCENT OF TRUCKS	2%
DESIGN SPEED	30 MPH
LENGTH OF PROJECT	965

NH 137 (RIVER STREET):	
AVERAGE DAILY TRAFFIC 20_26	7,100
AVERAGE DAILY TRAFFIC 20_46	9,300
PERCENT OF TRUCKS	2%
DESIGN SPEED	30 MPH
LENGTH OF PROJECT	385



LOCATION MAP




INDEX OF SHEETS

- 1 FRONT SHEET
- 2-3 STANDARD SYMBOLS SHEETS
- 4 EROSION CONTROL NOTES & STRATEGIES
- 5-6 EXISTING CONDITIONS PLANS
- 7 PIPE OUTLET DETAILS
- 8-9 WETLAND IMPACT PLANS
- 10-16 EROSION CONTROL PLANS
- 17-18 DIVERSION & DEWATERING PLANS
- 19 BRIDGE SECTION

**STA. 102+75
US ROUTE 202 SOUTH
END APPROACH
BEGIN FULL DEPTH
CONSTRUCTION**

**TOWN OF JAFFREY
COUNTY OF CHESHIRE**



**STA. 601+50
STRATTON ROAD
END FULL DEPTH
CONSTRUCTION
BEGIN APPROACH**

FOR CONSTRUCTION AND ALIGNMENT DETAILS
- SEE CONSTRUCTION PLANS

 GREGORY S. GOODRICH No. 12284 PROFESSIONAL ENGINEER	 CHARLES S. GREGORY No. 1383 PROFESSIONAL ENGINEER	 KRISTOPHER P. WILKES No. 288 CERTIFIED WETLAND SCIENTIST
VHB STRUCTURES	VHB HIGHWAY	VHB ENVIRONMENTAL

PERMITTING - LEVEL PLANS
SUBJECT TO CHANGE
NOT FOR CONSTRUCTION
NOVEMBER 7, 2023

NHDOT THE STATE OF NEW HAMPSHIRE DEPARTMENT OF TRANSPORTATION

RECOMMENDED FOR APPROVAL:



_____ DIRECTOR OF PROJECT DEVELOPMENT	_____ DATE
_____ MUNICIPAL HIGHWAYS ENGINEER BUREAU OF PLANNING AND COMMUNITY ASSISTANCE	_____ DATE
_____ APPROVED:	_____ DATE
_____ ASSISTANT COMMISSIONER AND CHIEF ENGINEER	_____ DATE

DRAWING NAME	FEDERAL PROJECT NO.	STATE PROJECT NO.	SHEET NO.	TOTAL SHEETS
16307FSC_We+.dgn	X-(A001)234	16307	1	19


DRAWN BY: _____ CHECKED BY: _____ DATE: _____

SDR PROCESSED NHDOT & VHB DATE 9/2021 DATE 10/2023 DATE 10/2023 DATE
 NEW DESIGN VHB TEAM SHEET CHECKED PJW AS BUILT DETAILS
 REVISIONS AFTER PROPOSAL STATION STATION DATE NUMBER


GENERAL




SHORELAND - WETLAND



FLOODPLAIN / FLOODWAY




ENGINEERING




REVISION DATE	DATE PLOTTED	VHB PROJECT NO.	DGN	STATE PROJECT NO.	SHEET NO.	TOTAL SHEETS
11-21-2014	3/6/2024	52792.00	16307SYM.dgn	16307	2	19

SDR PROCESSED	NHDT & VHB	DATE	9/2021	
	NEW DESIGN	VHB TEAM	DATE	10/2023
	SHEET CHECKED	PJW	DATE	10/2023
	AS BUILT DETAILS		DATE	
REVISIONS AFTER PROPOSAL	STATION			
	STATION			
	DATE			
	NUMBER			


DRAINAGE




BOUNDARIES / RIGHT-OF-WAY




UTILITIES



TRAFFIC SIGNALS / ITS



CONSTRUCTION NOTES



REVISION DATE	DATE PLOTTED	VHB PROJECT NO.	DGN	STATE PROJECT NO.	SHEET NO.	TOTAL SHEETS
9-1-2016	3/6/2024	52792.00	16307SYM.dgn	16307	3	19

EROSION CONTROL NOTES AND STRATEGIES

1. Erosion Control/Stormwater Control Selection, Sequencing and Maintenance
 - 1.1. Comply with RSA 485-A:17 Terrain Alteration.
 - 1.2. Install and maintain all erosion control/stormwater controls in accordance with the New Hampshire Stormwater Management Manual, Volume 3, Erosion and Sediment Controls During Construction, December 2008 (BMP Manual), available from the NH Department of Environmental Services (NHDES).
 - 1.3. Install erosion control/stormwater control measures prior to the start of work and in accordance with the manufacturer's recommendations.
 - 1.4. Select erosion control/stormwater control measures based on the size and nature of the project and physical characteristics of the site, including slope, soil type, vegetative cover, and proximity to jurisdictional areas.
 - 1.5. Install perimeter controls prior to earth disturbing activities.
 - 1.6. Install stormwater treatment ponds and drainage swales before rough grading the site.
 - 1.7. Clean, replace, and augment stormwater control measures and infiltration basins as necessary to prevent sedimentation beyond project limits throughout the project duration.
 - 1.8. Inspect erosion and sediment control measures in accordance with Section 645 of the specifications, weekly, and within 24 hours (during normal work hours), of any storm event greater than 0.25 inches of rain in a 24-hour period.
 - 1.9. Contain stockpiles with temporary perimeter controls. Protect inactive soil stockpiles with soil stabilization measures (temporary erosion control seed mix and mulch, soil binder) or cover them with anchored tarps. If the stockpile is to remain undisturbed for more than 14 days, mulch the stockpile.
 - 1.10. Maintain temporary erosion and stormwater control measures in place until the area has been permanently stabilized.
 - 1.11. An area is considered stable if one of the following has occurred:
 - Base course gravels have been installed in areas to be paved;
 - A minimum of 85% vegetative growth has been established;
 - A minimum of 3" of non-erosive material such as stone or rip-rap has been installed;
 - Temporary slope stabilization has been properly installed (see Table 1).
 - 1.12. Direct runoff to temporary practices until permanent stormwater infrastructure is constructed and stabilized.
 - 1.13. Use temporary mulching, permanent mulching, temporary vegetative cover, and permanent vegetative cover to reduce the need for dust control. Use mechanical sweepers on paved surfaces where necessary to prevent dust buildup. Apply water, or other dust inhibiting agents or tackifiers.
 - 1.14. Plan activities to account for sensitive site conditions
 - Sequence construction to limit the duration and area of exposed soils.
 - Clearly flag areas to be protected in the field and provide construction barrier to prevent trafficking outside of work areas.
 - Protect and maximize existing native vegetation and natural forest buffers between construction activities and sensitive areas.
 - When work is undertaken in a flowing watercourse, implement stream flow diversion methods prior to any excavation or filling activity.
 - 1.15. Utilize storm drain inlet protection to prevent sediment from entering a storm drainage system prior to the permanent stabilization of the contributing disturbed area.
 - 1.16. Use care to ensure that sediments do not enter any existing catch basins during construction. Place temporary inlet protection at inlets in areas of soil disturbance that are subject to sedimentation.
 - 1.17. Construct, stabilize, and maintain temporary and permanent ditches in a manner that will minimize scour. Direct temporary and permanent ditches to drain to sediment basins or stormwater collection areas.
 - 1.18. Supplement channel protection measures with perimeter control measures when ditch lines occur at the bottom of long fill slopes. Install the perimeter controls on the fill slope to minimize the potential for fill slope sediment deposits in the ditch line.
 - 1.19. Divert sediment laden water away from drainage inlet structures to the extent possible.
 - 1.20. Install sediment barriers and sediment traps at drainage inlets to prevent sediment from entering the drainage system.
 - 1.21. Clean catch basins, drainage pipes, and culverts if significant sediment is deposited.
 - 1.22. Construct and stabilize dewatering infiltration basins prior to any excavation that may require dewatering.
 - 1.23. Place and stabilize temporary sediment basins or traps at locations where concentrated flow (channels and pipes) discharge to the surrounding environment from areas of unstabilized earth disturbing activities.
 - 1.24. Stabilize, to appropriate anticipated velocities, conveyance channels or pumping systems needed to convey construction stormwater to basins and discharge locations prior to use.
 - 1.25. Size temporary sediment basins to contain the 2-year, 24 hour storm event.
 - 1.26. Size temporary sediment traps to contain 3,600 cubic feet of storage for each acre of drainage area.
 - 1.27. Construct detention basins to accommodate the 2-year, 24-hour storm event.
2. Construction Planning
 - 2.1. Divert off site runoff or clean water away from the construction activities to reduce the volume that needs to be treated on site.
 - 2.2. Divert storm runoff from upslope drainage areas away from disturbed areas, slopes and around active work areas to a stabilized outlet location.
 - 2.3. Construct impermeable barriers, as necessary, to collect or divert concentrated flows from work or disturbed areas.
 - 2.4. Locate staging areas and stockpiles outside of wetlands jurisdiction.
 - 2.5. Do not store, maintain, or repair mobile heavy equipment in wetlands, unless equipment cannot be practicably removed and secondary containment is provided.
 - 2.6. Provide a water truck to control excessive dust, at the discretion of the Contract Administrator.
3. Site Stabilization
 - 3.1. Stabilize all areas of unstabilized soil as soon as practicable, but no later than 45 days after initial disturbance.
 - 3.2. Limit unstabilized soil to a maximum of 5 acres unless documentation is provided that demonstrates that cuts and fills are such that 5 acres is unreasonable.
 - 3.3. Use erosion control seed mix in all inactive construction areas that will not be permanently seeded within two weeks of disturbance and prior to September 15th of any given year in order to achieve vegetative stabilization prior to the end of the growing season.
 - 3.4. Apply, and reapply as necessary, soil tackifiers in accordance with the manufacturer's specifications to minimize soil and mulch loss until permanent vegetation is established.
 - 3.5. Stabilize basins, ditches and swales prior to directing runoff to them.
 - 3.6. Stabilize roadway and parking areas within 72 hours of achieving finished grade.
 - 3.7. Stabilize cut and fill slopes within 72 hours of achieving finished grade.
 - 3.8. When temporarily stabilizing soils and slopes, utilize the techniques outlined in Table 1.
 - 3.9. Stabilize all areas that can be stabilized prior to opening up new areas to construction activities.
 - 3.10. Utilize Table 1 when selecting temporary soil stabilization measures.
 - 3.11. Divert off-site water through the project in an appropriate manner so as not to disturb the upstream or downstream soils, vegetation or hydrology beyond the permitted area.
 - 3.12. Install and maintain construction exits anywhere traffic leaves a construction site onto a public right-of-way.
 - 3.13. Sweep all construction related debris and soil from the adjacent paved roadways, as necessary.

4. Slope Protection
 - 4.1. Intercept and divert storm runoff from upslope drainage areas away from unprotected and newly established areas and slopes to a stabilized outlet or conveyance.
 - 4.2. Consider how groundwater seepage on cut slopes may impact slope stability and incorporate appropriate measures to minimize erosion.
 - 4.3. Convey storm water down the slope in a stabilized channel or slope drain.
 - 4.4. The outer face of the fill slope should be in a loose, ruffled condition prior to turf establishment.
5. Winter Construction
 - 5.1. To minimize erosion and sedimentation impacts, limit the extent and duration of winter excavation and earthwork activities. The maximum amount of disturbed earth shall not exceed a total of 5 acres from May 1st through November 30th, or exceed one acre during winter months, unless the contractor demonstrates to the Department that the additional area of disturbance is necessary to meet the contractor's Critical Path Method (CPM) schedule, and the contractor has adequate resources available to ensure that environmental requirements will be met.
 - 5.2. Construction performed any time between November 30th and May 1st of any year is considered winter construction. During winter construction:
 - Stabilize all proposed vegetation areas which do not exhibit a minimum of 85% vegetative growth by October 15th, or which are disturbed after October 15th, in accordance with Table 1.
 - Stabilize all ditches or swales which do not exhibit a minimum of 85% vegetative growth by October 15th, or which are disturbed after October 15th, in accordance with Table 1.
 - Protect incomplete road surfaces, where base course gravels have not been installed, and where work has stopped for the season after November 30th, in accordance with Table 1.
 - Unless a winter construction plan has been approved by NHDOT, conduct winter excavation and earthwork such that no more than 1 acre of the project is without stabilization any one time.
6. Wildlife Protection Measures
 - 6.1. Report all observations of threatened and endangered species on the project site to the Department's Bureau of Environment by phone at 603-271-3226 or by email at Bureau16@dot.nh.gov, indicating in the subject line the project name, number, and that a threatened/endangered species was found.
 - 6.2. Photograph the observed species and nearby elements of habitat or areas of land disturbance and provide them to the Department's Bureau of Environment at the above email address.
 - 6.3. In the event that a threatened or endangered species is observed on the project during work, the species shall not be disturbed, handled, or harmed prior to receiving direction from the Bureau of Environment.
 - 6.4. Utilize wildlife friendly erosion control methods when:
 - Erosion control blankets are used,
 - A protected species or habitat is documented,
 - The proposed work is in or adjacent to a priority resource area, and/or when specifically requested by NHB or NHF&G

GUIDANCE ON SELECTING TEMPORARY SOIL STABILIZATION MEASURES
TABLE 1

APPLICATION AREAS	DRY MULCH METHODS				HYDRAULICALLY APPLIED MULCHES ²				ROLLED EROSION CONTROL BLANKETS ³			
	HMT	WC	SG	CB	HM	SMM	BFM	FRM	SNSB	DNSB	DNSCB	DNCB
SLOPES ¹												
STEEPER THAN 2:1	NO	NO	YES	NO	NO	NO	NO	YES	NO	NO	NO	YES
2:1 SLOPE	YES ¹	YES ¹	YES	YES	NO	NO	YES	YES	NO	YES	YES	YES
3:1 SLOPE	YES	YES	YES	YES	NO	YES	YES	YES	YES	YES	YES	NO
4:1 SLOPE	YES	YES	YES	YES	YES	YES	YES	YES	YES	YES	NO	NO
WINTER STABILIZATION	4T/AC	YES	YES	YES	NO	NO	YES	YES	YES	YES	YES	YES
CHANNELS												
LOW FLOW CHANNELS	NO	NO	NO	NO	NO	NO	NO	NO	NO	NO	YES	YES
HIGH FLOW CHANNELS	NO	NO	NO	NO	NO	NO	NO	NO	NO	NO	NO	YES


ABBREV.	STABILIZATION MEASURE	ABBREV.	STABILIZATION MEASURE	ABBREV.	STABILIZATION MEASURE
HMT	HAY MULCH & TACK	HM	HYDRAULIC MULCH	SNSB	SINGLE NET STRAW BLANKET
WC	WOOD CHIPS	SMM	STABILIZED MULCH MATRIX	DNSB	DOUBLE NET STRAW BLANKET
SG	STUMP GRINDINGS	BFM	BONDED FIBER MATRIX	DNSCB	2 NET STRAW-COCONUT BLANKET
CB	COMPOST BLANKET	FRM	FIBER REINFORCED MEDIUM	DNCB	2 NET COCONUT BLANKET

NOTES:

1. All slope stabilization options assume a slope length ≤ 10 times the horizontal distance component of the slope, in feet.
2. Do not apply products containing polyacrylamide (PAM) directly to, or within 100 feet of any surface water without NHDES approval.
3. Install all methods in Table 1 per the manufacturer's recommendation for time of year and steepness of slope.



SDR PROCESSED	NHDOT & VHB	DATE	9/2021
	VHB TEAM	DATE	10/2023
	PJW	DATE	10/2023
AS BUILT DETAILS			



REVISIONS AFTER PROPOSAL	STATION	DESCRIPTION

NUMBER	DATE	STATION	DESCRIPTION

- NOTES**
- VHB SENIOR ENVIRONMENTAL SCIENTIST, KRISTOPHER WILKES (NH CWS #288), DELINEATED JURISDICTIONAL WETLANDS AND SURFACE WATERS WITHIN AND ADJACENT TO THE PROPOSED LIMITS DISTURBANCE ON OCTOBER 7, 2021.
 - WETLAND DELINEATION WAS PERFORMED IN ACCORDANCE WITH THE PROCEDURES AND STANDARDS OUTLINED IN THE REGIONAL SUPPLEMENT TO THE U.S. ARMY CORPS OF ENGINEERS WETLAND DELINEATION MANUAL: NORTHCENTRAL AND NORTHEAST REGION, VERSION 2.0 (JANUARY 2012).
 - WETLAND DELINEATION ALSO RELIED UPON THE FIELD INDICATORS FOR IDENTIFYING HYDRIC SOILS IN THE UNITED STATES, VERSION 8.2, PUBLISHED BY THE NATURAL RESOURCE CONSERVATION SERVICE AND THE FIELD INDICATORS FOR IDENTIFYING HYDRIC SOILS IN NEW ENGLAND, VERSION 4.0, PUBLISHED BY THE NEW ENGLAND INTERSTATE WATER POLLUTION CONTROL COMMISSION.
 - DOMINANT WETLAND VEGETATION WAS ASSESSED USING THE NORTHCENTRAL AND NORTHEAST REGION WETLAND PLANT LIST PUBLISHED BY THE U.S. ARMY CORPS OF ENGINEERS.
 - WETLANDS AND SURFACE WATERS WERE CLASSIFIED USING THE USFWS METHODOLOGY CLASSIFICATION OF WETLANDS AND DEEPWATER HABITATS OF THE UNITED STATES (COWARDIN ET AL., 1979, REVISED 1985).
 - STREAM TOP-OF-BANK DELINEATION WAS PERFORMED IN ACCORDANCE WITH ENV-WT 102.15 AND THE ORDINARY HIGH-WATER ELEVATION WAS SET AT 1005.9 FEET NGVD29.


WETLAND CLASSIFICATION CODES

PEM1E	PALUSTRINE, EMERGENT, PERSISTENT, SEASONALLY FLOODED/SATURATED
PSS1E	PALUSTRINE, SCRUB-SHRUB, BROAD-LEAVED DECIDUOUS, SEASONALLY FLOODED/SATURATED
R2UB3h	RIVERINE, LOWER PERENNIAL, UNCONSOLIDATED BOTTOM, MUD, DIKED/IMPOUNDED

THE TOB LINE IN THIS AREA WAS REVISED PER NHDES COMMENTS AND WAS NOT FIELD DELINEATED BY A NH CERTIFIED WETLAND SCIENTIST.



STATE OF NEW HAMPSHIRE JAFFREY			
DEPARTMENT OF TRANSPORTATION • BUREAU OF HIGHWAY DESIGN			
EXISTING CONDITIONS PLANS			
MODEL	DATE PLOTTED	VHB PROJECT NO.	DGN
EXCONDO1	3/6/2024	52792.00	16307Ex_Cond.dgn
STATE PROJECT NO.	SHEET NO.	TOTAL SHEETS	
16307	5	19	



SDR PROCESSED NEW DESIGN SHEET CHECKED AS BUILT DETAILS	NHDT & VHB	DATE	9/2021
	VHB TEAM	DATE	10/2023
	PJW	DATE	10/2023
REVISIONS AFTER PROPOSAL		STATION	DESCRIPTION
NUMBER		DATE	
STATION		DATE	

MATCH TO SHEET EXCONDOI

MATCH TO SHEET EXCONDOI

STATE OF NEW HAMPSHIRE
JAFFREY
DEPARTMENT OF TRANSPORTATION • BUREAU OF HIGHWAY DESIGN

EXISTING CONDITIONS PLANS




MODEL	DATE PLOTTED	VHB PROJECT NO.	DGN	STATE PROJECT NO.	SHEET NO.	TOTAL SHEETS
EXCONDOI	3/6/2024	52792.00	16307Ex_Cond.dgn	16307	6	19


SDR PROCESSED	NHDDOT & VHB	DATE	9/2021
NEW DESIGN	VHB TEAM	DATE	10/2023
SHEET CHECKED	PJW	DATE	10/2023
AS BUILT DETAILS		DATE	

REVISIONS AFTER PROPOSAL	DESCRIPTION

NUMBER	DATE	STATION	STATION



BLAKE STREET PIPE AT STA. 30+41 TO RIVER OUTLET
NOT TO SCALE




US ROUTE 202 CONNECTOR PIPE AT STA. 200+74 TO RIVER OUTLET
NOT TO SCALE



STATE OF NEW HAMPSHIRE JAFFREY					
DEPARTMENT OF TRANSPORTATION • BUREAU OF HIGHWAY DESIGN					
PIPE OUTLET DETAILS					
DATE PLOTTED	VHB PROJECT NO.	DGN	STATE PROJECT NO.	SHEET NO.	TOTAL SHEETS
3/6/2024	52792.00	14307Wet_Detail.dgn	16307	7	19

SDR PROCESSED	NHDOT & VHB	DATE	9/2021
NEW DESIGN	VHB TEAM	DATE	10/2023
SHEET CHECKED	PJW	DATE	10/2023
AS BUILT DETAILS			



WETLAND CLASSIFICATION CODES	
PEM1E	PALUSTRINE, EMERGENT, PERSISTENT, SEASONALLY FLOODED/SATURATED
PSS1E	PALUSTRINE, SCRUB-SHRUB, BROAD-LEAVED DECIDUOUS, SEASONALLY FLOODED/SATURATED
R2UB3h	RIVERINE, LOWER PERENNIAL, UNCONSOLIDATED BOTTOM, MUD, DIKED/IMPOUNDED

LEGEND	
#	WETLAND DESIGNATION NUMBER
#	WETLAND IMPACT LOCATION
TYPE OF WETLAND IMPACT	SHADING/HATCHING
NEW HAMPSHIRE WETLANDS BUREAU (PERMANENT NON-WETLAND)	[Diagonal Hatching]
NEW HAMPSHIRE WETLANDS BUREAU & ARMY CORP OF ENGINEERS (PERMANENT WETLAND)	[Solid Grey]
TEMPORARY IMPACTS (NON-WETLAND)	[Cross-hatch]
TEMPORARY IMPACTS (WETLAND)	[Dotted]

WETLAND IMPACT SUMMARY

WETLAND IDENTIFICATION	WETLAND CLASSIFICATION	WETLAND DESIGNATION	AREA IMPACTS									
			PERMANENT				TEMPORARY					
			N.H.W.B. (NON-WETLAND) BANK		N.H.W.B. & A.C.O.E. (WETLAND) BED		PALUSTRINE (NON-WETLAND)		(WETLAND)		PALUSTRINE WETLAND	
SF	LF	SF	LF	SF	LF	SF	LF	SF				
A	PSS1E	1						1086				
B	PEM1E	1						2093				
C	PEM1E	2						1217				
D	BANK	S-1	762	107								
E	R2UB3h	S-1			1143	110						
F	R2UB3h	S-1			1397	115						
G	BANK	S-1	1035	123								
H	BANK	S-1	90	57								
I	BANK	S-1	54	20								
J	BANK	S-1	14	9								
TA	PSS1E	1										0
TB	PEM1E	1										192
TC	PSS1E	1										0
TD	BANK	S-1					46	5				
TE	R2UB3h	S-1							663	117		
TF	BANK	S-1					266	104			732	125
TG	R2UB3h	S-1										
TH	BANK	S-1					36	5				
TL	BANK	S-1					207	45				
TM	R2UB3h	S-1							132	42		
TN	BANK	S-1					37	5				

STATE OF NEW HAMPSHIRE
 JAFFREY
 DEPARTMENT OF TRANSPORTATION • BUREAU OF HIGHWAY DESIGN

WETLAND IMPACT PLANS




MODEL	DATE PLOTTED	VHB PROJECT NO.	DGN	STATE PROJECT NO.	SHEET NO.	TOTAL SHEETS
WET01	3/6/2024	52792.00	16307Wet_Plans.dgn	16307	8	19

SDR PROCESSED	NHDOT & VHB	DATE	9/2021
NEW DESIGN	VHB TEAM	DATE	10/2023
SHEET CHECKED	PJW	DATE	10/2023
AS BUILT DETAILS		DATE	

REVISIONS AFTER PROPOSAL	DESCRIPTION
STATION	
STATION	
DATE	
NUMBER	

EROSION CONTROL PLAN LEGEND

- PC** PERIMETER CONTROL
 - SILT FENCE
 - EROSION CONTROL MIX BERM
 - EROSION CONTROL MIX SOX
 - TURBIDITY CURTAIN
 - SHEET PILE
 - COFFER DAM
- NB/PC** NATURAL BUFFER/PERIMETER CONTROL
 - SILT FENCE
 - EROSION CONTROL MIX BERM
 - EROSION CONTROL MIX SOX
 - TURBIDITY CURTAIN
 - SHEET PILE
 - COFFER DAM
- CP** CHANNEL PROTECTION
 - STONE CHECK DAMS
 - STRAW WATTLES
 - CHANNEL MATTING
 - CLASS D EROSION STONE
 - CLASS C STONE
- CWB** CLEAN WATER BYPASS
 - PUMP THROUGH PIPE
 - DRAIN THROUGH PIPE OR CHANNEL
- URS** UNIMPACTED RIVERINE SURFACE WATERS OF THE STATE
- ROA** ROUTINE ROADWAY QUALIFYING ACTIVITY
- SD** STREAM DIVERSION




MODEL	DATE PLOTTED	VHB PROJECT NO.	DGN	STATE PROJECT NO.	SHEET NO.	TOTAL SHEETS
ERO01	3/6/2024	52792.00	16307Ero_Plans.dgn	16307	10	19

STATE OF NEW HAMPSHIRE
 JAFFREY
 DEPARTMENT OF TRANSPORTATION • BUREAU OF HIGHWAY DESIGN
EROSION CONTROL PLANS

SDR PROCESSED	NHDDOT & VHB	DATE	9/2021
NEW DESIGN	VHB TEAM	DATE	10/2023
SHEET CHECKED	PJW	DATE	10/2023
AS BUILT DETAILS		DATE	

REVISIONS AFTER PROPOSAL	DESCRIPTION
STATION	
STATION	
DATE	
NUMBER	



**STA. 30+75
BLAKE STREET
END APPROACH
BEGIN FULL DEPTH
CONSTRUCTION**


**STA. 30+25
BLAKE STREET
LIMIT OF WORK**
MONADNKG
PROPERTIES
LLC

STATE OF NEW HAMPSHIRE
JAFFREY
DEPARTMENT OF TRANSPORTATION • BUREAU OF HIGHWAY DESIGN


EROSION CONTROL PLANS



MODEL	DATE PLOTTED	VHB PROJECT NO.	DGN	STATE PROJECT NO.	SHEET NO.	TOTAL SHEETS
ERO02	3/6/2024	52792.00	16307Ero_Plans.dgn	16307	11	19



SDR PROCESSED	REVISIONS AFTER PROPOSAL	STATION	DESCRIPTION
	NEW DESIGN	DATE	DATE
	SHEET CHECKED	DATE	DATE
AS BUILT DETAILS	DATE	DATE	DATE




STATE OF NEW HAMPSHIRE
 JAFFREY
 DEPARTMENT OF TRANSPORTATION • BUREAU OF HIGHWAY DESIGN

EROSION CONTROL PLANS

MODEL	DATE PLOTTED	VHB PROJECT NO.	DGN	STATE PROJECT NO.	SHEET NO.	TOTAL SHEETS
ERO03	3/6/2024	52792.00	16307Ero_Plans.dgn	16307	12	19

SDR PROCESSED	NHDDOT & VHB	DATE	9/2021
NEW DESIGN	VHB TEAM	DATE	10/2023
SHEET CHECKED	PJW	DATE	10/2023
AS BUILT DETAILS		DATE	

REVISIONS AFTER PROPOSAL	STATION	DATE	DESCRIPTION



STATE OF NEW HAMPSHIRE
 JAFFREY
 DEPARTMENT OF TRANSPORTATION • BUREAU OF HIGHWAY DESIGN



EROSION CONTROL PLANS



MODEL	DATE PLOTTED	VHB PROJECT NO.	DGN	STATE PROJECT NO.	SHEET NO.	TOTAL SHEETS
ER004	3/6/2024	52792.00	16307Ero_Plans.dgn	16307	13	19

SDR PROCESSED	NHDDOT & VHB	DATE	9/2021
NEW DESIGN	VHB TEAM	DATE	10/2023
SHEET CHECKED	PJW	DATE	10/2023
AS BUILT DETAILS		DATE	

REVISIONS AFTER PROPOSAL	DESCRIPTION
STATION	
DATE	
NUMBER	



STATE OF NEW HAMPSHIRE JAFFREY						
DEPARTMENT OF TRANSPORTATION • BUREAU OF HIGHWAY DESIGN						
EROSION CONTROL PLANS						
MODEL	DATE PLOTTED	VHB PROJECT NO.	DGN	STATE PROJECT NO.	SHEET NO.	TOTAL SHEETS
ERO05	3/6/2024	52792.00	16307Ero_Plans.dgn	16307	14	19

SDR PROCESSED	NHDDOT & VHB	DATE	9/2021
NEW DESIGN	VHB TEAM	DATE	10/2023
SHEET CHECKED	PJW	DATE	10/2023
AS BUILT DETAILS		DATE	


REVISIONS AFTER PROPOSAL	DESCRIPTION
STATION	
STATION	
DATE	
NUMBER	



STATE OF NEW HAMPSHIRE						
JAFFREY						
DEPARTMENT OF TRANSPORTATION • BUREAU OF HIGHWAY DESIGN						
EROSION CONTROL PLANS						
MODEL	DATE PLOTTED	VHB PROJECT NO.	DGN	STATE PROJECT NO.	SHEET NO.	TOTAL SHEETS
ERO07	3/6/2024	52792.00	16307Ero_Plans.dgn	16307	16	19

SDR PROCESSED		NH DOT & VHB		DATE	9/2021
NEW DESIGN		VHB TEAM		DATE	10/2023
SHEET CHECKED		P/JW		DATE	10/2023
AS BUILT DETAILS				DATE	

REVISIONS AFTER PROPOSAL	DESCRIPTION
STATION	
STATION	
DATE	
NUMBER	



COFFERDAM AND WATER DIVERSION NOTES

1. THIS WATER DIVERSION PLAN IS PROVIDED FOR GENERAL INFORMATION ONLY. THE CONTRACTOR SHALL MODIFY AS NECESSARY TO ACHIEVE REQUIRED WATER HANDLING DURING CONSTRUCTION OF THE BRIDGE. THE FINAL DIVERSION PLAN IS SUBJECT TO REVIEW AND APPROVAL BY THE ENGINEER.
2. THE FINAL WATER DIVERSION SHALL BE DESIGNED BY A PROFESSIONAL ENGINEER LICENSED IN THE STATE OF NEW HAMPSHIRE. THE CONTRACTOR SHALL SUBMIT STAMPED WORKING DRAWINGS SHOWING WATER DIVERSION STRUCTURE LOCATION, COFFERDAMS, CONSTRUCTION METHOD AND SEQUENCE, AND DEWATERING METHOD, FOR REVIEW AND DOCUMENTATION IN ACCORDANCE WITH SECTION 105.02. ALL COSTS FOR THE WATER DIVERSION STRUCTURE, DEWATERING, AND APPURTENANCES SHALL BE INCLUDED IN ITEM 503.103, WATER DIVERSION.
3. WATER DIVERSION AND CONSTRUCTION ACTIVITIES IN CHANNEL SHALL BE SCHEDULED FOR LOW FLOW. IF THERE IS FLOWING WATER DURING CONSTRUCTION THE FLOW SHALL BE DIVERTED AROUND THE WORK SITE IN A STABLE MANNER USING METHODS APPROVED BY THE ENGINEER. SUCH METHODS WOULD LIKELY INCLUDE USE OF A COFFERDAMS AND PUMPS.
4. UPON COMPLETION OF THE FOOTING CONSTRUCTION AND RIPRAP PLACEMENT, THE COFFERDAMS SHALL BE REMOVED AND WATER SHALL BE ROUTED THROUGH THE BRIDGE. COMPLETE REMOVAL IMMEDIATELY AFTER CONSTRUCTION, WITHIN ONE DAY WHENEVER POSSIBLE.
5. DEWATERING OF THE WORK AREA SHALL BE CONDUCTED IN A MANNER THAT PREVENTS DISCHARGE OF TURBID WATER TO THE CONTOOCOOCK RIVER AND ADJACENT WETLANDS. TURBID DISCHARGE SHALL BE DIRECTED TO A FILTER BAG (AND/OR A STABILIZED ABOVE-GRADE, TEMPORARY SEDIMENT BASIN/TRAP) LOCATED IN ONSITE UPLANDS. ALL COSTS SHALL BE INCLUDED IN ITEM 503.103.

CONSTRUCTION NOTES

1. RIPRAP WILL BE INSTALLED DURING THE DAM DRAWDOWN AND SHALL BE COORDINATED WITH THE DAM OWNER AND NH FISH AND GAME.
2. WATER DIVERSION AND FOUNDATION DEWATERING IS ANTICIPATED FOR THIS PROJECT. THE WORK SHALL BE PERFORMED DURING LOW-FLOW PERIODS. THE CONTRACTOR SHALL SELECT A DEWATERING METHOD THAT LOWERS GROUNDWATER AT LEAST 2 FEET BELOW EXCAVATION SUBGRADE.
3. ALL UNSUITABLE FILLS, ORGANICS, AND ANY DEBRIS SHALL BE COMPLETELY REMOVED BENEATH PROPOSED FOUNDATIONS AS DETAILED IN THE PLANS. THE EXTENT OF REMOVAL SHALL BE 1-FOOT Laterally FOR EVERY 1-FOOT OF EXCAVATION OUTSIDE THE PERIMETER OF ALL FOOTINGS.
4. CONTROL OF WATER WITHIN THE EXCAVATION SHALL BE CONDUCTED IN SUCH A MANNER AS TO PREVENT DISTURBANCE OF THE BEARING SOIL. WELL POINTS, SUMPS OR OTHER PUMPING AREAS SHALL BE LOCATED OUTSIDE THE FOOTING LIMITS AND FILTERED TO PREVENT PUMPING OF THE SOIL MATERIALS BELOW THE EXCAVATION SUBGRADE. INCLUDED IN ITEM 503.101 - WATER DIVERSION STRUCTURE.
5. ALL WORK SHALL BE PERFORMED IN ACCORDANCE WITH THE WETLAND PERMIT ISSUED BY NHDES SPECIFIC TO THE PROJECT.

GENERAL PLAN


SCALE: 1" = 10'



STATE OF NEW HAMPSHIRE						
JAFFREY						
DEPARTMENT OF TRANSPORTATION • BUREAU OF HIGHWAY DESIGN						
DIVERSION AND DEWATERING PLAN (1 OF 2)						
MODEL	DATE PLOTTED	VHB PROJECT NO.	DGN	STATE PROJECT NO.	SHEET NO.	TOTAL SHEETS
Default	3/6/2024	52792.00	16307_div1	16307	17	19

SDR PROCESSED	NHDDOT & VHB	DATE	9/2021
NEW DESIGN	VHB TEAM	DATE	10/2022
SHEET CHECKED	BAM	DATE	3/6/2024
AS BUILT DETAILS		DATE	



REVISIONS AFTER PROPOSAL	STATION	DESCRIPTION



GENERAL PLAN
SCALE: 1" = 10'


- NOTE**
- DAM DRAWDOWN IS REQUIRED TO CONDUCT REPAIRS ON BRIDGE NOS. 154/084 AND 155/084. DRAWDOWN SHALL BE COORDINATED WITH DAM OWNER AND NH FISH AND GAME.
 - SEE NOTES ON DIVERSION AND DEWATERING PLAN (1 OF 2) FOR COFFERDAM AND WATER DIVERSION NOTES 1 THRU 3.

STATE OF NEW HAMPSHIRE JAFFREY						
DEPARTMENT OF TRANSPORTATION • BUREAU OF HIGHWAY DESIGN						
DIVERSION AND DEWATERING PLAN (2 OF 2)						
MODEL	DATE PLOTTED	VHB PROJECT NO.	DGN	STATE PROJECT NO.	SHEET NO.	TOTAL SHEETS
diver plan 2	3/6/2024	52792.00	16307_div2.dgn	16307	18	19



SDR PROCESSED	NHDDOT & VHB	DATE	9/2021
NEW DESIGN	VHB TEAM	DATE	10/2023
SHEET CHECKED	PJW	DATE	10/2023
AS BUILT DETAILS		DATE	

REVISIONS AFTER PROPOSAL	DESCRIPTION
STATION	
STATION	
DATE	
NUMBER	



BRIDGE SECTION
SCALE: 1" = 5'



STATE OF NEW HAMPSHIRE
JAFFREY
DEPARTMENT OF TRANSPORTATION • BUREAU OF HIGHWAY DESIGN

BRIDGE SECTION

MODEL	DATE PLOTTED	VHB PROJECT NO.	DGN	STATE PROJECT NO.	SHEET NO.	TOTAL SHEETS
Default	3/6/2024	52792.00	16307_div3	16307	19	19

Attachment B

Updated Mitigation Documentation

US 202 / NH 124 / NH 137 Intersection Improvements Project - Jaffrey, NH
 Updated ARM Fund Mitigation Payment Justification (per the Dec 2023 RFMI Comments)

PERMANENT WETLAND IMPACT SUMMARY										
WETLAND IDENTIFICATION	WETLAND CLASSIFICATION	WETLAND DESIGNATION	PERMANENT					Subject to Mitigation?	Impact Description	
			N.H.W.B. (NON-WETLAND) BANK		N.H.W.B. & A.C.O.E. (WETLAND) BED		PALUSTRINE WETLAND			
			SF	LF	SF	LF	SF			
A	PSS1E	1						1086	Yes, Wetland 1 is a PRA.	Wetland 1 (PSS area)
B	PEM1E	1						2093	Yes, Wetland 1 is a PRA.	Wetland 1 (PEM area)
C	PEM1E	2						1217	No, Wetland 2 is not a PRA and total non-PRA wetland impacts are under 10,000 sq. ft.	Wetland 2 (entire area)
D	BANK	S-1	762	107					Yes, non-compliant bridge.	Left bank under new bridge
E	R2UB3h	S-1			1143	110			Yes, non-compliant bridge.	Left bed under new bridge
F	R2UB3h	S-1			1397	115			Yes, non-compliant bridge.	Right bed under new bridge
G	BANK	S-1	1035	123					Yes, non-compliant bridge.	Right bank under new bridge
H	BANK	S-1	90	57					No, grading associated with retaining wall removal.	Left bank near retaining wall removal
I	BANK	S-1	54	20					No, grading associated with parking area.	Right bank near parking area/Wetland 1.
J	BANK	S-1	14	9					No, grading associated with parking area.	Right bank near parking area/Wetland 1.
TOTALS			1955	316	2540	225		4396		

KEY
Subject to Mitigation (Stream Calculator)
Subject to Mitigation (Wetlands Calculator)
Not included in stream calculator to not double count the bed impacts.
<i>#s that changed from the May 2023 RFMI Response</i>

ARM Fund Calculations (Dec 2023 RFMI Revisions)			
Wetlands Calculator	3,179	SF	\$14,344.05
Stream Calculator	345	LF	\$105,110.46
TOTAL PAYMENT			\$119,454.51

US 202 / NH 124 / NH 137 Intersection Improvements

Project Jaffrey, NH

Mitigation Calculation - Wetland Impacts

2022 VALUES

TOWN	LAND VALUE	NHDES AQUATIC RESOURCE MITIGATION FUND WETLAND PAYMENT CALCULATION **INSERT AMOUNTS IN YELLOW CELLS**	
Acworth	2015		
Albany	1166		
Alexandria	3283		
Allenstown	11545	1 Convert square feet of impact to acres:	
Alstead	3107	INSERT SQ FT OF	Square feet of impac 3179.00
Alton	28465		43560.00
Amherst	33150	Acres of impact =	0.0730
Andover	5187		
Antrim	5186		
Ashland	17888	2 Determine acreage of wetland construction:	
Atkinson	53267	Forested wetlands:	0.1095
Auburn	25811	Tidal wetlands:	0.2189
Barnstead	10183	All other areas:	0.1095
Barrington	14071		
Bartlett	10785		
Bath	2148	3 Wetland construction cost:	
Bean's Grant	494	Forested wetlands:	\$11,215.66
Bean's Purchase	494	Tidal Wetlands:	\$22,431.31
Bedford	53267	All other areas:	\$11,215.66
Belmont	16815		
Bennington	5777		
Benton	494	4 Land acquisition cost (See land value table):	
Berlin	2091	INSERT LAND VALUE FROM TABLE WHICH APPEARS TO THE LEFT. (Insert the amount do not copy and paste.)	Town land value: 6739
Bethlehem	1170		Forested wetlands: \$737.72
Boscawen	8475		Tidal wetlands: \$1,475.43
Bow	22793		All other areas: \$737.72
Bradford	5543		
Brentwood	25013	5 Construction + land costs:	
Bridgewater	21888	Forested wetland:	\$11,953.37
Bristol	19371	Tidal wetlands:	\$23,906.75
Brookfield	3208	All other areas:	\$11,953.37
Brookline	24118		
Cambridge	494	6 NHDES Administrative cost:	
Campton	6327	Forested wetlands:	\$2,390.67
Canaan	5832	Tidal wetlands:	\$4,781.35
Candia	13335	All other areas:	\$2,390.67
Canterbury	4856		
Carroll	4102	***** TOTAL ARM PAYMENT*****	
Center Harbor	43396	Forested wetlands:	\$14,344.05
Chandler's Purchase	494	Tidal wetlands:	\$28,688.09
Charlestown	3287	All other areas:	\$14,344.05
Chatham	742		
Chester	16676		
Chesterfield	9817		
Chichester	10581		
Claremont	5788		
Clarksville	681		
Colebrook	1771		
Columbia	684		
Concord	37684		
Conway	17622		
Cornish	2954		
Crawford's Purchase	494		
Croydon	1878		
Cutt's Grant	494		
Dalton	1912		
Danbury	2798		
Danville	25564		
Deerfield	9596		
Deering	6106		
Derry	53267		
Dix's Grant	494		
Diville	494		
Dorchester	869		
Dover	53267		
Dublin	6403		
Dummer	494		
Dunbarton	7038		
Durham	35249		
East Kingston	26497		
Easton	1943		
Eaton	3515		
Effingham	4109		
Ellsworth	655		
Enfield	12084		
Epping	22559		
Epsom	10218		
Errol	1110		
Erving's Location	494		
Exeter	53267		
Farmington	9882		
Fitzwilliam	4939		
Francestown	5172		
Franconia	4017		
Franklin	15980		
Freedom	16133		
Fremont	18506		
Gilford	30949		
Gilmanton	7638		
Gilsum	2184		
Goffstown	38305		
Gorham	3104		
Goshen	2880		



US 202 / NH 124 / NH 137 Intersection Improvements Project

Jaffrey, NH

Mitigation Calculation - Stream Impacts

NHDES AQUATIC RESOURCE MITIGATION FUND STREAM PAYMENT CALCULATION		
INSERT LINEAR FEET OF IMPACT on BOTH BANKS AND CHANNEL	Right Bank	115.00
	Left Bank	107.0000
	Channel	123.0000
	TOTAL IMPACT	345.0000
	Stream Impact Cost:	\$87,592.05
	NHDES Administrative cost:	
		\$17,518.41
***** TOTAL ARM FUND STREAM PAYMENT*****		
		\$105,110.46

