
STANDARD PLANS for ROAD CONSTRUCTION



STATE OF NEW HAMPSHIRE DEPARTMENT OF TRANSPORTATION


April 1, 2023

HIGHWAY STANDARD PLANS

| | III GII WA I BIANDAND I LAND |
|----------|----------------------------------------------------------------------|
| STANDARD | DECORDEDA |
| NO. | DESCRIPTION |
| 1,0, | |
| CR-1 | GRANITE CURB DETAILS |
| CR-2 | CURB DETAILS |
| DL -1 | ROADSIDE DELINEATION |
| DL-2 | INTERCHANGE DELINEATION |
| DL -3 | MILLED RUMBLE STRIPS (SHOULDERS) |
| DL -4 | MILLED RUMBLE STRIPS (SHOULDERS) |
| DL -5 | MILLED RUMBLE STRIPS (SHOULDERS) |
| DL -6 | MILLED RUMBLE STRIPS (CENTERLINE) |
| DL -7 | MILLED RUMBLE STRIPS (CENTERLINE) |
| DL-8 | MILLED RUMBLE STRIPS (CENTERLINE) |
| DP-1 | DRAINAGE PIPE DETAILS |
| DR-1 | GRATE AND FRAME DETAILS |
| DR-2 | D.I., MANHOLE COVER AND PAVEMENT DEPRESSION DETAILS |
| DR-3 | PRECAST CONCRETE MEDIAN BARRIER DRAINAGE DETAILS |
| DR-4 | UNDERDRAIN FLUSHING BASIN AND POLYETHYLENE LINER DETAILS |
| DR-5 | PRECAST REINFORCED CONCRETE C.B., D.I. AND M.H. |
| ES-1 | END SECTIONS FOR CORRUGATED STEEL AND REINFORCED CONCRETE PIPES |
| EW-1 | EARTHWORK - MUCK EXCAVATION |
| FN-1 | WOVEN WIRE FENCE |
| FN-2 | CHAIN LINK FENCE |
| GR-1 | BEAM GUARDRAIL STANDARD SECTION-WOOD POSTS AND HARDWARE DETAILS |
| GR-2 | BEAM GUARDRAIL STANDARD SECTION-STEEL POSTS AND HARDWARE DETAILS |
| GR-3 | PREFERRED PLATFORM FOR ENERGY ABSORBING GUARDRAIL TERMINAL (EAGRT) |
| GR-4 | ALTERNATIVE PLATFORM FOR ENERGY ABSORBING GUARDRAIL TERMINAL (EAGRT) |
| GR-5 | BEAM GUARDRAIL TERMINAL SECTION TYPE E-2 |
| GR-6 | BEAM GUARDRAIL TERMINAL SECTION TYPE E-2 HARDWARE DETAILS |
| GR-7 | BEAM GUARDRAIL TERMINAL SECTION TYPE E-2 MODIFIED 30 |
| GR-8 | BEAM GUARDRAIL TERMINAL SECTION TYPE E-2 MODIFIED 40 |
| GR-9 | BEAM GUARDRAIL TERMINAL SECTION TYPE E-2 MODIFIED 45 |
| GR-10 | BEAM GUARDRAIL TERMINAL UNIT TYPE G-2 |
| GR-11 | BEAM GUARDRAIL THRIE BEAM DOUBLE FACED (WOOD POSTS) |
| GR-12 | BEAM GUARDRAIL THRIE BEAM DOUBLE FACED (STEEL POSTS) |
| GR-13 | BEAM GUARDRAIL THRIE BEAM SINGLE FACED (WOOD POSTS) |
| GR-14 | BEAM GUARDRAIL THRIE BEAM SINGLE FACED (STEEL POSTS) |
| GR-15 | PRECAST CONCRETE BARRIER 42" F-SHAPE (DOUBLE-FACED) |
| GR-16 | TRANSITION F-SHAPE BARRIER |
| GR-17 | TRANSITION F-SHAPE BARRIER AND GUARDRAIL (WOOD POSTS) |
| GR-18 | TRANSITION F-SHAPE BARRIER AND GUARDRAIL (STEEL POSTS) |
| GR-19 | SINGLE SLOPE BARRIER |
| GR-20 | TRANSITION SINGLE SLOPE CONCRETE BARRIER, PRECAST |
| GR-21 | TRANSITION SINGLE SLOPE CONCRETE BARRIER AND GUARDRAIL (WOOD POSTS) |
| GR-22 | TRANSITION SINGLE SLOPE CONCRETE BARRIER AND GUARDRAIL (STEEL POSTS) |
| GR-23 | PORTABLE CONCRETE BARRIER 10 FOOT |
| HR-1 | HANDRAIL DETAILS |
| HR-2 | CONCRETE BOUND AND STEPS |
| HW-1 | HEADWALL DETAILS |
| HW-2 | HEADWALL DETAILS (45° WINGS) |
| HW-3 | HEADWALL DETAILS (2 PIPES 45° WINGS) |
| MB-1 | MAILBOX DETAILS |
| PL-1 | PLANTING DETAILS |
| PL-2 | PLANTING DETAILS |
| SL-1 | PULL BOXES & CONDUIT TRENCH DETAIL |
| SL-2 | CONCRETE FOUNDATIONS & LIGHT POLE BASE, TYPE B |
| | |

TRAFFIC STANDARD PLANS

| STANDARD NO. | DESCRIPTION | |
|-----------------|--------------------------------------------------------------------------------------------|-----------------|
| PM-1 | LAYOUT DETAILS | |
| PM-2 | TOLERANCES FOR PAVEMENT MARKING LINES | |
| PM-3 | DIVIDED ROADWAY MULTIPLE LANES WITH ENTRANCE AND EXIT RAMPS | STRIPING LAYOUT |
| PM-4 | DIVIDED ROADWAY MULTIPLE LANES WITH ENTRANCE AND EXIT RAMPS | STRIPING LAYOUT |
| PM-5 | DIVIDED ROADWAY MULTIPLE LANES WITH ENTRANCE AND EXIT RAMPS | STRIPING LAYOUT |
| PM-6 | PAINTED ISLAND DETAILS | |
| PM-7 | INTERSECTION DETAILS | |
| PM-8 | WORD AND SYMBOL LANE LAYOUT | |
| PM-9 | PAVEMENT MARKING AT MINOR INTERSECTIONS | |
| PM-10 | TURNING LANE EXTENSION DETAILS | |
| PM-11 | CROSSWALK DETAIL OPTIONS | |
| PM-12 | WORDS AND SYMBOLS | |
| PM-13 | WORDS AND SYMBOLS | |
| PM-14 | SPEED ZONE PAVEMENT MARKINGS (DIVIDED HIGHWAY) | |
| PS-1 | ALUMINUM PLANK DETAILS | |
| PS-2 PS-3 | ALUMINUM PLANK DETAILS ALUMINUM SHEET DETAILS | |
| PS-4 | TUBULAR / U-CHANNEL POST DETAIL | |
| PS-5 | STEEL BEAM DETAILS (NON-BREAKAWAY) | |
| PS-6 | STEEL BEAM DETAILS (NON-BREAKAWAY) | |
| PS-7 | STEEL BEAM DETAILS (BREAKAWAY) | |
| PS-8 | STEEL BEAM DETAILS (BREAKAWAY) | |
| PS-9 | BREAKAWAY MOUNTS | |
| PS-10 | BREAKAWAY MOUNTS | |
| SG-1 | ROUTE MARKER DETAILS | |
| SG-2 | REGULATORY SIGNS | |
| SG-3 | REGULATORY SIGNS | |
| SG-4 | REGULATORY SIGNS | |
| SG-5 | REGULATORY SIGNS | |
| SG-6 | REGULATORY SIGNS | |
| SG-7 | WARNING SIGNS | |
| SG-8 | WARNING SIGNS | _ |
| SG-9 | WARNING SIGNS | |
| SG-10 | WARNING SIGNS | |
| SG-11 | WARNING SIGNS | |
| SG-12 | MISCELLANEOUS SIGNS | |
| SG-13 | INFORMATIONAL SIGNS | |
| SG-14 | INFORMATIONAL SIGNS | |
| TS-1 TS-2 | TRAFFIC SIGNAL MAST ARM FOUNDATION—TYPE 1A TRAFFIC SIGNAL MAST ARM FOUNDATION—TYPE 1B & 1C | |
| TS-3 | TRAFFIC SIGNAL MAST ARM FOUNDATION—TYPE 16 & 10 | |
| TS-4 | QUADRUPOLE LOOP DETECTOR 2-4-2 TURNS | |
| TS-5 | RECTANGULAR LOOP DETECTOR 3 TURNS | |
| 100 | 1.2017.11.0027.11 2001 221201011 3 1011110 | |



MAX. LENGTH RADIUS USE CURVED CURB < 21' 21′ 22′ - 28′ 29' - 35' 36' - 42' 43' - 49' 50' - 56' 57' - 60' OVER 60' 10'

* NORMALLY 7" REVEAL, VARIES 9" MAX. TO 2" AT DRIVEWAYS AND O" AT PEDESTRIAN SIDEWALK RAMPS. NOTE: ADJOINING STONES SHALL HAVE THE SAME

MINIMUM LENGTH OF STRAIGHT CURB STONES = 3' MAXIMUM LENGTH OF STRAIGHT CURB STONES = 10' MAXIMUM LENGTH OF STRAIGHT CURB STONES LAID ON CURVES - SEE CHART

OR APPROXIMATELY THE SAME LENGTH.

NHDOT STANDARD PLANS GRANITE SLOPE CURB

ITEM 609.2X - (STRAIGHT OR

CURVED) GRANITE SLOPE CURB

√4" OR 6", 1:1 SLOPE

MINIMUM LENGTH OF STRAIGHT CURB STONES = 18"

MAXIMUM LENGTH OF STRAIGHT CURB STONES = 8'

LAID ON CURVES - SEE CHART

MAXIMUM LENGTH OF STRAIGHT CURB STONES

VARIABLE SLOPE

BACKFILL MATERIAL

AS SHOWN ON PLANS

9" ±1/2" FOR 4" REVEAL

 $12'' \pm \frac{1}{2}''$ FOR REVEALS > 4"

RADIUS FOR

STONES WITH

SQUARE JOINTS

< 2'

2' - 15'

16' - 28'

29' - 41'

42' - 55'

56′ - 68′

69′ - 82′

83' - 96'

97' - 110' OVER 110'

NOTE: ADJOINING STONES SHALL HAVE THE SAME

OR APPROXIMATELY THE SAME LENGTH.

FINISHED

GRADE

VARIABLE | SLOPE

<u>SECTION</u>

REV. DATE PLATE 06-16-2010 STANDARD

MAXIMUM

LENGTH


USE CURVED CURB

USE RADIAL JOINTS

1'-6"

NHDOT STANDARD PLANS STRAIGHT OR CURVED GRANITE CURB


| REV. | PLATE | |
|------------|-------|----------|
| 06-16-2010 | | 1 |
| | | STANDARD |
| | | CR-1 |



 $R' = 5\frac{5}{8}'' \text{ FOR 1' } R$

DETAIL FOR CUTTING SLOPE CURB <u>WITH RADIAL JOINTS</u>

NOTE: USE FOR 2' TO 15' RADIUS - SEE CHART ON PLATE 4.



 $R' = 11^{5}/8'' \text{ FOR } 1.5' \text{ R}$

DETAIL FOR CUTTING CURVED SLOPE CURB WITH <u>1' OR 1.5' RADIUS</u>

| NHDOT STANDARD PLANS | REV. DATE | PLATE |
|-------------------------------------------------|------------|----------|
| DETAILS TOD CUTTING STOLET SDANITE SLODE SUDD | 06-16-2010 | 3 |
| DETAILS FOR CUTTING STRAIGHT GRANITE SLOPE CURB | | STANDARD |
| | | CR-1 |

| L-1 | 2' | 2.5′ | 3′ | 3.5′ | 4 ′ | 5′ | 6′ | 8 ′ | 10′ | 12′ | 14′ | 15′ |
|------------|-----------|--------------|-----------|----------|----------|----------|----------|------------------------------------|----------|----------|-----------|-----------|
| | | - | | | - | L | -2 | - | | | | |
| 0'-9" | 0'-61/2" | | | | | | | | | | | |
| 1′-0″ | 0'-83/4" | 0'-91/2" | | | | | | | | | | |
| 1 ′ –1 ″ | 0'-91/2" | 0'-101/4" | | | | | | | | | | |
| 1 ′ –2 ″ | 0'-101/4" | 0'-11" | 0'-111/2" | | | | | | | | | |
| 1′-3″ | 0'-11" | 0'-113/4" | 1'-01/4" | | | | | | | | | |
| 1 ′ –4 ″ | 0'-113/4" | 1'-01/2" | 1'-11/4" | 1'-11/2" | | | | | | | | |
| 1′-5″ | 1'-01/2" | 1'-11/2" | 1'-2" | 1'-21/2" | 1'-23/4" | 1-31/4" | 1'-31/2" | 1'-4" | 1 ′ -4 ″ | 1'-41/4" | 1'-41/4" | 1'-41/4" |
| 1 ′ -6 ″ | 1'-11/4" | 1'-21/4" | 1'-23/4" | 1'-31/4" | 1'-31/2" | 1 ' -4 " | 1'-41/2" | 1'-43/4" | 1′-5″ | 1-51/4" | 1'-51/4" | 1'-51/4" |
| 1′-7″ | 1'-2" | 1'-3" | 1'-33/4" | 1 ′ –4 ″ | 1'-41/2" | 1′-5″ | 1'-51/4" | 1'-5 ³ / ₄ " | 1′-6″ | 1'-61/4" | 1-61/4" | 1-61/4" |
| 1 ′ -8 ″ | 1'-23/4" | 1'-33/4" | 1'-41/2" | 1′-5″ | 1'-51/4" | 1′-6″ | 1'-61/4" | 1'-63/4" | 1′-7″ | 1′-7″ | 1'-71/4" | 1'-71/4" |
| 1′-9″ | | | | | | | 1'-71/4" | 1'-71/2" | 1′-8″ | 1′-8″ | 1'-81/4" | 1'-81/4" |
| 1′-10″ | | | | | | | 1′-8″ | 1'-81/2" | 1'-83/4" | 1′-9″ | 1'-91/4" | 1'-91/4" |
| 1 ′ –1 1 ″ | | | | | | | 1'-9" | 1'-91/2" | 1'-93/4" | 1'-10" | 1'-101/4" | 1'-101/4" |
| 2′-0″ | | | | | | | 1'-10" | 1'-101/2" | 1-103/4" | 1'-11" | 1'-11" | 1'-11" |
| 2′-1″ | | | | | | | | | | | 2'-0" | 2'-0" |
| 2'-2" | | | | | | | | | | | 2'-1" | 2'-1" |
| 2′-3″ | | | | | | | | | | | 2'-2" | 2'-2" |
| 2′-4″ | | | | | | | | | | | 2'-3" | 2'-3" |
| 2′-5″ | | | | | | | | | | | 2'-4" | 2'-4" |
| 2′-6″ | | | | | | | | | | | 2'-43/4" | 2'-5" |
| 2′-7″ | | | | | | | | | | | 2'-53/4" | 2'-53/4" |
| 2′-8″ | | | | | | | | | | | 2'-63/4" | 2'-63/4" |

RADIUS (SEE DETAIL ON PLATE 3)

| NHDOT STANDARD PLANS | | | | | |
|----------------------|----------|------------|---------|--|--|
| CHART FOR | CUTTING | STRAIGHT | GRANITE | | |
| SLOPE CU | JRB WITH | I RADIAL . | IOINTS | | |


| REV. | PLATE | | |
|------------|-------|----------|--|
| 06-16-2010 | | 4 | |
| | | STANDARD | |
| | | CR-1 | |
| | | · | |

REVISION DATE 07-13-2001 06-16-2010

STANDARD

NO. CR-1

*.DGN FILE NAME CR-1




DELINEATOR SPACING

APPROXIMATE SPACING FOR DELINEATORS ON HORIZONTAL CURVES


| | T | 1 |
|---------------------|--------------|----------------|
| RADIUS | SPACING FOR | SPACING FOR |
| OF | POSTMOUNTED | BEAM GUARDRAIL |
| CURVE | DELINEATORS | DELINEATORS |
| (FT) | ON CURVE = S | ON CURVE = S |
| | (FT) | (FT) |
| ≤ 50 | 20 | 18.75 |
| > 50 BUT ≤ 115 | 25 | 25 |
| > 115 BUT ≤ 180 | 35 | 25 |
| > 180 BUT ≤ 250 | 40 | 25 |
| > 250 BUT ≤ 300 | 50 | 50 |
| > 300 BUT ≤ 400 | 55 | 50 |
| > 400 BUT ≤ 500 | 65 | 50 |
| > 500 BUT ≤ 600 | 70 | 50 |
| > 600 BUT ≤ 700 | 75 | 75 |
| > 700 BUT ≤ 800 | 80 | 75 |
| > 800 BUT ≤ 900 | 85 | 75 |
| > 900 BUT ≤ 1,000 | 90 | 75 |
| > 1,000 ON MAINLINE | 250 | 100 |
| > 1,000 ON RAMPS | 100 | 100 |

- 1. THE MINIMUM SPACING SHALL BE 20 FEET FOR POST MOUNTED DELINEATORS AND 18.75 FEET FOR BEAM GUARDRAIL AND CONCRETE BARRIER DELINEATORS.
- 2. IN ADVANCE OF OR BEYOND A CURVE, AND PROCEEDING AWAY FROM THE END OF THE CURVE, THE SPACING OF THE FIRST POST MOUNTED DELINEATOR IS 2S, THE SECOND IS 3S, AND THE THIRD IS 6S, BUT NOT TO EXCEED 250 FEET IF ON A MAINLINE, OR 100 FEET ON A RAMP.




GENERAL NOTES


- 1. UNLESS OTHERWISE ORDERED, DELINEATORS SHALL BE MOUNTED ALONG THE RIGHT SIDE OF ALL ROADWAYS (SEE TYPICAL). DELINEATORS MAY ALSO BE USED ON THE LEFT SIDE OF DIVIDED HIGHWAYS WHERE NEEDED FOR CLEAR INDICATION OF THE ALIGNMENT.
- 2. DELINEATORS LOCATED BEHIND GUARDRAIL SHALL BE INSTALLED SO THAT THE DELINEATOR POST IS ADJACENT TO THE TRAILING EDGE OF THE NEAREST GUARDRAIL POST.
- 3. WHEN DELINEATION IS USED ONLY ON CURVES, THREE DELINEATORS SHALL BE PLACED BEFORE AND AFTER THE CIRCULAR PORTION OF THE CURVE.
- 4. WHEN DELINEATION IS USED ON TANGENTS, THE SPACING SHALL BE 250 FEET. THE TANGENT SPACING SHALL BEGIN BEYOND THE SPACING REQUIREMENTS FOR CURVES.
- 5. DELINEATOR COLORS SHALL IN ALL CASES CONFORM TO THE COLOR OF THE EDGELINES.
- 6. DELINEATORS WILL NOT BE PLACED BEHIND SIDEWALK.




TYPICAL INSTALLATION (ITEM 621.31)




(ITEM 621.2)





DELINEATOR WITHIN GUARDRAIL SECTION



RETROREFLECTIVE PERMANENT CONCRETE BARRIER DELINEATOR

(ITEM 621.1)

BARRIER DELINEATOR GENERAL NOTES

- A. THIS DELINEATOR IS TO BE PLACED ON TOP OF CONCRETE BARRIER.
- B. IF GLARE SCREEN IS PLACED ON TOP OF THE CONCRETE BARRIER, THEN DELINEATORS ARE ATTACHED TO EITHER SIDE OF THE BARRIER AND DO NOT NEED TO BE RETRO-REFLECTORIZED ON BOTH SIDES. THE UPPER EDGE OF THE DELINEATOR IS TO BE PLACED VERTICALLY 1/2 INCH DOWN FROM THE TOP OF THE BARRIER.
- C. YELLOW DELINEATOR FOR MEDIAN BARRIERS SHALL BE LOCATED ON THE LEFT SIDE OF THE ROADWAY FACING TRAFFIC IN BOTH DIRECTIONS, AND SHALL HAVE RETROREFLECTIVE MATERIAL ON BOTH SIDES, BEGINNING AT THE FIRST FULL HEIGHT OF THE CONCRETE MEDIAN BARRIER AND SPACED ACCORDING TO CHART FOR BEAM GUARDRAIL DELINEATORS.

DELINEATION STANDARD

ROADSIDE DELINEATION

STANDARD NO. DL-1

REVISION DATE 07-13-2001 06-16-2010 03-05-2015

*.DGN FILE NAME


S

STANDARD NO. DL-1

NO. DL-2

07-13-2001 06-16-2010

*.DGN FILE NAME



STANDARD NO. DL-8

MILLED RUMBLE STRIPES (CENTERLINE)





NO. DP-1

07-13-2001 06-16-2010

*.DGN FILE NAME

DP-1





BOLTS FOR USE WITH LOW HEADWALL STRUCTURES

ELEVATIONS

ALL HOLES 9/16" DIA. TO BE

DRILLED OR PUNCHED PRIOR

TO COATING PIPE, OR FIELD

BOLTS TO BE SPACED APPROX.

REV. DATE

PLATE

STANDARD

DP-1

18" C-C.

DRILLED IF CHANGES ORDERED.

INSIDE FACE OF

ANCHOR BOLT AND

SPECIFICATION.

HEXAGONAL NUTS ASTM A307,

GALV. TO ASTM A153 (AASHTO M232)

FLOW LINE

TACK WELD WHEN USED

IN A VERTICAL POSITION

NHDOT STANDARD PLANS

³⁄₄"± →

2" STD

WASHER⁻

NHDOT STANDARD PLANS

 REV. DATE
 PLATE

 4
 4

 STANDARD
 DP-1


STANDARD NO. DP-1




NO. DR-1


07-13-2001 06-16-2010 08-14-2015

*.DGN FILE NAME



- 2. FREE OPEN AREA = 1.73 S.F.
- 3. NOT TO BE USED WHEN BICYCLE TRAFFIC IS ANTICIPATED.
- 4. USE 3-FLANGE FRAME IF INSTALLED ADJACENT TO GRANITE CURB.





GENERAL NOTES


- 1. ALL DIMENSIONS ARE NOMINAL.
- 2. FRAMES USING NARROWER DIMENSIONS FOR THICKNESS ARE ALLOWED PROVIDED:
- A. THE FRAMES MEET OR EXCEED THE SPECIFIED LOAD RATING.
 B. THE INTERIOR PERIMETER (SEAT AREA) DIMENSIONS OF THE FRAMES REMAIN THE SAME TO ALLOW CONTINUED USE OF EXISTING GRATES/COVERS AS THE EXISTING FRAMES ALLOW, WITHOUT SHIMS OR
- OTHER MODIFICATIONS OR ACCOMMODATIONS.

 C. ALL OTHER PERTINENT REQUIREMENTS OF THE SPECIFICATIONS ARE MET.
- 3. FRAME AVAILABLE IN 4" OR 8" HEIGHTS.
- 4. FREE OPEN AREA = 2.55 S.F.
- 5. USE 3-FLANGE FRAME IF INSTALLED ADJACENT TO GRANITE CURB.

TYPE "B" GRATE & FRAME

'/2" R. TYP.

| REV. DATE | PLATE |
|------------|----------|
| 06-16-2010 | 2 |
| 08-14-2015 | STANDARD |
| | DR-1 |



TO BE USED IN BERM DITCHES AND AT LOCATIONS INACCESSIBLE TO VEHICULAR TRAFFIC

NHDOT STANDARD PLANS

TYPE "C" GRATE & FRAME

B

 \underline{PLAN}

251/4"

24¹/₄"
23⁷/₈"

221/4"

SECTION A-A

NHDOT STANDARD PLANS

TYPE "A" GRATE & FRAME

 $-\frac{3}{8}$ " R. TYP.

11/4"

| PIPE DIAMETER | | EPTH "A" HES |
|------------------|------------|-----------------|
| INCHES | ONE THROAT | TWO THROAT |
| 12" | 8 " | 8 " |
| 15 " | 8 " | 8 " |
| 18" | 16" | 8 " |
| 24" | 18" | 16" |

REV. DATE

STANDARD
DR-1

06-16-2010


IN A SERIES OF CONNECTING


C.B.'S OR D.I.'S, THE OUTLET

PIPES MAY INCREASE IN

DIAMETER, BUT THE SURFACE

THROAT OPENINGS ARE NOT AFFECTED.





GENERAL NOTES


- 1. ALL DIMENSIONS ARE NOMINAL.
- 2. NOT TO BE USED WHEN BICYCLE TRAFFIC IS ANTICIPATED.
- 3. USE 3-FLANGE FRAME IF INSTALLED ADJACENT TO GRANITE CURB.
- 4. FREE OPEN AREA = 1.80 S.F.


| REV. DATE | PLATE | |
|------------|----------|--|
| 06-16-2010 | 3 | |
| | STANDARD | |
| | DR-1 | |


NHDOT STANDARD PLANS $TYPE \ ^{\prime\prime}E^{\prime\prime} \ GRATE$


| REV. | DATE | PLATE |
|------------|------|----------|
| 06-16-2010 | | 4 |
| | | STANDARD |
| | | DR-1 |
| | | |












6.5




PLAN



TOP OF GRATE_ OR COVER SEE NOTE NO. 2 — SEE NOTE NO. 4 — MIN. 3" (TYP.) 4' TO 8' (SEE NOTE NO. 5) -HOLE CAST TO PLAN CHART

SECTION A-A



* FOR $>6'\phi$ STRUCTURES

SECTION B-B

FLAT SLAB TOP

| DIAMETER | WALL THICKNESS (MIN.) | FLOOR THICKNESS (MIN.) |
|------------|-----------------------------|------------------------------|
| 4′ | 5 " | 6" |
| 5 <i>'</i> | 6" | 8 " |
| 6′ | 7 " | 8 " |
| 8′ | 9 " | 10" |

GENERAL NOTES

78

60

- 1. ITEM NUMBERS: C.B.= 604.1XXX, D.I.= 604.2XXX, M.H.= 604.32XX
- 2. FITTING FRAME TO GRADE MAY BE DONE WITH PREFABRICATED ADJUSTMENT RINGS OR CLAY BRICKS (2 COURSES MAX.).
- 3. CB & DI GRATES IN PAVED AREAS SHALL BE SET ACCORDING TO THE PAVEMENT DEPRESSION DETAIL SHOWN ON PLATE 4 OF STANDARD NO. DR-2.
- 4. CONE SECTIONS MAY BE EITHER CONCENTRIC OR ECCENTRIC, OR FLAT SLAB TOPS MAY BE USED WHERE PIPE WOULD OTHERWISE ENTER INTO THE CONE SECTION OF THE STRUCTURE AND WHERE PERMITTED.
- 5. FOR STRUCTURES WITH DIAMETERS GREATER THAN 4', THE DIAMETER MAY BE CONSTANT FROM TOP TO BOTTOM WITH A FLAT SLAB TOP, OR A RISER SECTION THAT TRANSITIONS FROM A STANDARD 4' CONE SECTION TO THE LARGER DIAMETER RISER OR BASE SECTION MAY BE USED.
- 6. PIPE ELEVATIONS SHOWN ON PLANS SHALL BE FIELD VERIFIED PRIOR TO PRECASTING.
- 7. OUTSIDE EDGES OF PIPES SHALL PROJECT NO MORE THAN 3" BEYOND INSIDE WALL OF STRUCTURE.
- 8. PRECAST SECTIONS SHALL HAVE A TONGUE AND GROOVE JOINT 4" HIGH AT AN 11° ANGLE CENTERED IN THE WIDTH OF THE WALL AND SHALL BE ASSEMBLED USING AN APPROVED FLEXIBLE SEALANT IN JOINTS.
- 9. ALL STRUCTURES WITH MULTIPLE PIPES SHALL HAVE A MINIMUM OF 12" OF INSIDE SURFACE BETWEEN HOLES, NO MORE THAN 75% OF A HORIZONTAL CROSS-SECTION SHALL BE HOLES, AND THERE SHALL BE NO HOLES CLOSER THAN 3" TO JOINTS.

DRAINAGE STANDARD

PRECAST REINFORCED CONCRETE C.B., D.I. AND M.H.





REVISION DATE


07-13-2001

06-16-2010

*.DGN FILE NAME

ES-1

NO. ES-1



| | | | DIMENSIONS | | | | | |
|-----------|------|-------|------------|------|-------|---------|--------------|--|
| ITEM | PIPE | METAL | A (1" | В | H (1" | L(11/2' | W (2" | |
| NO. | DIA. | GAGE | TOL.) | MAX. | TOL.) | TOL.) | TOL.) | |
| 603.34112 | 12" | 16 | 6" | 6" | 6" | 21" | 24" | |
| 603.34115 | 15" | 16 | 7 " | 8" | 6" | 26" | 30" | |
| 603.34118 | 18" | 16 | 8 <i>"</i> | 13" | 6" | 31" | 36" | |
| 603.34124 | 24" | 16 | 10" | 16" | 6" | 41" | 48" | |
| 603.34130 | 30" | 14 | 12" | 16" | 8" | 51" | 60" | |
| 603.34136 | 36" | 14 | 14" | 19" | 9" | 60" | 72" | |
| 603.34142 | 42" | 12 | 16" | 22" | 11" | 69" | 84" | |
| 603.34148 | 48" | 12 | 18" | 27" | 12" | 78" | 90" | |

- DIA. PIPE IN ONE PIECE, FOR 36" TO 48" DIA. PIPE TO BE MADE FROM TWO SHEETS JOINED BY RIVETING
- 2. CONNECTOR SECTION, CORNER PLATE AND TOE PLATE TO BE SAME THICKNESS AS END SECTION AND EACH TO BE GAL VAN I ZED.

| T D | SEE TABLE FOR SLOPE X CULVERT PLANNED END SECTION CULVERT LENGTH |
|-----|-----------------------------------------------------------------------|
|-----|-----------------------------------------------------------------------|

<u>PLAN</u>

ORDERED

GENERAL NOTES

- 1. DESIGN OF END SECTION SHALL CONFORM TO STANDARD REIN-FORCED CONCRETE PIPE.
- 2. CUT OFF WALL TO BE POURED IN FIELD, IF NECESSARY, AS DIRECTED BY THE ENGINEER.
- 3. PAYMENT FOR THE CUT OFF WALL WILL BE MADE UNDER THE APPROPRIATE CONTRACT ITEMS.

| GROOVED END ON OUTLET END SECTION TONGUE END ON INLET END SECTION | | | | |
|-------------------------------------------------------------------|-------------|--------------|----------------------------|---|
| (OR END SECTION TO FIT PIPE USED) C X | ITEM NO. | PIPE DIA. | APPROX. SLOPE X to Y | |
| Y | 603.30112 | 12" | 3 TO 1 | 4 |
| T PAR OR | 603.30115 | 15" | 3 TO 1 | (|
| T T | 603.30118 | 18" | 3 TO 1 | į |
| STEEL FABRIC REINFORCMENT | 603.30124 | 24" | 3 TO 1 | 9 |
| REINFURCMENT | 603.30130 | 30" | 3 TO 1 | 1 |
| | 603.30136 | 36" | 3 TO 1 | 1 |
| | 603.30142 | 42" | 3 TO 1 | 2 |
| LONGITUDINAL SECTION END VIEW | 603.30148 | 48" | 3 TO 1 | 2 |
| OPTIONAL CONCRETE——————————————————————————————————— | | | | |

SLOPE DETAIL

| ITEM NO. | PIPE DIA. | APPROX. SLOPE X to Y | A | В | С | D | R | Т |
|-------------|--------------|----------------------------|-------|--------|----------------------------------|-----|------|------|
| 603.30112 | 12" | 3 TO 1 | 4 " | 24" | 48 ⁷ / ₈ " | 24" | 9" | 2" |
| 603.30115 | 15" | 3 TO 1 | 6" | 27" | 46" | 30" | 11" | 21/4 |
| 603.30118 | 18" | 3 TO 1 | 9" | 27" | 46" | 36" | 12" | 21/2 |
| 603.30124 | 24" | 3 TO 1 | 91/2" | 431/2" | 30" | 48" | 14" | 3" |
| 603.30130 | 30" | 3 TO 1 | 12" | 54" | 19 ³ / ₄ " | 60" | 15 " | 31/2 |
| 603.30136 | 36" | 3 TO 1 | 15" | 63" | 33" | 72" | 20" | 4" |
| 603.30142 | 42" | 3 TO 1 | 21" | 63" | 33" | 78" | 22" | 41/2 |
| 603.30148 | 48" | 3 TO 1 | 24" | 72" | 24" | 84" | 22" | 5" |

| NHDOT STANDARD PLANS | | | | | | | | | |
|----------------------|-----|---------|-----|---------|---|------------|-------|------|--|
| | END | SECTION | FOR | PLASTIC | & | CORRUGATED | STEEL | PIPE | |

NHDOT STANDARD PLANS

| REV. | DATE | PLATE |
|------------|------|----------|
| 06-16-2010 | | 1 |
| | | STANDARD |
| | | ES-1 |

CONCRETE END SECTION FOR REINFORCED CONCRETE PIPE

NHDOT STANDARD PLANS

| REV. DATE | | PLATE |
|------------|--|----------|
| 06-16-2010 | | 2 |
| | | STANDARD |
| | | ES-1 |

STANDARD NO. ES-1


REV. DATE PLATE 3 STANDARD ES-1

NHDOT STANDARD PLANS

REV. DATE STANDARD

ALTERNATE CONNECTIONS GENERAL NOTES STD. COUPLING — 1. END SECTION FOR 12" TO 30" BAND ³⁄8″ GALV. BOLTS OR BOLTING ON CENTER LINE. TOE PLATE MAX. SPCG. **ELEVATION**

TYPICAL CROSS-SECTION



NO. FN-1


REVISION DATE

07-13-2001

06-16-2010

*.DGN FILE NAME

FN-1




GENERAL NOTES

- 1. ALL END POSTS SHALL HAVE ONE BRACE, ALL CORNER AND INTERMEDIATE BRACE OR PULL POSTS SHALL HAVE TWO BRACES.
- 2. INTERMEDIATE OR LINE POSTS SHALL BE STANDARD STUDDED TEE POSTS.
- 3. END POSTS, CORNER POSTS AND PULL POSTS SHALL BE AN ANGLE POST DETAILED IN PLATE 3. BRACES SHALL BE AN ANGLE POST DETAILED IN PLATE 4.
- 4. WHERE GROUND CONDITION PERMITS, FORMS FOR FOOTING WILL NOT BE REQUIRED.
- 5. CONCRETE SHALL BE CLASS A.

| | NHDOT STANDARD PLANS | |
|-------|-------------------------|-------|
| | | 06-16 |
| WOVEN | WIRE FENCE (ITEM 607.1) | |
| | | |

| REV. | DATE | PLATE |
|------------|------|----------|
| 06-16-2010 | | 1 |
| | | STANDARD |
| | | FN-1 |





<u>DETAIL OF CORNER BRACE - POST ASSEMBLY</u>


NHDOT STANDARD PLANS

POST ASSEMBLIES FOR WOVEN WIRE FENCE (ITEM 607.41)

| REV. | PLATE | |
|------------|-------|----------|
| 06-16-2010 | | 2 |
| | | STANDARD |
| | | FN-1 |







TYPICAL FENCE POST ASSEMBLY

| NHDOT STANDARD PLANS | | REV. DATE | |
|--------------------------------------|------------|-----------|----------|
| | 06-16-2010 | | 3 |
| POST ASSEMBLIES FOR WOVEN WIRE FENCE | | | STANDARD |

NHDOT STANDARD PLANS

ANGLE BRACES FOR WOVEN WIRE FENCE

| REV. | DATE | PLATE |
|------------|------|----------|
| 06-16-2010 | | 4 |
| | | STANDARD |
| | | FN-1 |

STANDARD NO. FN-1

NO. FN-2


REVISION DATE

07-13-2001

06-16-2010

*.DGN FILE NAME

FN-2



ELEVATION

GENERAL NOTES

- 1. ALL END POSTS SHALL HAVE ONE BRACE. (SEE DETAIL PLATE 2).
- 2. ALL CORNER AND INTERMEDIATE BRACE OR PULL POSTS SHALL HAVE TWO BRACES.
- 3. POST FOOTING DETAILS ARE SHOWN IN PLATE 3. FOR FENCE ERECTION ON THE RIGHT-OF-WAY LINE, SEE PLATE 3 OF STD. NO. FN-1.
- 4. FENCE DETAILS ARE FOR STEEL, ALUMINUM, OR VINYL COATED FENCING. FOR ADDITIONAL DETAILS AND NOTES, SEE PLATES 2, 3, & 4.

| NHDOT STANDARD PLANS | REV. | DATE | PLATE |
|----------------------|------------|------|----------|
| | 06-16-2010 | | 1 |
| $CHAIN\ LINK\ FENCE$ | | | STANDARD |
| | | | |


REV. DATE

06-16-2010

PLATE

STANDARD


FN-2



GENERAL NOTES

1. FOR ADDITIONAL DETAILS AND NOTES SEE PLATES 1, 3 & 4.

| NHDOT STANDARD PLANS | REV. | DATE | PLATE |
|----------------------|------------|------|----------|
| | 06-16-2010 | | 2 |
| $CHAIN\ LINK\ FENCE$ | | | STANDARD |
| | | | FN-2 |



END, CORNER AND PULL POST

| TO | OP RAILS | | LIN | E POSTS | |
|-----------------|--------------------------------------|-------|-----------------|--------------------------------------|-------|
| FENCE HEIGHT | ROUND | lb/ft | FENCE HEIGHT | TUBUL | AR |
| (ft) | | | (f +) | ROUND | lb/ft |
| | STEEL | | | STEEL | |
| ALL | 2 ⁷ / ₈ " O.D. | 5.79 | UP TO 6' | 1.90" O.D. | 2.72 |
| A | LUMINUM | | OVER 6' | 2 ³ ⁄8″ O.D. | 3.65 |
| UP TO 12' | 2 ⁷ / ₈ " O.D. | 2.00 | AL | LUMINUM | |
| | 0 | | UP TO 12' | 2 ³ / ₈ " O.D. | 1.264 |

| | STEEL SWING GATE AND POST TABLE | | | | | |
|------|---------------------------------|-----------------|--------------------------------------|-------|------------------------------|-------|
| TYPE | GATE O | PENING | GATE POST (TU | | (TUBULAR) | |
| 1176 | SINGLE | DOUBLE | ROUND | lb/ft | SQUARE | lb/ft |
| Α | UP TO 6' | UP TO 12' | 2 ⁷ / ₈ " O.D. | 5.79 | $2^{1/2}'' \times 2^{1/2}''$ | 5.70 |
| В | OVER 6' TO 13' | OVER 12' TO 26' | 4" O.D. | 9.11 | 3" × 3" | 7.55 |
| C | OVER 13' TO 18' | OVER 26' TO 36' | 6 ⁵ / ₈ " O.D. | 18.97 | _ | - |
| D | OVER 18' | OVER 36' | 8 ⁵ / ₈ " O.D. | 28.55 | _ | - |
| CATE | UP TO 6' | | 1.660" D.D. | 2.27 | 11/2" × 11/2" | 1.90 |
| GATE | OVER 6' | | 1.90" O.D. | 2.72 | 2"× 2" | 2.72 |

| ALUMINUM SWING GATE AND POST TABLE | | | | | | |
|------------------------------------|-----------------|-----------------|-------------------------|-------|-----------|-------|
| TYPE | GATE OPENING | | GATE | POST | (TUBULAR) | |
| IIFE | SINGLE | DOUBLE ROUND | ROUND | lb/ft | SQUARE | lb/ft |
| A - A | UP TO 6' | UP TO 12' | 2 ⁷ ⁄8″ O.D. | 2.004 | | 1.76 |
| B - A | OVER 6' TO 12' | OVER 12' TO 24' | 4″ O.D. | 3.151 | _ | _ |
| C - A | OVER 12' TO 18' | OVER 24' TO 36' | 6 ⁵ ⁄8″ O.D. | 6.564 | _ | _ |
| D - A | OVER 18' TO 32' | OVER 36' TO 44' | 8 ⁵ ⁄8″ O.D. | 9.878 | _ | _ |
| GATE FRAME ALL | | | 1.90" O.D. | 0.940 | 2" × 2" | 1.12 |

| TYPE GATE O | | OPEN I NG | GATE POST (TUBULAR) | | | |
|-------------|-----------------|-----------------|--------------------------------------|-------|---------|-----|
| ITE | SINGLE | DOUBLE ROUND | ROUND | lb/ft | SQUARE | 16/ |
| A - A | UP TO 6' | UP TO 12' | 2 ⁷ / ₈ " O.D. | 2.004 | 3" × 3" | 1.7 |
| B - A | OVER 6' TO 12' | OVER 12' TO 24' | 4" O.D. | 3.151 | _ | - |
| C - A | OVER 12' TO 18' | OVER 24' TO 36' | 6 ⁵ / ₈ " O.D. | 6.564 | _ | - |
| D - A | OVER 18' TO 32' | OVER 36' TO 44' | 8 ⁵ / ₈ " O.D. | 9.878 | _ | - |
| | GATE FRAME | ALL | 1.90" O.D. | 0.940 | 2" × 2" | 1.1 |

NHDOT STANDARD PLANS POSTS FOR CHAIN LINK FENCE

STANDARD NO. FN-2


PLATE 4

STANDARD

FN-2

REV. DATE

06-16-2010



1. WHERE GROUND CONDITION PERMITS, FORMS FOR FOOTINGS

2. ALUMINUM POSTS IN CONCRETE SHALL HAVE A PROTECTIVE

WILL NOT BE REQUIRED.

COATING - 607.2.6

NHDOT STANDARD PLANS

CHAIN LINK FENCE

[FBB01-03]

STANDARD

NO. GR-1

& HARDWARE DETAILS

RAIL

EDGE OF

PAVEMENT

STEEL POST

TYPICAL SIDE VIEW

(SHOWN WITH FASTENERS)

STEEL POST -

CLARIFICA TION

DETAIL FOR

GENERAL NOTE 6

TRAFFIC

LINE POST ELEVATION

VIEW AT BEAM SPLICE

SEE NOTE 5

INTENDED USE

RAIL SPLICE BOLTS

POST BOLT (STEEL POSTS)

POST BOLT

|DESIGNATOR| L

FBB01

FBB02

FBB03

11/4"

FULL LENGTH THREAD

5/8" BUTTON HEAD BOLT AND RECESSED NUT

[FBB01-03]

13/4" MIN. THREAD LENGTH

9¹/₂" 4" MIN. THREAD LENGTH

GUARDRAIL STANDARD

DIMENSIONS. IN ORDER TO USE ANY OFFSET BLOCKS THAT HAVE

A) THE FACE OF RAIL SHALL REMAIN AT THE EDGE OF

SPECIFICATIONS AND DETAILS REMAIN IN FORCE.

PAVEMENT OR AT THE INDICATED LOCATION AS SHOWN ON

B) THE DISTANCE FROM THE BACK OF THE POST TO THE BREAK IN THE SLOPE SHALL NOT BE LESS THAN WHAT IS SHOWN

4:1 OR OTHER THAN THE NOMINAL DIMENSIONS AS SHOWN ON THE PLANS,


ON THE PLANS BUT IT MAY BE MORE.

C) ALL OTHER REQUIREMENTS OF THE PERTINENT


FLATTER SLOPE A) THE FOLLOWING APPLIES:

THE PLANS, AND

BEAM GUARDRAIL STANDARD SECTION-STEEL POSTS & HARDWARE DETAILS




WOOD POST



STANDARD SECTION


606.140 - BEAM GUARDRAIL (STANDARD SECTION-WOOD POSTS) LINEAR FOOT



ITEM


PAID:

SECTION THRU RAIL ELEMENT [4 SPACE W-BEAM GUARDRAIL DESIGNATED RWM04a (NOMINALLY 12'-6")] [8 SPACE W-BEAM GUARDRAIL UNDESIGNATED AT THIS TIME (NOMINALLY 25'=0")]



| DESIGNATOR | L | Т | INTENDED USE |
|------------|-------|-----------------------|------------------------|
| FBB01 | 11/4" | FULL LENGTH THREAD | RAIL SPLICE BOLTS |
| FBB03 | 10" | 4" MIN. THREAD LENGTH | POST BOLT |
| FBB04 | 18" | 4" MIN. THREAD LENGTH | POST BOLT (WOOD POSTS) |

5/8" BUTTON HEAD BOLT AND RECESSED NUT [FBB01-04]



LINE POST ELEVATION VIEW AT BEAM SPLICE


(SHOWN WITHOUT FASTENERS)

[FBBO4] WITH [FWC16a] UNDER NUT 3/4" Ø :=**^**===**|** FACE OF RAIL EDGE OF PAVEMENT [PDE04] WOOD POST &

CLARIFICATION DETAIL FOR

GENERAL NOTE 6

TYPICAL SIDE VIEW (SHOWN WITH FASTENERS)



WASHER[FWC16a]

- IN AASHTO'S "A GUIDE TO STANDARDIZED HIGHWAY BARRIER HARDWARE".
- 3. ONLY USE RECTANGULAR PLATE WASHERS [FWRO3] WHERE SHOWN ON THE OTHER STANDARD SHEETS OR AS REQUIRED BY THE MANUFACTURERS FOR THEIR PROPRIETARY PRODUCTS.
- 4. USE 12'-6" LENGTH RAIL ELEMENTS IN RAIL CURVES OF LESS THAN 100' RADIUS.
- 5. ESTABLISH RAIL HEIGHT AS FOLLOWS:
 - A) SET THE HEIGHT OF RAIL FROM THE EDGE OF THE PAVEMENT (EP) WHEN THE FACE OF RAIL IS AT THE EDGE OF PAVEMENT.
 - B) SET THE HEIGHT OF RAIL FROM THE GROUND AT THE FACE OF RAIL WHEN:
 - I) THE FACE OF RAIL IS OFFSET FROM THE EP AND THE CROSS SLOPE FROM THE EP TO THE FACE OF RAIL IS 10:1 OR FLATTER OR
 - II) THE FACE OF RAIL IS AT THE BACK OF A CURBED SIDEWALK AND THE CURB IS AT THE EDGE OF PAVEMENT
 - C) WHEN SITUATIONS OTHER THAN THOSE DESCRIBED IN A OR B ABOVE ARE ENCOUNTERED, EXTABLISH RAIL HEIGHT THROUGH AN ENGINEERING REVIEW TO ENSURE APPROPRIATE SYSTEM PERFORMANCE.
- 6. USE OF POSTS SHORTER THAN 7', BUT NOT LESS THAN 6'-0" LONG, IS ONLY ALLOWED UNDER THE FOLLOWING CONDITIONS:
 - A) WHERE THERE IS A MINIMUM DISTATNCE OF 1' FROM THE BACK OF THE GUARDRAIL POST ALONG A 10:1 OR FLATTER SLOPE TO THE SLOPE BREAK OF A 4:1 OR FLATTER SLOPE OR
 - B) WHERE THERE IS A MINIMUM DISTANCE OF 2' FROM THE BACK OF THE GUARDRAIL POST ALONG A 10:1 OR FLATTER SLOPE TO THE SLOPE BREAK OF A STEEPER THAN 4:1 STABLE SOIL OR STONE LINED SLOPE. THE TERM STABLE INCLUDES NOT SHOWING SIGNS OF SLOPE MOVEMENT (SUCH AS DEPRESSIONS, CRACKS PARALLEL TO THE ROADWAY, ETC.) OR ACTIVE EROSION.

7. THE FHWA HAS LISTED OFFSET BLOCKS ON THEIR WEBSITE THAT ARE ELIGIBLE FOR FEDERAL PARTICIPATION PER NCHRP 350 TEST LEVEL 3 CRITERIA. OTHERS MAY BE ADDED UNDER MASH AT TEST LEVEL 3 OR HIGHER IN THE FUTURE, SOME OF THESE OFFSET BLOCKS HAVE OR MAY HAVE DIMENSIONS THAT VARY MORE THAN WOULD BE CONSIDERED WITHIN THE NORMAL CONTEXT OF NOMINAL DIMENSIONS. IN ORDER TO USE ANY OFFSET BLOCKS THAT HAVE OTHER THAN THE NOMINAL DIMENSIONS AS SHOWN ON THE PLANS, THE FOLLOWING APPLIES:

- A) THE FACE OF RAIL SHALL REMAIN AT THE EDGE OF PAVEMENT OR AT THE INDICATED LOCATION AS SHOWN ON THE PLANS, AND
- B) THE DISTANCE FROM THE BACK OF THE POST TO THE BREAK IN THE SLOPE SHALL NOT BE LESS THAN WHAT IS SHOWN ON THE PLANS BUT IT MAY BE MORE.
- C) ALL OTHER REQUIREMENTS OF THE PERTINENT SPECIFICATIONS AND DETAILS REMAIN IN FORCE.

GUARDRAIL STANDARD

BEAM GUARDRAIL STANDARD SECTION-WOOD POSTS & HARDWARE DETAILS



TYPICAL FORESLOPE

△ CRUSHED GRAVEL

FORESLOPE AND 2:1 BACKSLOPE

FOR SHOULDER LEVELING

△ EMBANKMENT IN-PLACE-

INTERSECTION POINT OF 8% FLATTENED_

TYPICAL DITCHES-

SECTION C-C

ANCHOR

** THE BACK SLOPE SHALL BE 2:1 OR

STEEPER APPROACHING THE ANCHOR. IT IS NOT THE INTENT TO FLATTEN AN

EXISTING BACKSLOPE THAT IS STEEPER

THAN 2:1 UNLESS SO NOTED ON THE PLANS OR PROPOSAL.

TYPICAL FORESLOPE

△ CRUSHED GRAVEL

FORESLOPE AND 2:1 BACKSLOPE

FOR SHOULDER LEVELING

△ EMBANKMENT IN-PLACE-

INTERSECTION POINT OF 8% FLATTENED

TYPICAL DITCHES—

SECTION B-B

△ SEE NOTE 6 FOR ALL HATCHED AREAS

SECTION

△ EXTEND STRUCTURAL

SECTION OR USE GRAVEL

△ EMBANKMENT IN-PLACE-

SECTION A-A

TYPICAL SLOPE -


GR-5

BEAM GUARDRAIL

GUARDRAIL STANDARD

WILL BE PAID AS ITEM 206.2 - ROCK STRUCTURE EXCAVATION.

STANDARD TERMINAL UNIT TYPE E-2 NO. GR-5



SECTION TYPE E-2 AND E-2MOD NO. GR-6

INTERSECTION POINT OF 8% FLATTENED

SECTION C-C

** THE BACK SLOPE SHALL BE 2:1 OR

STEEPER APPROACHING THE ANCHOR. IT IS NOT THE INTENT TO FLATTEN AN

EXISTING BACKSLOPE THAT IS STEEPER

THAN 2:1 UNLESS SO NOTED ON THE PLANS OR PROPOSAL.

FORESLOPE AND 2:1 BACKSLOPE

TYPICAL DITCHES—

SECTION B-B

△ SEE NOTE 6 FOR ALL HATCHED AREAS

INTERSECTION POINT OF 8% FLATTENED

FORESLOPE AND 2:1 BACKSLOPE

△ EMBANKMENT IN-PLACE

SECTION A-A

TYPICAL SLOPE-

NO. GR-7 **REVISION DATE** 03-01-2006 06-16-2010

*.DGN FILE NAME

GR-7

GUARDRAIL STANDARD

BEAM GUARDRAIL TERMINAL SECTION TYPE E-2 MODIFIED 30

△ EMBANKMENT IN-PLACE-

INTERSECTION POINT OF 8% FLATTENED

FORESLOPE AND 2:1 BACKSLOPE

TYPICAL DITCHES-

SECTION C-C

** THE BACK SLOPE SHALL BE 2:1 OR

STEEPER APPROACHING THE ANCHOR.

IT IS NOT THE INTENT TO FLATTEN AN

EXISTING BACKSLOPE THAT IS STEEPER THAN 2:1 UNLESS SO NOTED ON THE

PLANS OR PROPOSAL.

TYPICAL SLOPE -

SECTION A-A

△ EMBANKMENT IN-PLACE-

INTERSECTION POINT OF 8% FLATTENED

FORESLOPE AND 2:1 BACKSLOPE

TYPICAL DITCHES—

SECTION B-B

△ SEE NOTE 6 FOR ALL HATCHED AREAS

GUARDRAIL STANDARD

BEAM GUARDRAIL TERMINAL
SECTION TYPE E-2 MODIFIED 40

BEAM GUARDRAIL TERMINAL

GUARDRAIL STANDARD

SECTION TYPE E-2 MODIFIED 45


REVISION DATE 03-01-2006 06-16-2010

*.DGN FILE NAME GR-9

203.5596 - GUARDRAIL E-2 PLATFORMS. ROCK EXCAVATION WILL BE PAID AS ITEM 206.2 - ROCK STRUCTURE EXCAVATION.

△ EXTEND STRUCTURAL SECTION OR USE GRAVEL △ EMBANKMENT IN-PLACE-TYPICAL SLOPE -

SECTION A-A




SECTION B-B

△ SEE NOTE 6 FOR ALL HATCHED AREAS

TYPICAL FORESLOPE J 6:1 ANCHOR △ CRUSHED GRAVEL FOR SHOULDER LEVELING △ EMBANKMENT IN-PLACE-TYPICAL DITCHES— INTERSECTION POINT OF 8% FLATTENED FORESLOPE AND 2:1 BACKSLOPE

> ** THE BACK SLOPE SHALL BE 2:1 OR SECTION C-C STEEPER APPROACHING THE ANCHOR. IT IS NOT THE INTENT TO FLATTEN AN

EXISTING BACKSLOPE THAT IS STEEPER THAN 2:1 UNLESS SO NOTED ON THE PLANS OR PROPOSAL.



NO. GR-10


REVISION DATE

07-13-2001

06-16-2010

*.DGN FILE NAME


GR-10



TERMINAL UNIT TYPE G-2

606.147- BEAM GUARDRAIL (TERMINAL UNIT TYPE G-2) PAID: ON DIVIDED HIGHWAYS ONLY WITH DIRECTION OF TRAFFIC USE:


AS INDICATED



NOTE: TIGHTEN CABLE ASSEMBLY TO TAUT TENSION & DOUBLE-NUT BOTH ENDS

STEEL POST






RECTANGULAR PLATE WASHER [FWR03] (3 REQ'D)


1" HEX NUT & WASHER

[FNX24a] AND [FWC24a]




SLOTTED HOLE


END PLATE [FPA01]



ANCHOR PLATE [FPA01]



SOIL PLATE (2 REQ'D-POSTS A)



BEARING PLATE [FPB01]


GENERAL NOTES

- 1. THE LENGTH OF NEED IS THE TOTAL LENGTH OF A LONGITUDINAL BARRIER NEEDED TO SHIELD AN AREA OF CONCERN. TO DETERMINE THE LENGTH OF NEED, REFER TO THE ROADSIDE DESIGN GUIDE - AASHTO, LATEST ADOPTED VERSION, THE G-2 UNIT SHALL TERMINATE IN A 4:1 OR FLATTER SLOPE.
- 2. DESIGNATIONS PROVIDED IN BRACKETS [REFERENCE STANDARD ELEMENTS DETAILED IN A GUIDE TO STANDARDIZED HIGHWAY BARRIER RAIL HARDWARE, LATEST ADOPTED VERSION, AASHTO-AGC-ARTBA JOINT COOPERATIVE COMMITTEE.
- 3. ALL DIMENSIONS SUBJECT TO MANUFACTURER'S TOLERANCES.
- 4. STANDARDS NO. GR-1 (OR GR-2), SHALL BE USED IN CONJUNCTION WITH THIS STANDARD. SEE THESE STANDARDS FOR ADDITIONAL DETAILS OF COMMON HARDWARE.
- 5. TIGHTEN CABLE ASSEMBLY TO TAUT TENSION AND DOUBLE-NUT BOTH ENDS.
- 6. DIMENSIONS OF PLASTIC AND SYNTHETIC BLOCKOUTS ARE AS SHOWN ON MANUFACTURER'S DRAWINGS.

GUARDRAIL STANDARD

BEAM GUARDRAIL TERMINAL UNIT TYPE G-2

STANDARD NO. GR-10



END LENGTH OF NEED OR FIRST

4:1 SLOPE (SEE NOTE NO. 1)

PAY LIMIT FOR STANDARD

SECTION BEAM GUARDRAIL

TRAFFIC

_30" TYP.

THREE

SIDES/

0

ANCHOR PLATE-

STANDARD SWAGED

FITTING [FCAO1]

12'-6"

PAY LIMITS FOR TERMINAL

UNIT TYPE G-2

SEE DETAIL "A"-

__6′<u>_3</u>″

[FBX16a] HEX BOLT AND NUT

WITH WASHER [FWC16a] ON FRONT

FACE AT NEUTRAL AXIS OF RAIL,

NEUTRAL

(8 REQ'D).

W-BEAM [RWM14a]

AXIS

FACE OF GUARDRAIL AS SHOWN

ON THE TYPICAL SECTION

WOOD OR STEEL

TO MATCH STD.

SECTION

6'-3"

ELEVATION

-END PLATE

-STUD

1" HEX NUTS

[FNX24a]

& WASHER

[FWC24a]


ANCHOR PLATE ASSEMBLY DETAILS

<u>PLAN</u>

POSTS


ELEVATION END SECTION

STRUCTURAL SHAPE STEEL POST & BLOCK
[PWE02] MODIFIED



STANDARD NO. GR-11

BEAM DOUBLE-FACED (WOOD)



STANDARD NO. GR-12

BEAM DOUBLE-FACED (STEEL)


BEAM GUARDRAIL

THRIE BEAM SINGLE-FACED

STANDARD

NO. GR-13

[RTM01a & RTM02a]



NO. GR-15 REVISION DATE


06-16-2010 11-05-2010

*.DGN FILE NAME

GR-15

S





21/2" I.R. (TYP.) 60° (TYP.)

*4 STIRRUP BAR

*6 LOOP BAR (TOP VIEW)

3. EACH BARRIER UNIT SHALL INCLUDE ONE S 3 \times 7.5 AS SHOWN ON THIS PLAN SHEET.


5. LEVELING PADS OR SHIMMING MATERIAL SHALL BE SUBSIDIARY TO THE BARRIER ITEM.


4. SHOP DRAWINGS, SHALL INCLUDE REINFORCING SCHEDULE.

GUARDRAIL STANDARD

CONCRETE BARRIER
PRECAST DOUBLE-FACED
SINGLE SLOPE

STANDARD NO. GR-19





5′-0″

2'-5"

#6 LOOP BAR (TOP VIEW)

#6 LOOP BAR (SIDE VIEW)

9'-0"

#5 BOTTOM LONGITUDINAL BARS

≥ 45°

STIRRUPS

EXTRA ANCHOR

HOLE BARS

LOOP BAR

#4

#6

#6 CONNECTION BARS

| | PORT | ABLE CONCRET | E BARRIER LAY | YOUT |
|---|------------|----------------|-----------------|------------|
| | OPERATING | DESIRABLE | MAXIMUM FLARE | MINIMUM |
| | SPEED | LATERAL OFFSET | RATE * | LENGTH OF |
| | SFEED | FROM T.W. ** | (FREE-STANDING) | PCB SYSTEM |
| | ≤30 MPH | 2 ′ | 7:1 | |
| | 40 MPH | 5 ′ | 9:1 | |
| | 50 MPH | 6.5′ | 11:1 | |
| - | 60 MPH | 8 ′ | 13:1 | |
| | 70 MPH | 10′ | 15 : 1 | |
| | ALL SPEEDS | 15'MAX. *** | | 100′ |

- * MEASURE FLARE FROM A LINE PARALLEL TO THE ROADWAY T.W., WHETHER ON A CURVE OR A TANGENT.
- ** FOR RESTRICTED SITE CONDITIONS, LESSER OFFSETS MAY BE PERMITTED BY THE ENGINEER.
- *** TO REDUCE POTENTIAL FOR HIGH-ANGLE IMPACTS (> 15°)

GUARDRAIL STANDARD

PORTABLE CONCRETE BARRIER

STANDARD NO. GR-23

REQUIRED. 3. EACH BARRIER UNIT SHALL INCLUDE ONE LINKING PIN. 4. LIFTING OPTIONS SHOWN ARE ADVISORY ONLY. IT SHALL BE THE CONTRACTORS' RESPONSIBILITY TO PROVIDE ADEQUATE LIFTING POINTS ON EACH BARRIER.

DATE SHALL BE SHOWN ON BARRIER. ALL EXPOSED EDGES OF CONCRETE SHALL BE CHAMFERED 3/4" UNLESS

11. ADEQUATE PROTECTION SHALL BE MEASURES AS DESCRIBED IN THE MOST CURRENT EDITION OF THE ROADSIDE

MATERIAL NOTES

DESIGN GUIDE AS ADOPTED BY THE DEPARTMENT. PLACING GRANULAR MATERIAL AT THE END(S) OF THE BARRIER

1. BARRIERS SHALL BE LIGHT COLORED CLASS "AA" CONCRETE HAVING A MINIMUM 28 DAY COMPRESSION STRENGTH OF

2. ALL REINFORCING STEEL SHALL BE AASHTO M31 (ASTM-A615) GRADE 60. REINFORCEMENT SHOWN IS THE MINIMUM

4,000 PSI. BARRIERS SHALL HAVE A SMOOTH UNIFORM SURFACE FREE OF DEFECTS AND IRREGULARITIES. CASTING

9. DETAILS FOR ANCHOR BOLTS ARE SHOWN ONLY FOR USE AS REQUIRED OR DIRECTED.

10. TEMPORARY LIGHTING SHALL BE PAID UNDER ITEM 670.10X.

SHALL NOT BE CONSIDERED ADEQUATE PROTECTION.

OTHERWISE NOTED.

5. CONNECTING DEVICES SHALL BE COMPATIBLE WITH OTHER UNITS AND SHALL ALLOW PLACEMENT ON A 110' RADIUS. 6. DELINEATORS SHALL BE ATTACHED TO THE BARRIER USING BOLTS AND ANCHORS OR OTHER APPROVED MECHANICAL CONNECTION, AS SHOWN ON STANDARD NO. DL-1:

FROM © BARRIER TO OUTSIDE EDGE $R = 1 \frac{1}{4}$ (TOP 2" ONLY) $\frac{\text{F6 } ^{3} \text{/4}'' \ \phi}{\text{LOOP BAR}}$ $R = \frac{5}{8}''$ (INSIDE SLOT FULL HEIGHT)

BARRIER END DETAIL SCALE: 3'' = 1' - 0''

PLAN SCALE: $1^{1}/2^{"} = 1^{'}-0^{"}$

#4F4 (PAIRS) 🗘

#4F3 (TYP)

#4F2 (TYP)

1'-0"

SEE BARRIER

SEE SHEET 2 OF 2 FOR REBAR SCHEDULE AND BENDING DIAGRAMS


12′-6″

6 #4F5 U, AS SHOWN IN SECTION B-B


(1 PER ANCHORING PIN SLOT

CENTER AROUND SLOT TYP)

#4F1 (TYP)



VIEW A-A SCALE: $1^{1}/2^{"} = 1^{'}-0^{"}$



<u>ELEVATION</u>

SCALE: $1^{1}/2^{2} = 1^{2} - 0^{2}$

GENERAL NOTES

- 1. THE PORTABLE CONCRETE BARRIER DETAILS, AS SHOWN ON THIS SHEET, ARE IN COMPLIANCE WITH THE REQUIREMENTS OF MANUAL FOR ASSESSING SAFETY HARDWARE (MASH 16).
- (ROADSIDE SAFETY RESEARCH PROGRAM POOLED FUND STUDY NO TPF-5 (114) MAY 2017). THE FREE-STANDING BARRIER HAS BEEN TL-3 CRASH TESTED WITH A 5.28' DYNAMIC DEFLECTION. 2. CONCRETE BARRIER SHALL BE FURNISHED BY THE CONTRACTOR AND PAID AS ITEM 606.417 - PORTABLE CONCRETE BARRIER FOR TRAFFIC CONTROL. CONNECTIONS TO EXISTING BARRIERS, WHEN REQUIRED, SHALL BE SUBSIDIARY TO ITEM 606.417.
- 3. THE CONTRACTOR SHALL FURNISH AND INSTALL APPROVED RETROREFLECTIVE DELINEATORS AT 25-FOOT INTERVALS ALONG THE TOP AND/OR ONE FOOT DOWN THE SIDE OF THE PORTABLE CONCRETE BARRIER, SUBSIDIARY TO ITEM 606,417, MECHANICALLY CONNECT DELINEATOR TO PORTABLE CONCRETE BARRIER, THE COLOR OF DELINEATORS SHALL, IN ALL CASES, CONFORM TO THE COLOR OF EDGE LINE MARKINGS, DELINEATORS SUPPLEMENT, BUT DO NOT REPLACE, THE NEED FOR RETROREFLECTIVE SOLID EDGE LINE MARKINGS,
- 4. UNPROTECTED OPENINGS IN PORTABLE CONCRETE BARRIER WILL NOT BE PERMITTED, UNLESS SPECIFICALLY AUTHORIZED BY THE ENGINEER.
- 5. A 10:1 OR FLATTER FORESLOPE (SUBSIDIARY TO ITEM 606,417) SHALL BE PROVIDED IN ADVANCE OF ALL PORTABLE CONCRETE BARRIER SYSTEMS WITHIN THE CLEAR ZONE FOR ATTENUATION. REFER TO MOST CURRENT EDITION OF THE ROADSIDE DESIGN GUIDE AASHTO ADOPTED BY THE DEPARTMENT, FOR CLEAR ZONE WIDTHS AND ADDITIONAL INFORMATION.
- 6. WHEN PORTABLE CONCRETE BARRIER IS INSTALLED ON BOTH SIDES OF TRAFFIC, THE BEGINNINGS OF THE BARRIER SHALL BE STAGGERED BY AT LEAST 50 FEET.
- 7. PLACE RETROREFLECTORIZED DRUMS OR BARRICADES IN ACCORDANCE WITH THE MUTCD IN ADVANCE OF PORTABLE CONCRETE BARRIER TO WARN AND ALERT DRIVERS.
- 8. ANCHOR PIN DETAILS CAN BE PROVIDED IF REQUIRED OR DIRECTED.
- 9. TEMPORARY LIGHTING SHALL BE PAID UNDER ITEM 670.10X.
- 10. ADEQUATE PROTECTION SHALL BE MEASURES AS DESCRIBED IN THE MOST CURRENT EDITION OF THE ROADSIDE DESIGN GUIDE AS ADOPTED BY THE DEPARTMENT. PLACING GRANULAR MATERIAL AT THE END(S) OF THE BARRIER SHALL NOT BE CONSIDERED ADEQUATE PROTECTION.

MATERIAL NOTES

- 1. BARRIERS SHALL BE LIGHT COLORED CLASS AAA CONCRETE HAVING A MINIMUM 28 DAY COMPRESSION STRENGTH OF 5,000 PSI. BARRIERS SHALL HAVE A SMOOTH UNIFORM SURFACE FREE OF DEFECTS AND IRREGULARITIES. CASTING DATE SHALL BE SHOWN ON BARRIER. ALL EXPOSED EDGES OF CONCRETE SHALL BE CHAMFERED 3/4" UNLESS OTHERWISE NOTED.
- 2. ALL REINFORCING STEEL SHALL BE AASHTO M31 (ASTM-A615) GRADE 60. REINFORCEMENT SHOWN IS THE MINIMUM REQUIRED. ALL REINFORCING STEEL SHALL HAVE A MINIMUM 11/2" CLEAR COVER UNLESS OTHERWISE NOTED.
- 3. EACH BARRIER UNIT SHALL INCLUDE ONE LINKING PIN.
- 4. LIFTING OPTIONS SHOWN ARE ADVISORY ONLY. IT SHALL BE THE CONTRACTORS RESPONSIBILITY TO PROVIDE ADEQUATE LIFTING POINTS ON EACH BARRIER.
- 5. DELINEATORS SHALL BE ATTACHED TO THE BARRIER USING BOLTS AND ANCHORS OF OTHER APPROVED MECHANICAL CONNECTION, AS SHOWN ON STANDARD NO. DL-1.

GUARDRAIL STANDARD


1 ′ -0 ′′


PORTABLE CONCRETE BARRIER (1 OF 2)



STANDARD NO. GR-24

BARRIER WEIGHT APPROXIMATELY = 2.84 TONS/UNIT






JOINING TWO BARRIERS

SCALE: 3" = 1'-0"

ELEVATION


SECTION C-C



BENDING DIAGRAMS SCALE: 11/2" = 1'-0"

<u>#4F5</u>

#4F4 (PAIRS)





ELEVATION

F6 $\frac{3}{4}$ " ϕ LOOP BAR SCALE: 11/2" = 1'-0"

6-LOOP BARS (7'-2" TOTAL LENGTH) (ASTM A36) HOT DIP GALVANIZE AFTER FABRICATION PER ASTM A123 OR AASHTO M 111

2'-11"






GUARDRAIL STANDARD


PORTABLE CONCRETE BARRIER (2 OF 2)


S


GR-24


STANDARD NO. GR-25















NO. HR-1

REVISION DATE 07-13-2001

06-16-2010



— 4" MIN.



06-16-2010

REV. DATE

PLATE

STANDARD

HR-1

12 " MIN.

GENERAL NOTES

1. RAIL SHALL BE $1\frac{1}{4}$ " TO $1\frac{1}{2}$ " O.D. 2. POSTS SHALL BE 11/4" NOMINAL.

SAFETY RAIL WITH GUARD

8'-0" MAX.


3. WHEN THIS DIMENSION EXCEEDS 4'-0" A GUARD IS REQUIRED (SEE PLATE 3).

4. ITEM 606.620X - RAMP HANDRAIL, (MATERIAL).

NHDOT STANDARD PLANS RAMP HANDRAIL

SAFETY RAIL

REV. DATE 06-16-2010 STANDARD



6. ITEM 606.610X - STEP HANDRAIL, (MATERIAL).

8'-0" MAX.

SPACED EVENLY

RAIL-


PARAPET-

30" MAX.

NHDOT STANDARD PLANS

STEP HANDRAIL

30" MAX.




GENERAL NOTES


- 1. FOR DETAILS OF HANDRAIL, SEE PLATE 2.
- 2. FRAME AND CONNECTORS TO HANDRAIL SHALL BE 1" NOMINAL.
- 3. PALINGS SHALL BE 3/4" NOMINAL SPACED 6" ON CENTER.
- 4. ITEM 606.611X STEP HANDRAIL W/ GUARD, (MATERIAL);

606.621X - RAMP HANDRAIL W/ GUARD, (MATERIAL).

NHDOT STANDARD PLANS REV. DATE PLATE 06-16-2010 GUARD FOR HANDRAIL STANDARD HR-1



SAFETY RAIL & SAFETY RAIL WITH GUARD




GENERAL NOTES

- 1. RAIL, POSTS, AND HORIZONTAL MEMBER OF SAFETY RAIL WITHOUT GUARD SHALL BE 11/4" NOMINAL.
- 2. FRAME SHALL BE 1" NOMINAL.
- 3. PALINGS SHALL BE 3/4" NOMINAL SPACED 6" ON CENTER.
- 4. ITEM 606.630X SAFETY RAIL, (MATERIAL); 606.631X -SAFETY RAIL W/ GUARD, (MATERIAL).

NHDOT STANDARD PLANS

REV. DATE PLATE 06-16-2010 HR-1

STANDARD STANDARD NO. HR-1



- 2. BOUNDS TO BE SET IN GRAVEL, 9" ON ALL SIDES OF AND UNDER BOUND.

- 3. WHEN BOUNDING NON-STATE RIGHT-OF-WAY FOR
- CITIES AND TOWNS, USE ITEM 622.4 STONE BOUNDS.
- 4. ITEM 622.2 CONCRETE BOUNDS.

DETAIL OF METAL FORM

ELEVATION

| NHDOT STANDARD PLANS | | | | | | | | | | |
|----------------------|-------|--|--|--|--|--|--|--|--|--|
| CONCRETE | BOUND | | | | | | | | | |

PLAN

| REV. | DATE | PLATE |
|------------|------|----------|
| 06-16-2010 | | 1 |
| | | STANDARD |
| | | HR-2 |

RAISED ISLAND BLOCKOUTS

GENERAL NOTES

1. ISLANDS LESS THAN 16'-0" LONG

CIRCULAR BLOCKOUT LOCATED AT

2. ADDITIONAL SIGNING BLOCKOUTS SHALL BE PROVIDED OPPOSITE ALL DRIVEWAYS AND SIDE ROAD

3. BLOCKOUTS SHALL BE BACKFILLED

BLOCKOUTS AND COLD PATCH ARE

WITH 2" OF COLD PATCH.

ISLAND CONSTRUCTION.

SUBSIDIARY TO THE RAISED

4. IT MAY BE NECESSARY TO ADJUST

THE LOCATION OF BLOCKOUTS TO

PEDESTRIAN CROSSWALK OPENINGS.

AVOID UTILITY STRUCTURES OR


REQUIRE ONLY ONE 18"


THE MIDPOINT.

APPROACHES.

NHDOT STANDARD PLANS REV. DATE PLATE 06-16-2010 STANDARD HR-2

DELINEATION BLOCKOUTS FULL LENGTH OF ISLAND






ELEVATION

SECTION H-H

| | 1 | REINFORCING S' | TEEL |
|------|------------------|--------------------------------------|---------------------------------------------|
| MARK | SIZE | NUMBER | LENGTH (EACH) |
| R | #5 1.043#/FT. | 1 EA. PARAPET 1 EA. FT. OF WIDTH "W" | 8" FOR "A" +13" EACH "B" +16" FOR "C" |
| S | #4 0.668#/FT. | 1 FOR "A" 1 FOR "B" 2 FOR "C" | 6" EA. PARAPET +12"/FT. OF WIDTH "W" |

| NHDOT STANDARD PLANS | REV. DATE | PLATE |
|----------------------|------------|----------|
| | 06-16-2010 | 3 |
| CONCRETE $STEPS$ | | STANDARD |
| | | ─ HR-2 |



TYPICAL TREATMENT OF RAISED ISLAND TO

PROVIDE BLOCKOUTS FOR SIGNING AND DELINEATION

SECTION I-I

NHDOT STANDARD PLANS

MORTAR RUBBLE MASONRY STEPS

| REV. | DATE | PLATE | |
|-----------|------|----------|----|
| 6-16-2010 | | 4 | |
| | | STANDARD | lì |
| | | HR-2 | |

STANDARD NO. HR-2

S

STANDARD

NO. HR-2

REVISION DATE

07-13-2001

06-16-2010

*.DGN FILE NAME

HR-2

W/2 TYPICAL

18" DIAMETER

FOR SIGNING

9" DIAMETER

W/2 TYPICAL


CIRCULAR BLOCKOUT

FOR DELINEATION

(6'-0" MINIMUM)

CIRCULAR BLOCKOUT

(6'-0" MINIMUM)



HW-2

STANDARD

NO. HW-2


REVISION DATE

07-13-2001

06-16-2010

*.DGN FILE NAME

HW-2



SECTIONS ON CENTERLINE FOR PC-4 SIMILAR TO PC-2.

| | MACONDV | MACONDY DED | | | | | | | WIDTH AT | ″L ″ | HEADWALL | |
|-------------------------|------------------------------------------|----------------------------------------------|----------------------------------------|----------------------|---------------------------------|-----------------------|-----------------------|----------------------|----------|--------------------------|--------------------------------------------|---------------------------------|
| DIAMETER D INCHES | MASONRY PER FOOT OF WALL CU. YD | MASONRY PER STANDARD HEADER CU. YD. | STEEL PER STANDARD HEADER LB. | LENGTH OF BARS | EXC. FOR 1' DEPTH CU. YD. | HEADER LENGTH L | HEADER HEIGHT H | FILL HEIGHT FH | "h" | BOTTOM OF HEADER W | MASONRY IN CORNER FRUSTUM CU. YD. | EXC. FOR 1' DEPTH CU. YD. |
| 12 | 0.204 | 0.80 | 11 | 3'-10" | 0.911 | 4'-3" | 3'-9" | 1'-1" | 1'-3" | 1'-11'/4" | 0.31 | 1.195 |
| 15 | 0.240 | 1.32 | 16 | 5-8 | 1.204 | 6-0 | 4-3 | 1-7 | 1-6 | 2-03/4 | 0.38 | 1.588 |
| 18 | 0.260 | 1.66 | 16 | 5-8 | 1.375 | 7-0 | 4-6 | 1-10 | 1-6 | 2-11/2 | 0.42 | 1.700 |
| 24 | 0.301 | 2.41 | 24 | 8-8 | 1.731 | 9-0 | 5-0 | 2-4 | 1-6 | 2-3 | 0.51 | 2.086 |
| 30 | 0.344 | 3.32 | 29 | 10-8 | 2.106 | 11-0 | 5-6 | 2-10 | 1-6 | 2-41/2 | 0.61 | 2.491 |
| 36 | 0.389 | 4.43 | 35 | 12-8 | 2.500 | 13-0 | 6-0 | 3-4 | 1-6 | 2-6 | 0.72 | 2.917 |
| 42 | 0.461 | 6.28 | 42 | 15-2 | 3.082 | 15-9 | 6-9 | 4-1 | 1-9 | 2-81/4 | 0.94 | 3.549 |
| 48 | 0.512 | 7.77 | 47 | 17-2 | 3.520 | 17-9 | 7-3 | 4-7 | 1-9 | $2-9^{3}/_{4}$ | 1.05 | 4.019 |
| 54 | 0.565 | 9.46 | 52 | 19-2 | 3.977 | 19-9 | 7-9 | 5-1 | 1-9 | 2-111/4 | 1.20 | 4.522 |
| 60 | 0.621 | 11.42 | 58 | 21-2 | 4.451 | 21-9 | 8-3 | 5-7 | 1-9 | $3-0^{3}/_{4}$ | 1.37 | 5.024 |
| 66 | 0.689 | 13.68 | 63 | 23-2 | 4.947 | 23-9 | 8-9 | 6-1 | 1-9 | 3-21/4 | 1.55 | 5.559 |
| 72 | 0.740 | 15.79 | 69 | 25′-2″ | 5.460 | 25′-9″ | 9'-3" | 6'-7" | 1'-9" | 3'-33/4" | 1.75 | 6.108 |


NOTE: STEEL QUANTITIES ARE FOR CONCRETE HEADWALLS ONLY


NHDOT STANDARD PLANS HEADWALLS FOR R.C. PIPE:

CONCRETE MORTAR RUBBLE MASONRY

P.C.-3 P.C.-4

| REV. | PLATE | |
|------------|-------|----------|
| 06-16-2010 | | 1 |
| | | STANDARD |
| | | HW-2 |
| | | |
| | | |






ALL LIKE BARS IN EACH HEADWALL ARE THE SAME SIZE. EACH STD. HEADER HAS 4 A, B & C-BARS, AND 2 D-BARS.

| | | | | | | | | 23 | I SLUP | E | | | | | | | | | | |
|-------------|------------------|--------------|---------------------------------|-------|------------|--------|-------|--------|---------|-------|-------|--------|------|-------------------|------------------|-------------------|-----------|--------|------|--|
| DIAMETER | QUANTIT | IES P | | ļ | DIMENSIONS | | | | | | | | | REINFORCING STEEL | | | | | | |
| D INCHES | CONC. CU. YD. | STEEL LB. | EXC. FOR 1' DEPTH CU. YD. | A | В | С | E | F | G | Н | I | J | SIZE | A BARS | LEN B BARS | IGTH C BARS | D BARS | | Dή | |
| 24 | 1.50 | 32 | 1.36 | 2'-3" | 5′-1″ | 6'-0" | 2'-5" | 1'-11" | 1′-9″ | 4'-6" | 4'-0" | 3'-6" | #4 | 4'-9" | 2'-7" | 2'-5" | | 2'-4" | 1'-7 | |
| 30 | 2.01 | 37 | 1.63 | 2-9 | 5-7 | 6-10 | 3-0 | 1-11 | 2-3 | 5-0 | 4-6 | 3-10 | #4 | 5-3 | 3-3 | 3-1 | 4-7 | 2-7 | 2-0 | |
| 36 | 2.62 | 42 | 1.88 | 3-3 | 6-1 | 7-8 | 3-7 | 2-0 | 2-9 | 5-6 | 5-0 | 4-1 | #4 | 5-9 | 3-10 | 3-6 | 5-2 | 2-8 | 2-6 | |
| 42 | 3.31 | 47 | 2.18 | 3-9 | 6-7 | 8-6 | 4-2 | 2-1 | 3-3 | 6-0 | 5-6 | 4-4 | #4 | 6-3 | 4-5 | 4-1 | 5-10 | 2-10 | 3-0 | |
| 48 | 4.11 | 123 | 2.42 | 4-4 | 7-2 | 9-5 | 4-10 | 2-2 | 3-9 | 6-6 | 6-0 | 4-8 | #6 | 6-10 | 5-1 | 4-8 | 7-8 | 4-0 | 3-8 | |
| 60 | 5.98 | 146 | 3.04 | 5-4 | 8-2 | 11-0 | 6-0 | 2-4 | 4-8 | 7-6 | 7-0 | 5-3 | #6 | 7-10 | 6-3 | 5-8 | 8-11 | 4-6 | 4-5 | |
| 72 | 8.33 | 171 | 3.69 | 6'-5" | 9'-3" | 12′-9″ | 7'-3" | 2'-5" | 5′-8″ | 8'-6" | 8'-0" | 5′-10″ | #6 | 8′-11″ | 7'-6" | 6'-9" | 10'-4" | 4'-10" | 5′-6 | |
| | | | | | | | | 4 | 1:1 SLO | PE | | | | | | | | | | |
| 24 | 1.93 | 37 | 1.60 | 2'-3" | 5'-1" | 6'-2" | 3'-2" | 2'-0" | 2'-6" | 4'-6" | 4'-3" | 3'-10" | #4 | 4'-9" | 3'-6" | 3'-2" | 4'-10" | 2'-7" | 2'-3 | |
| 30 | 2.62 | 44 | 1.93 | 2-9 | 5-7 | 7-0 | 3-11 | 2-1 | 3-2 | 5-0 | 4-9 | 4-3 | #4 | 5-3 | 4-3 | 3-10 | 5-9 | 2-10 | 2-1 | |
| 36 | 3.44 | 50 | 2.25 | 3-3 | 6-1 | 7-10 | 4-8 | 2-2 | 3-10 | 5-6 | 5-3 | 4-7 | #4 | 5-9 | 5-1 | 4-7 | 6-5 | 2-10 | 3-7 | |
| 42 | 4.39 | 56 | 2.60 | 3-9 | 6-7 | 8-8 | 5-6 | 2-3 | 4-5 | 6-0 | 5-9 | 5-0 | #4 | 6-3 | 5-10 | 5-3 | 7-4 | 3-0 | 4-4 | |
| 48 | 5.49 | 144 | 2.96 | 4-4 | 7-2 | 9-7 | 6-3 | 2-4 | 5-1 | 6-6 | 6-3 | 5-4 | #6 | 6-10 | 6-6 | 6-0 | 9-2 | 4-1 | 5-1 | |
| 60 | 8.10 | 172 | 3.70 | 5-4 | 8-2 | 11-3 | 7-9 | 2-6 | 6-5 | 7-6 | 7-3 | 6-1 | #6 | 7-10 | 8-0 | 7-6 | 10-8 | 4-3 | 6-5 | |
| 72 | 11.36 | 202 | 4.51 | 6'-5" | 9'-3" | 13'-0" | 9'-4" | 2'-8" | 7′-8″ | 8'-6" | 8'-3" | 6'-9" | #6 | 8'-11" | 9'-6" | 9'-1" | 12'-3" | 4'-6" | 7'-9 | |

| [12 11.36 202 4.51 6 -5 9 -5 15 -0 9 -4 2 -6 1 -6 6 -6 6 -5 6 -9 #6 6 -11 | 9 -6 9 -1 12 -3 4 -6 1 | _9 |
|---------------------------------------------------------------------------------------------|--------------------------------|----------|
| NHDOT STANDARD PLANS | REV. DATE | PLATE |
| | 06-16-2010 | 3 |
| CONCRETE HEADWALLS WITH 45° WINGS FOR PIPES OTHER THAN R.C. P.C5 | | STANDARD |
| | | HW-2 |



P.C.-7

CONCRETE HEADWALLS WITH 45° WINGS FOR R.C. PIPE

| DIA. | QUANTIT | IES P | ER HEADER | | DIMENSIONS | | | | | | | | | | REINFORCING STEEL | | | | | | | | |
|--------|---------|-------|-----------|----------------|------------|---------------------------------------|-----------------|--------|--------|-------|------------|----------------|-------|-------|-------------------|----------------|----------------|-----------|-----------|-------|--------------|--|--|
| D | CONC. | STEEL | EXC. FOR | | | | | | | | l <u>.</u> | | | 77 | | | LENG | STH | | D-BA | | | |
| INCHES | CU. YD. | LB. | 1' DEPTH | A | В | C | E | F | G | H | 1 | J | K | D/2 | SIZE | A BARS | B BARS | C BARS | D BARS | a | PAI | | |
| 24 | 2.44 | 46 | | 6'-0" | 8′-10″ | 10'-0" | 3'-0" | 1'-11" | 2'-3" | 5′-0″ | 4′-6″ | 3′-10″ | 1′-6″ | 1′-0″ | #4 | 8'-6" | 3'-2" | 3'-0" | 4'-8" | 2′-5″ | | | |
| 30 | 3.18 | 53 | 2.28 | 7-5 | 10-3 | 11-9 | 3-7 | 2-0 | 2-9 | 5-6 | 5-0 | 4-1 | 1-6 | 1-3 | #4 | 9-11 | 3-9 | 3-7 | 5-3 | 2-6 | 2-9 | | |
| 36 | 3.99 | 61 | 2.69 | 8-10 | 11-8 | 13-7 | 4-2 | 2-1 | 3-3 | 6-0 | 5-6 | 4-4 | 1-6 | 1-6 | #4 | 11-4 | 4-3 | 4-1 | 5-10 | 2-8 | 3-2 | | |
| 42 | 5.43 | 161 | 3.22 | 10-3 | 13-1 | 15-6 | 5-1 | 2-2 | 4-0 | 6-9 | 6-3 | 4-10 | 1-9 | 1-9 | #6 | 12-9 | 5-3 | 4-11 | 7-10 | 3-10 | 4-0 | | |
| 48 | 6.53 | 180 | 3.64 | 11-8 | 14-6 | 17-3 | 5-9 | 2-3 | 4-6 | 7-3 | 6-9 | 5-1 | 1-9 | 2-0 | #6 | 14-2 | 5-11 | 5-7 | 8-5 | 3-10 | 4-7 | | |
| 54 | 7.76 | 197 | 4.00 | 13-1 | 15-11 | 19-1 | 6-4 | 2-4 | 5-0 | 7-9 | 7-3 | 5-4 | 1-9 | 2-3 | #6 | 15-7 | 6-7 | 6-1 | 9-2 | 4-1 | 5-1 | | |
| 60 | 9.10 | 214 | 4.45 | 14-6 | 17-4 | 20-10 | 6-11 | 2-5 | 5-6 | 8-3 | 7-9 | 5-8 | 1-9 | 2-6 | #6 | 17-0 | 7-1 | 6-8 | 9-9 | 4-1 | 5-8 | | |
| 66 | 10.56 | 232 | 4.84 | 15-11 | 18-9 | 22-5 | 7-6 | 2-6 | 6-0 | 8-9 | 8-3 | 5-11 | 1-9 | 2-9 | #6 | 18-5 | 7-8 | 7-3 | 10-5 | 4-2 | 6-3 | | |
| 72 | 12.28 | 249 | 5.25 | 17'-4" | 20'-2" | 24'-2" | 8'-2" | 2'-7" | | | 8'-9" | 6'-3" | 1′-9″ | 3′-0″ | #6 | 19'-10" | 8'-3" | 7′–10″ | 11'-0" | 4'-3" | 6′-9″ | | |
| | • | 1 | | | | , , , , , , , , , , , , , , , , , , , | | | 1 SLOF | | | , , | | | | , , | , , | | | | | | |
| 24 | 3.05 | 53 | 2.29 | | 8'-10" | 10'-0" | 3'-11" | 2'-1" | 3'-2" | 5'-0" | 4'-9" | 4'-3" | 1′-6″ | 1′-0″ | #4 | 8'-6" | 4'-3" | 4'-0" | 5'-6" | | | | |
| 30 | 3.92 | 61 | 2.70 | 7-5 | 10-3 | 11-9 | 4-8 | 2-2 | 3-9 | 5-6 | 5-3 | 4-7 | 1-6 | 1-3 | #4 | 9-11 | 5-0 | 4-8 | 6-3 | 2-8 | 3-7 | | |
| 36 | 5.09 | 70 | 3.15 | 8-10 | 11-8 | 13-7 | 5-5 | 2-3 | 4-5 | 6-0 | 5-9 | 5-0 | 1-6 | 1-6 | #4 | 11-4 | 5-9 | 5-4 | 7-1 | 2-10 | 4-3 | | |
| 42 | 6.97 | 185 | 3.78 | 10-3 | 13-1 | 15-6 | 6-7 | 2-5 | 5-4 | 6-9 | 6-6 | 5-6 | 1-9 | 1-9 | #6 | 12-9 | 6-11 | 6-5 | 9-3 | 4-0 | 5-3 | | |
| 48 | 8.44 | 204 | 4.24 | 11-8 | 14-6 | 17-3 | 7-4 | 2-6 | 6-0 | 7-3 | 7-0 | 5-11 | 1-9 | 2-0 | #6 | 14-2 | 7-8 | 7-1 | 10-1 | 4-2 | 5-11 | | |
| 54 | 10.13 | 225 | 4.74 | 13-1 | 15-11 | 19-1 | 8-2 | 2-7 | 6-9 | 7-9 | 7-6 | 6-3 | 1-9 | 2-3 | #6 | 15-7 | 8-6 | 7-10 | 10-11 | 4-3 | 6-8 | | |
| 60 | 11.90 | 245 | 5.23 | 14-6 | 17-4 | 20-10 | 8-11 | 2-8 | 7-4 | 8-3 | 8-0 | 6-7 | 1-9 | 2-6 | #6 | 17-0 | 9-3 | 8-8 | 11-9 | 4-4 | 7-5 | | |
| 66 | 13.87 | 266 | 5.75 | 15-11 | 18-9 | 22-5 | 9-8 | 2-9 | 8-0 | 8-9 | 8-6 | 7-0 | 1-9 | 2-9 | #6 | 18-5 | 10-0 | 9-5 | 12-8 | 4-7 | 8-1 | | |
| 72 | 16.13 | 283 | 6.29 | <u> 17'-4"</u> | 20'-2" | 24'-2" | <u> 10' –6"</u> | 2'-10" | 8'-8" | 9'-3" | 9'-0" | <i>('</i> −4 " | 1′-9″ | 3′-0″ | #6 | <u>19'-10"</u> | <u>10'-10"</u> | 9′-9″ | 13'-5" | 4′-8″ | <u>8′-9″</u> | | |

| NHDOT STANDARD PLANS | | | | | | | | | | | | | |
|------------------------------------------------------|------|--|--|--|--|--|--|--|--|--|--|--|--|
| | | | | | | | | | | | | | |
| CONCRETE HEADWALLS WITH 45° WINGS FOR TWIN R.C. PIPE | P.C9 | | | | | | | | | | | | |

REV. DATE PLATE -16-2010 STANDARD HW-2

STANDARD NO. HW-2



STANDARD

NO. HW-3


REVISION DATE

07-13-2001

06-16-2010

*.DGN FILE NAME

HW-3



EXCAVATION BETWEEN PIPES INCLUDED IN STRUCTURE EXCAVATION

DIMENSIONS SHOWN ARE TO PAYMENT LINES. MASONRY TO BE STEPPED OUTSIDE PAYMENT LINES ON SLOPING FACES.

END ELEVATION

 $\underline{UNDERDRAIN}$

<u>PLAN</u>

-SYMMETRICAL ABOUT $oldsymbol{\mathcal{C}}$

4" WEEPER IN

OUTLET HEADWALL

(SUBSID.)

2:1 SLOPE (FOR 3:1 AND 4:1 SLOPES SEE PLATE 2)

(2) (2) (4)

ROUND SLOPE (SEE DETAIL

ON STANDARD NO. HW-1,

PLATE NO. 4)

<u>__1.5:1</u>

SIDE ELEVATION

| DIAMETER | QUANTITIES IN CUBIC YARDS, PER HEADER | | | | | DIMENSIONS | | | | | | | | |
|----------|---------------------------------------|----------------------------------------|------------------------------|----------------------------------------------|------------|------------|-------|--------|--------|--------|-------|-------|--------|-------|
| D INCHES | M.R.M. V=5′ | M.R.M. PER FOOT ADD. LENGTH V=5' | EXC. FOR 1' DEPTH V=5' | EXC. PER FOOT ADD. LENGTH 1 FOOT DEPTH | A V=5 ′ | B V=5 ' | С | E | F | G | Н | I | J | K |
| 24 | 4.40 | 0.300 | 3.08 | 0.157 | 10'-0" | 12'-10" | 2'-3" | 2'-11" | 1'-11" | 0'-6" | 5'-0" | 4'-6" | 3'-10" | 1'-6" |
| 30 | 5.56 | 0.348 | 3.60 | 0.163 | 11-2 | 14-0 | 2-5 | 3-6 | 2-0 | 0-5 | 5-6 | 5-0 | 4-1 | 1-6 |
| 36 | 6.71 | 0.389 | 4.03 | 0.167 | 12-4 | 15-2 | 2-6 | 4-1 | 2-1 | 0-4 | 6-0 | 5-6 | 4-4 | 1-6 |
| 42 | 8.75 | 0.458 | 4.68 | 0.173 | 13-6 | 16-4 | 2-8 | 5-0 | 2-2 | 0-3 | 6-9 | 6-3 | 4-10 | 1-9 |
| 48 | 10.43 | 0.515 | 5.29 | 0.179 | 14-8 | 17-6 | 2-10 | 5-8 | 2-3 | 0-2 | 7-3 | 6-9 | 5-1 | 1-9 |
| 54 | 12.07 | 0.562 | 5.85 | 0.182 | 15-10 | 18-8 | 2-11 | 6-3 | 2-4 | 0-1 | 7-9 | 7-3 | 5-4 | 1-9 |
| 60 | 14.09 | 0.624 | 6.47 | 0.188 | 17-0 | 19-10 | 3-1 | 6-10 | 2-5 | 0-1 | 8-3 | 7-9 | 5-8 | 1-9 |
| 66 | 16.05 | 0.675 | 7.03 | 0.191 | 18-2 | 21-0 | 3-2 | 7-5 | 2-6 | 0-0 | 8-9 | 8-3 | 5-11 | 1-9 |
| 72 | 18.41 | 0.742 | 7.63 | 0.198 | 19'-4" | 22'-2" | 3'-4" | 8'-1" | 2'-7" | -0′-1″ | 9'-3" | 8'-9" | 6'-3" | 1'-9" |

NHDOT STANDARD PLANS MORTAR RUBBLE MASONRY HEADWALLS WITH 45° WINGS FOR TWIN R. C. PIPES P.C.-10

NHDOT STANDARD PLANS

UNDERDRAIN HEADWALLS & UNDERDRAIN "L" HEADWALLS

<u>UNDERDRAIN</u>

1:4

BATTER

| REV. | PLATE | |
|------------|-------|----------|
| 06-16-2010 | | 1 |
| | | STANDARD |
| | | HW-3 |

| | 1 00 10 201 | ∪ | |
|---------|--------------------------|----------------|------------------|
| | | | STANDARD HW-3 |
| | | | |
|). UH-1 | $\underline{UNDERDRAIN}$ | CONCRETE | NO. UL-1 |
|). UH-2 | "L"HEADWALL | MOR. RUB. MAS. | NO. UL-3 |
| ES. | | | |


REV. DATE

06-16-2010

PLATE

STANDARD

HW-3



| DIAMETER | QU | ANTITIES IN CUBIC | YARDS, PER | HEADER | DIMENSIONS | | | | | | | | | |
|----------------------|-----------------|----------------------------------------|------------------------------|----------------------------------------------|------------|-----------|-------|-------|-------|-------|-------|--------|--------|-------|
| DIAMETER D INCHES | M.R.M. V=1.5 | M.R.M. PER FOOT ADD. LENGTH V=5' | EXC. FOR 1' DEPTH V=5' | EXC. PER FOOT ADD. LENGTH 1 FOOT DEPTH | A V=5 ′ | B v=5′ | С | E | F | G | Н | I | J | K |
| 24 | 4.77 | 0.300 | 3.27 | 0.157 | 10'-0" | 12′-10″ | 2'-3" | 3'-6" | 2'-0" | 0'-6" | 5'-0" | 4'-8" | 4'-1" | 1'-6" |
| 30 | 6.08 | 0.348 | 3.83 | 0.163 | 11-2 | 14-0 | 2-5 | 4-3 | 2-1 | 0-6 | 5-6 | 5-2 | 4-5 | 1-6 |
| 36 | 7.38 | 0.389 | 4.34 | 0.167 | 12-4 | 15-2 | 2-6 | 4-11 | 2-2 | 0-4 | 6-0 | 5-8 | 4-9 | 1-6 |
| 42 | 9.72 | 0.458 | 5.06 | 0.173 | 13-6 | 16-4 | 2-8 | 6-0 | 2-4 | 0-3 | 6-9 | 6-5 | 5-3 | 1-9 |
| 48 | 11.59 | 0.515 | 5.69 | 0.179 | 14-8 | 17-6 | 2-10 | 6-8 | 2-5 | 0-3 | 7-3 | 6-11 | 5-7 | 1-9 |
| 54 | 13.52 | 0.562 | 6.27 | 0.182 | 15-10 | 18-8 | 2-11 | 7-5 | 2-6 | 0-2 | 7-9 | 7-5 | 5-11 | 1-9 |
| 60 | 15.80 | 0.624 | 6.92 | 0.188 | 17-0 | 19-10 | 3-1 | 8-1 | 2-7 | 0-1 | 8-3 | 7-11 | 6-3 | 1-9 |
| 66 | 18.10 | 0.675 | 7.58 | 0.191 | 18-2 | 21-0 | 3-2 | 8-10 | 2-8 | 0-0 | 8-9 | 8-5 | 6-7 | 1-9 |
| 72 | 20.80 | 0.742 | 8.26 | 0.198 | 19'-4" | 22'-2" | 3'-4" | 9'-6" | 2'-9" | 0-0 | 9'-3" | 8′-11″ | 6′-11″ | 1'-9" |

3:1 SLOPE

| | | | | | 4:1 SLO | PE | | | | | | | | |
|-------------------------|-----------------|----------------------------------------|------------------------------|----------------------------------------------|------------|------------|-------|--------|--------|-------|-------|-------|-------|-------|
| DIAMETER | QU | ANTITIES IN CUBIC | YARDS, PER | HEADER | | | | | DIMENS | IONS | | | | |
| DIAMETER D INCHES | M.R.M. V=1.5 | M.R.M. PER FOOT ADD. LENGTH V=5' | EXC. FOR 1' DEPTH V=5' | EXC. PER FOOT ADD. LENGTH 1 FOOT DEPTH | A V=5 ' | B v=5 ' | С | E | F | G | Н | I | J | K |
| 24 | 5.01 | 0.300 | 3.39 | 0.157 | 10'-0" | 12'-10" | 2'-3" | 3'-10" | 2'-1" | 0'-6" | 5'-0" | 4'-9" | 4'-3" | 1'-6" |
| 30 | 6.37 | 0.348 | 3.94 | 0.163 | 11-2 | 14-0 | 2-5 | 4-7 | 2-2 | 0-6 | 5-6 | 5-3 | 4-7 | 1-6 |
| 36 | 7.79 | 0.389 | 4.47 | 0.167 | 12-4 | 15-2 | 2-6 | 5-4 | 2-3 | 0-4 | 6-0 | 5-9 | 5-0 | 1-6 |
| 42 | 10.30 | 0.458 | 5.25 | 0.173 | 13-6 | 16-4 | 2-8 | 6-6 | 2-5 | 0-3 | 6-9 | 6-6 | 5-6 | 1-9 |
| 48 | 12.34 | 0.515 | 5.90 | 0.179 | 14-8 | 17-6 | 2-10 | 7-3 | 2-6 | 0-3 | 7-3 | 7-0 | 5-11 | 1-9 |
| 54 | 14.46 | 0.562 | 6.52 | 0.182 | 15-10 | 18-8 | 2-11 | 8-1 | 2-7 | 0-2 | 7-9 | 7-6 | 6-3 | 1-9 |
| 60 | 16.85 | 0.624 | 7.23 | 0.188 | 17-0 | 19-10 | 3-1 | 8-10 | 2-8 | 0-1 | 8-3 | 8-0 | 6-7 | 1-9 |
| 66 | 19.41 | 0.675 | 7.89 | 0.191 | 18-2 | 21-0 | 3-2 | 9-7 | 2-9 | 0-0 | 8-9 | 8-6 | 7-0 | 1-9 |
| 72 | 22.26 | 0.742 | 8.62 | 0.198 | 19'-4" | 22'-2" | 3'-4" | 10'-5" | 2'-10" | 0-0 | 9'-3" | 9'-0" | 7'-4" | 1'-9" |

| NHDOT STANDARD PLANS | REV. | PLATE | |
|------------------------------------------------|------------|-------|----------|
| MORTAR RUBBLE MASONRY HEADWALLS WITH 45° WINGS | 06-16-2010 | | 2 |
| FOR TWIN R. C. PIPES P.C10 | | | STANDARD |
| FOR TWIN R. C. FIFES F.C. 10 | | | HW-3 |

NHDOT STANDARD PLANS

REV. DATE PLATE 06-16-2010 STANDARD HW-3

STANDARD NO. HW-3

MAILBOX STANDARD

MAILBOX SUPPORT

ASSEMBLY DETAILS

STANDARD


NO. MB-1

6. FOR ADDITIONAL INFORMATION, REFER TO THE LATEST ADOPTED EDITION OF THE AASHTO -

7. CONTACT THE LOCAL POSTMASTER FOR OFFSET AND HEIGHT FROM EP WHEN INSTALLING IN

UNCURBED AREAS.

ROADSIDE DESIGN GUIDE - CHAPTER 11, ERECTING MAILBOXES ON STREETS AND HIGHWAYS.




NO. PL-2

REVISION DATE 07-13-2001 06-16-2010


*.DGN FILE NAME

PL-2




NOTE:


TYPICAL BED PLANT SPACING




GROUNDCOVER BED PLANTING



SEEDLINGS (EVERGREEN) OR WETLAND PLUG PLACEMENT





3 HUB STAKES AND GUYS FOR

CAL. AND EVERGREEN TREES OVER

DECIDUOUS TREES OVER 4"

1) REMOVE SUCKER SHOOTS AT BASE OF TREE. (2) MAKE CLEAN CUTS ON OLD STUBS, IF PRESENT. (DO NOT FLUSH CUT) (3) REMOVE ENTIRE SUPPLY OF TWIGS AND BUDS ON TRUNK. (4) REMOVE LOWER BRANCH WHERE AN OVERLYING BRANCH OCCUPIES ABOUT THE SAME AREA. 5) SHAPE TREE BY REMOVING INJURED, DEAD AND MISSHAPED BRANCHES. (6) REMOVE CROSS BRANCHES AND THOSE DEVELOPING INTO SECONDARY LEADERS. NOTE:

BRANCHES IN DOTTED LINES INDICATE THOSE

TO BE REMOVED.

NOTE:

TREE PRUNING

PLANTING STANDARD

PLANTING DETAILS

LEGEND

DIVERGING (OR CONVERGING) LINES FOR PAINTED ISLANDS

{}SSL()* = {SIZE IN INCHES} SINGLE SOLID LINE (COLOR W=WHITE, Y=YELLOW)
{}DSL()* = {SIZE IN INCHES} DOUBLE SOLID LINE (COLOR W=WHITE, Y=YELLOW)
{}SSB()* = {SIZE IN INCHES} SINGLE SOLID W/ BROKEN LINE (COLOR W=WHITE, Y=YELLOW)
{}SBL()* = {SIZE IN INCHES} SINGLE BROKEN LINE (COLOR W=WHITE, Y=YELLOW)
{}DBL()* = {SIZE IN INCHES} DOUBLE BROKEN LINE (COLOR W=WHITE, Y=YELLOW)

*EXAMPLE: A 4" SINGLE SOLID LINE WHITE = 4" SSLW

PAVEMENT MARKING STANDARD

LAYOUT DETAILS

07-13-2001
02-26-2010

*.DGN FILE NAME

STANDARD

REVISION DATE

NO. PM-1

ANDARD PLANS

Wew Humpshire

PAVEMENT MARKING STANDARD

LINE OR WITH A FULL CYCLE OF BROKEN LINE

(IF APPROPRIATE).

TOLERANCES FOR PAVEMENT
MARKING LINES

STANDARD NO. PM-2


STANDARD

REVISION DATE 07-13-2001 02-26-2010

*.DGN FILE NAME PM-2

NO. PM-2

NOT TO SCALE - REFERENCE: MUTCD FIGURE 3B-9(A)



NOT TO SCALE - REFERENCE: MUTCD FIGURE 3B-8(A)

GENERAL NOTES

- 1. ALL RAMPS WITH A MINIMUM ROADWAY WIDTH OF 20' SHALL RECEIVE BOTH WHITE EDGE LINE AND YELLOW MEDIAN LINE WHETHER THE RAMP HAS RAISED CURB OR NOT.
- 2. THE EDGE AND MEDIAN LINE MARKINGS FOR FREEWAY RAMPS WILL BE A MINIMUM OF 24" FROM CENTERLINE TO THE FACE OF CURB OR EDGE OF PAVEMENT. MEDIAN LINE MARKINGS FOR ALL OTHER RAMPS WILL BE A MINIMUM OF 30" FROM THE CURB OR EDGE OF PAVEMENT.
- 3. THE MINIMUM DISTANCE BETWEEN THE EDGE AND MEDIAN LINES FOR RAMPS SHALL BE 14'. THE MEDIAN LINE ON A RAMP SHALL CONNECT WITH THE GORE MARKING. THE EDGELINE SHALL CONNECT WITH THE MAINLINE EDGELINE TO PROVIDE A CONTINUOUS LINE.
- 4. SEE PAVEMENT MARKING PLANS OR OTHER PROJECT DOCUMENT PLANS FOR PROJECT SPECIFIC DESIGN DIMENSIONS.
- 5. ALL DOTTED LANE LINES FOR ACCELERATION/DECELERATION LANES SHALL RUN THE FULL LENGTH OF EACH LANE AND CONTINUE THROUGH THE TRANSITION TAPER.

LEGEND

(T) THERMOPLASTIC


6"SSLW(T)* IF ASSOCIATED WITH A PARTIAL INTERCHANGE, MAY BE PAINT.



ARROWS SHOWN ON THIS SHEET INDICATE DIRECTION OF TRAFFIC ONLY.

| POSTED SPEED (mph) | L |
|--------------------|---------------------|
| ≤ 40 | WS ² /60 |
| ≥ 45 | WS |

- L = TRANSITION TAPER
- W = WIDTH OF OFFSET (FEET)
- S = POSTED SPEED LIMIT OR DESIGN SPEED (MPH)



12"SSLW(T)

PAVEMENT MARKING STANDARD

SEE 'GORE LINE OFFSET'

- PHYSICAL

GORE


DETAIL

DIVIDED HIGHWAY PARALLEL RAMP MARKINGS NO. PM-3 REVISION DATE 07-13-2001 02-26-2010 11-05-2010

STANDARD

02-22-2021

*.DGN FILE NAME





NOT TO SCALE - REFERENCE: MUTCD FIGURE 3B-9(B)


SHALL RUN THE FULL LENGTH OF THE RAMP OPENING.

PAVEMENT MARKING STANDARD

DIVIDED HIGHWAY TAPERED RAMP MARKINGS







W = WIDTH OF OFFSET (feet)
S = POSTED SPEED LIMIT (mph)

ws ²/60


POSTED SPEED (mph)

≤ 40


≥ 45

PAINTED ISLAND WITH LEFT TURN LANE

| DECELENATION TRANSI | I I OIV I AI L |
|---------------------|----------------|
| POSTED SPEED (mph) | LENGTH (ft) |
| ≤ 40 | 75 |
| ≥ 45 | 100 |
| | |



SINGLE LANE, TWO-WAY LEFT TURN WITH LEFT TURN ONLY



STRIPING AT ENDS OF RAISED ISLANDS


* ARROWS SHOWN ON THIS SHEET INDICATE DIRECTION OF TRAFFIC ONLY.

GENERAL NOTES

- 1. SEE STANDARD NO. PM-8 FOR LAYOUT OF WORDS AND SYMBOLS WITHIN TURN LANES.
- 2. SEE RAISED ISLAND BLOCKOUTS ON STANDARD HR-2

PAVEMENT MARKING STANDARD

PAINTED ISLAND DETAILS



| STATE OF NEW HAMPSHIRE |
|--------------------------------------------------|
| STATE OF NEW TIMES STATE |
| DEPARTMENT OF TRANSPORTATION . BUREAU OF TRAFFIC |
| |

INTERSECTION DETAILS

REVISION DATE DGN STATE PROJECT NO. SHEET NO. TOTAL SHEETS

O1/10/20 _ _ _ _ _ _

WORD AND SYMBOL LANE LAYOUT

NOT TO SCALE

25 ft TO 75 ft LANE LINE 100 ft LANE


VARIES

*

ONLY

100 ft LANE LINE


150 ft LANE LINE



* SEE NOTE NO. 7


GENERAL NOTES

- 1. WORDS AND SYMBOLS SHALL BE CENTERED LATERALLY WITHIN THE LANE. THE LONGITUDINAL DIMENSION SHALL BE PARALLEL TO THE LANE.
- 2. LONGITUDINAL SPACING BETWEEN SUCCESSIVE WORDS AND/OR SYMBOLS IN TURN LANES SHOULD BE IN EVEN INCREMENTS OF AT LEAST 4 TIMES AND NO GREATER THAN 10 TIMES THE HEIGHT OF THE LARGEST CHARACTER.
- 3. LANE LINES LONGER THAN 75' SHALL BE LAYED OUT IN MULTIPLES OF 50'.
- 4. LANE LINES DESIGNED TO ACCOMMODATE A CALCULATED QUEUE SHALL BE ROUNDED UP TO THE NEAREST 50'.
- 5. TO COMPLETE ARROW AND "ONLY" LAYOUT FOR LANE LENGTHS GREATER THAN 350': (LENGTH OF LANE LINE MINUS 48') / NUMBER OF INCREMENTS. STENCIL SERIES SHALL BEGIN AND END WITH AN ARROW.
- 6. THE STOP LINE MAY NOT BE PRESENT.
- 7. SEE THE PAVEMENT MARKING PLANS FOR THE APPROPRIATE LAYOUT, INCLUDING IF THROUGH ARROWS ARE REQUIRED.
- 8. WORDS, LANE LINES AND SYMBOLS SHALL BE THERMOPLASTIC (T).
- 9. THE SOLID LANE LINE SHALL BE A MINIMUM OF 25'.




OR CURB LINE.

300 ft LANE LINE



350 ft LANE LINE




STATE OF NEW HAMPSHIRE


DEPARTMENT OF TRANSPORTATION . BUREAU OF TRAFFIC

 $WORD \ AND \ SYMBOL \ LANE \ LAYOUT$

REVISION DATE DGN STATE PROJECT NO. SHEET NO. TOTAL SHEETS

O1/10/20 _ _ _ _ _






MAINLINE

EDGE OF PAVEMENT

4"SSLW

CENTERLINE AND EDGELINE "CUTS" AT SIDE ROAD W/ TURN LANES



MAINLINE

4"SSLW

EDGE OF PAVEMENT

GENERAL NOTES

- 1. EDGELINE DETAILS SHOWN ARE FOR MAINLINE ROADWAYS WITHOUT TURN LANES. THE PRESENCE OF TURN LANES MAY REQUIRE DIFFERENT EDGELINE TREATMENTS.
- 2. EDGELINES ON SIDE ROADS, WHEN CALLED FOR, SHALL FOLLOW THE ABOVE MAINLINE TYPICALS. EDGELINES SHALL NOT BE CONTINUOUS AROUND THE MAINLINE/ SIDE ROAD RADIUS. EDGELINES SHALL END AT STOP BARS.
- 3. CENTERLINE AND EDGELINE SHALL BE CONTINUOUS PAST RESIDENTIAL DRIVEWAYS. CENTERLINE AND EDGELINE SHALL BREAK FOR COMMERCIAL DRIVES W/TRAFFIC CONTROLS, MINOR SIDE ROADS OR PRIVATE ROAD INTERSECTIONS.
- 4. LOCATION OF THE STOP LINE MAY VARY DUE TO INTERSECTION SIGHT DISTANCE AND VEHICLE TURNING RADUIS, AND MAY NOT ALWAYS COINCIDE WITH THE LOCATION OF THE STOP SIGN.
- 5. IF THERE IS NO EDGELINE, END STOP BAR 12" FROM EDGE OF PAVEMENT.
- 6. STOP BARS, WORDS, LANE LINES, SYMBOLS AND ARROWS SHALL BE THERMOPLASTIC (T).

PAVEMENT MARKING STANDARD

PAVEMENT MARKINGS
AT MINOR INTERSECTIONS

STANDARD NO. PM-9


07-13-2001 02-26-2010

*.DGN FILE NAME

STANDARD PLANS

New Hampshire

Department of Transportation



INTERNATIONAL SYMBOL OF ACCESSIBILITY

PAY QUANTITY FOR EACH ACCESSIBLE PAVEMENT MARKING SYMBOL 2.58f+2.

GENERAL NOTES

- 1. VAN ACCESS AISLE SHALL BE A MINIMUM 8' WIDE. R7-8a SIGN WILL BE ADDED TO VAN ACCESSIBLE PARKING SIGN R7-8.
- 2. ARROW ON THIS SHEET INDICATE DIRECTION OF TRAFFIC ONLY.
- 3. (T) = THERMOPLASTIC PAVEMENT MARKING.

PAVEMENT MARKING STANDARD

ACCESSIBLE PARKING DETAIL

TRAFFIC *

4″ SSLW(T) 12' MIN. = 11' LANE WITH 1' BUFFER ZONE

5' MIN. ACCESS AISLE (SEE NOTE 1)

PERPENDICULAR ACCESSIBLE PARKING

FACE OF CURB OR PVMT. EDGE

4″ SSLW─

(TYP)

- ACCESSIBLE SIGN

(R7-8)

4" SSLW(T) (TYP)

ACCESSIBLE SIGN

(R7-8)

-ACCESSIBLE SIGN &

(R7-8 & R7-8a)

VAN ACCESSIBLE SIGN

- ACCESSIBLE SIGN

ACCESSIBLE RAMP REQ'D IN CURB AREAS (TYP)

(R7-8)

1:12

ACCESSIBLE SIGN

(R7-8)


1:12

(TYP)


FACE OF CURB

OR PAVEMENT EDGE


PARALLEL ACCESSIBLE PARKING




SCHOOL $PAY \ QUANTITY = 34.7 \ FT^2$




X-ING $PAY \quad QUANTITY = 20.8 \quad FT^2$




STOP $PAY QUANTITY = 22.2 FT^{2}$



AHEAD $PAY \quad QUANTITY = 31.3 \quad FT^{2}$




ONLY $PAY \ QUANTITY = 22.3 \ FT^2$



TURN ARROW


(RIGHT TURN OPPOSITE IN KIND)

PAY QUANTITY = 17.0 FT²




THROUGH (STRAIGHT ARROW)

PAY QUANTITY = 12.5 FT²



 $COMBINATION \ ARROW$ $PAY \ QUANTITY = 28.8 \ FT^{2}$



WRONG-WAY ARROW $PAY QUANTITY = 24.1 FT^{2}$


GENERAL NOTES


- 1. ALL WORDS AND SYMBOLS SHALL BE RETROREFLECTIVE WHITE AND SHALL CONFORM TO THE LATEST VERSION OF THE MUTCD.
- 2. MULTI-WORD MESSAGES SHALL READ "UP"; THAT IS, THE FIRST WORD SHALL BE NEAREST THE APPROACHING DRIVER.
- 3. THE WORD "ONLY" SHALL NOT BE USED WITH THROUGH OR COMBINATION ARROWS, AND SHALL NOT BE USED ADJACENT TO A BROKEN LANE LINE. A WORD/SYMBOL SHALL PRECEED THE WORD "ONLY".
- 4. COMBINATION ARROWS MAY BE COMPRISED OF 2 SINGLE ARROWS (e.g. TURN AND THROUGH ARROWS). HOWEVER, THE SHAFTS OF THE ARROWS SHALL COINCIDE AS SHOWN.
- 5. PREFORMED WORDS AND SYMBOLS SHALL BE PRE-CUT BY THE MANUFACTURER.
- 6. WRONG-WAY ARROWS SHALL NOT BE SUBSTITUTED FOR THROUGH ARROWS.
- 7. ALL STOP BARS, WORDS, SYMBOLS AND ARROWS SHALL BE THERMOPLASTIC.


PAVEMENT MARKING STANDARD

WORDS AND SYMBOLS









RAILROAD CROSSING SYMBOL PAY QUANTITY = $63.6 \text{ f+}^2 \text{ (SEE NOTE 3)}$

⊸ 24″ TRANSVERSE LINE TRANSVERSE LINE (SEE NOTE 3) — (SEE NOTE 3) 20 ft 15 ft 15 ft STOP LINE — (SEE NOTE 3) 50 ft (SEE NOTE 1)

VARIES WITH APPROACH SPEED AND SIGHT DISTANCE, BUT NOT LESS THAN 50' (SEE MUTCD).

PAVEMENT MARKINGS AT RAILROAD-HIGHWAY GRADE CROSSINGS

- 1. A PORTION OF THE PAVEMENT MARKING RXR SYMBOL SHOULD BE DIRECTLY OPPOSITE THE ADVANCE WARNING SIGN (W10-1, NOT SHOWN).
- 2. ON MULTI-LANE ROADS THE TRANSVERSE LINES SHOULD EXTEND ACROSS ALL APPROACH LANES, AND INDIVIDUAL RXR SYMBOLS SHOULD BE USED IN EACH APPROACH LANE.
- 3. RXR SYMBOL WILL BE PAID FOR BY THE SQUARE FOOT, TRANSVERSE LINES AND STOP BARS (24"WIDE) WILL BE PAID FOR BY THE LINEAR FOOT.

PAVEMENT MARKING STANDARD

WORDS AND SYMBOLS


STANDARD NO. PM-13

STANDARD

07-13-2001 02-26-2010

PM-13

LAYOUT DETAILS



* TRAFFIC

* TRAFFIC

APPROACH END PATTERN - ALTERNATE (DEPARTURE END OPPOSITE IN KIND) (SEE NOTE NO. 2)

SEE DETAILS BELOW-

ZONE LENGTH = 1501 f+(TYPICAL)(SEE NOTE 3)

> APPROACH END PATTERN - STANDARD (DEPARTURE END OPPOSITE IN KIND)

INTERMEDIATE PATTERN

(VARIES, MULTIPLES OF 1501 ft, 3 ZONES MINIMUM)

PAVEMENT MARKING DETAILS

RIGHT SHOULDER SHOWN - LEFT SHOULDER OPPOSITE IN KIND (SEE NOTE NO. 2)

GENERAL NOTES


- 1. ALL SPEED ZONE MARKINGS SHALL BE SOLID WHITE.
- 2. ALTERNATE APROACH END PATTERN SHALL BE USED FOR 3 ZONE LAYOUT ONLY, STANDARD PATTERN SHALL BE USED IN LIEU OF ALTERNATE PATTERN FOR LEFT SHOULDER WIDTHS LESS THAN 8 ft.
- 3. LONGITUDINAL DISTANCES SHALL BE MEASURED BY NHDOT SURVEY PERSONNEL. A COPY OF SURVEY NOTES SHALL BE FORWARDED TO BUREAU OF TRAFFIC.
- 4. FOR LEGAL REASONS, STATE POLICE SHALL BE PRESENT DURING THE INSTALLATION OF THESE MARKINGS. (TEL. 603-271-3678).
- 5. STATE POLICE SHOULD BE NOTIFIED WHEN ANY EXISTING MARKINGS ARE REMOVED DUE TO CONSTRUCTION.

*ARROWS SHOWN ON THIS SHEET INDICATE DIRECTION OF TRAFFIC ONLY

PAVEMENT MARKING STANDARD

SPEED ZONE PAVEMENT MARKINGS





STANDARD PEDESTRIAN CROSSING LAYOUT FOR CONTROLLED AND UNCONTROLLED APPROACHES AT INTERSECTIONS

N.T.S.

24″ TO 30″¬

CONTINENTAL CROSSWALK MARKING DETAIL FOR UNCONTROLLED CROSSING LOCATIONS N.T.S.

LAYOUT FOR UNCONTROLLED MIDBLOCK LOCATIONS


N.T.S.

GENERAL NOTES

- 1. SPACING FOR THE CONTINENTAL BLOCK MARKINGS SHOULD BE UNIFORM FOR EACH INDIVIDUAL CROSSWALK BUT BE ADJUSTED TO AVOID PLACEMENT DIRECTLY IN THE WHEEL PATH.
- 2. CROSSWALKS LOCATED AT A YIELD CONTROLLED SLIP RAMP OR OTHER YIELD CONTROLLED INTERSECTION APPROACH SHALL USE CONTINENTAL BLOCK MARKINGS REGARDLESS OF WHETHER THE CROSSWALK IS IN ADVANCE OF OR BEYOND THE YIELD CONTROL.
- 3. LOCATE UNCONTROLLED CROSSWALKS TO THE LEFT SIDE OF THE MINOR STREET WITH THE HIGHER RIGHT TURN VOLUMES.
- 4. STREET LIGHTING FOR UNCONTROLLED CROSSINGS TO MEET FHWA "INFORMATIONAL REPORT ON LIGHTING DESIGN FOR MIDBLOCK CROSSWALKS" (APRIL 2008) WHEN REQUIRED.
- 5. WHEN PROPOSED BY A MUNICIPALITY OUTSIDE NHDOT, INSTALLATION OF STREET LIGHTING SHALL MEET THE REQUIREMENTS OF THE CURRENT EDITION OF THE NHDOT UTILITY ACCOMMODATION MANUAL, AND IS SUBJECT TO THE REQUIREMENTS OF THE EXCAVATION PERMIT AND POLE LICENSING PROCEDURE.
- 6. VERIFY THAT WARNING SIGN LOCATIONS ARE NOT OBSCURED FROM THE VIEW OF APPROACHING TRAFFIC BY LIGHT POLES OR OTHER OBJECTS.
- 7. CONTROLLED CROSSWALKS SHALL BE OUTSIDE THE PAVEMENT LIMITS OF THE MAJOR STREET. THIS APPLIES TO BOTH MARKED AND IMPLIED CROSSWALKS.

LEGEND

(T) = THERMOPLASTIC



STANDARD CROSSWALK MARKING DETAIL FOR CONTROLLED CROSSING LOCATIONS

N.T.S.

PAVEMENT MARKING STANDARD

PEDESTRIAN CROSSINGS

STANDARD


NO. PM-15

REVISION DATE

07-13-2001


*.DGN FILE NAME PS-1

NO. PS-1



ATTACHMENT OF AUXILIARY PANELS AND SERVICE SYMBOL PANELS (BACK VIEW)

- 1. AUXILIARY PANELS SHALL BE MOUNTED TO THE RIGHT SIDE OF THE MAIN SIGN FOR RIGHT-HAND EXIT RAMPS, OR TO THE LEFT FOR LEFT-HAND EXIT RAMPS. SUPPORTS SHALL EXTEND TO THE TOP OF THE AUXILIARY PANEL AND SHALL OVERLAP THE MAIN SIGN BY A MINIMUM OF 3 FULL PLANKS AS SHOWN.
- 2. SERVICE SYMBOL PANELS, WHEN NOT ON A SEPARATE SIGN, SHALL BE MOUNTED IMMEDIATELY BELOW THE MAIN SIGN AND CENTERED LATERALLY WITHIN THE WIDTH OF THE SIGN, SUPPPORTS SHALL OVERLAP THE MAIN SIGN BY A MINIMUM OF 2 FULL PLANKS AS SHOWN.
- 3. POST CLIP ASSEMBLIES SHALL BE INSTALLED ON BOTH SIDES OF EACH AUXILIARY PANEL SUPPORT AND SERVICE SYMBOL SUPPORT AT EACH PLANK, AS WELL AS EACH END OF BOTH SUPPORTS.



GENERAL NOTES

- 1. GAP BETWEEN ANY TWO ASSEMBLED PLANK SECTIONS SHALL NOT EXCEED 3/32".
- 2. ALLOWABLE LATERAL BOW SHALL NOT EXCEED \pm 1/16".
- 3. ALL PLANK SECTIONS SHALL BE ONE PIECE FOR THE ENTIRE WIDTH OF SIGN SPECIFIED, AND SHALL NOT EXCEED \pm 1/8" FROM THE LENGTH & WIDTH SPECIFIED.
- 4. ALL PLANK SECTIONS SHALL BE 12" WIDE UNLESS OTHERWISE SPECIFIED.
- 5. SIGNS 8' AND GREATER IN WIDTH SHALL BE MOUNTED ON STEEL BEAM.

PLANK MOUNTED ON STEEL BEAM

- 1. POST CLIP ASSEMBLIES SHALL BE INSTALLED ON BOTH SIDES OF EACH POST AT EACH PLANK AS WELL AS AT THE TOP AND BOTTOM OF THE SIGN.
- 2. STEEL BEAM SHALL BE FLUSH WITH TOP OF SIGN AND SHALL NOT EXTEND ONTO AUXILIARY PANELS.
- 3. STEEL BEAMS SHALL NOT BE USED AS AUXILIARY PANEL SUPPORTS.

PLANK MOUNTED ON TUBING

- 1. POST CLAMP ASSEMBLIES SHALL BE INSTALLED AT EACH PLANK, AS WELL AS AT THE TOP AND BOTTOM OF THE SIGN.
- 2. TUBING SHALL NOT BE USED AS AUXILIARY PANEL SUPPORTS.

SIGNING STANDARD

ALUMINUM PLANK DETAILS




REVISION DATE 07-13-2001

02-26-2010

*.DGN FILE NAME

PS-2

NO. PS-2



POST CLIP

— STOP NUT

FILLER

WASHER

POST CLIP

END OF PLANK

FLAT

WITH NYLON

-PLACE BOLT IN

EVERY SLOTTED HOLE


POST —


CLAMP

5/16" CAP SCREW-


2-7/8" FLAT WASHER—

BOLT







POST CLIP BOLT



POST CLIP







POST CLAMP 4" DIA. 11 GAUGE

- POST - CHANNEL BRACKET LOCK NUT

<u>DETAIL "D"</u>

POST CLAMP ASSEMBLIES 1. SEE SPECIFICATION 615.2.7.3 FOR ADDITIONAL


- INFORMATION REGARDING THE CHANNEL BRACKET AND POST CLAMP.
- 2. USE 5/16" CAP SCREW WITH 2-7/8" O.D. WASHERS AND LOCKNUT FOR CLAMP CONNECTION.
- 3. ALL HARDWARE SHALL BE STAINLESS STEEL.

SIGNING STANDARD

STANDARD

NO. PS-2

ALUMINUM PLANK DETAILS



_3/8" x 13/16"

HEX BOLT

─3/8" HEX NUT

POST CLIP ASSEMBLY

EACH POST (TYP.)

2 PER PLANK,

13/16"—

EXTRUDED SIGN PANEL

→ DETAIL "A"

FACE OF PLANK ──►

3/8" FLAT WASHER -UNDER BOLT HEAD

AND NUT

END VIEW SECTION A-A

REVISION DATE


07-13-2001

02-26-2010

*.DGN FILE NAME

PS-3


NO. PS-3




CHANNEL

BRACKET

ALUMINUM POST SPACING



CHANNEL BRACKET 14 GAUGE




DETAIL A

POST CLAMP 4" DIA. 11 GAUGE

POST

CLAMP

SEE DETAIL



SIGN BLANK ATTACHMENT DETAIL

POST CLAMP ASSEMBLIES

- 1. SEE SPECIFICATION 615.2.7.3 FOR ADDITIONAL INFORMATION REGARDING THE CHANNEL BRACKET AND POST CLAMP.
- 2. USE 5/16" STAINLESS STEEL CAP SCREW WITH 2-7/8" O.D. WASHERS & LOCKNUT FOR CLAMP CONNECTION.

SIGN AND U-CHANNEL POST ASSEMBLY DETAIL

– 5/16" NYLON INSERT LOCKNUT

GALVANIZED

 $-3/16" \times 3/4"$ NYLON WASHER

 $-5/16" \times 7/8"$ FENDER WASHER

U-CHANNEL POST

- 1. FOR GALVANIZED U-CHANNEL POST, SEE NHDOT STANDARD SPECIFICATION FOR ROAD AND BRIDGE CONSTRUCTION BOOK, SECTION 615.
- 2. THE STAINLESS STEEL HEX HEAD BOLT LENGTH SHALL BE INCREASED TO ACCOMMODATE A THICKER SIGN MATERIAL.
- 3. THE POST SHALL BE SET A MINIMUM OF 3 INCHES TO A MAXIMUM OF 6 INCHES BELOW THE TOP OF SIGN.
- 4. U-CHANNEL POSTS SHALL NOT BE SPLICED AND DO NOT REQUIRE CHANNEL BRACKETS.
- 5. U-CHANNEL POSTS SHALL BE INSTALLED 36" OR GREATER BELOW EXISTING GROUND.

GENERAL NOTES

- 1. BRACKETS: ALL SIGNS TO BE FASTENED TO POSTS WITH POST CLAMP ASSEMBLIES AS SHOWN.
- 2. SIGN WIDTH 36" OR LESS MAY BE MOUNTED ON ONE (1) U-CHANNEL POST.
- 3. RECTANGULAR SIGNS 72" x 48" OR LESS MAY BE MOUNTED ON DUAL U-CHANNEL POST. DIAMOND SHAPE SIGNS GREATER THAN 36" SHALL BE MOUNTED ON ALUMINUM TUBING (INTERSTATE).
- 4. SIGN HEIGHT 48" OR LESS, CENTER CHANNEL BRACKET MAY BE OMITTED.
- 5. DIAMOND SHAPE SIGNS 48" OR LARGER REQUIRE TWO CHANNEL BRACKETS.
- 6. SIGNS 72" \times 72" OR GREATER SHALL BE ALUMINUM PLANK.




ALUMINUM SHEET DETAILS FOR TUBING & U-CHANNEL POSTS


SIGNING STANDARD

STANDARD NO. PS-4


<u>DIRECT BURIED</u> <u>BREAKAWAY</u>



SINGLE POST




DOUBLE POST




ANCHOR DETAIL

ANCHORS: USE 1 PIECE OF 2" × 12" PLANK (PRESSURE TREATED)
CLAMPED TO POST WITH A MINIMUM OF 12" OVERHANG, TO BE PARALLEL
WITH GROUND LINE. PLACE 2" × 12" PLANK BEHIND SIGN POST.



FOOTING DETAIL




MAXIMUM BREAKAWAY STUB HEIGHT

BREAKAWAY SUPPORTS PLACED ON ROADSIDE SLOPES SHALL NOT ALLOW IMPACTING VEHICLES TO SNAG ON EITHER THE FOUNDATION OR ANY SUBSTANTIAL REMAINS OF THE SUPPORT. SURROUNDING TERRAIN SHALL BE GRADED TO PERMIT VEHICLES TO PASS OVER ANY NON-BREAKAWAY PORTION OF THE SIGN INSTALLATION WHICH REMAINS IN THE GROUND OR RIGIDLY ATTACHED TO THE FOUNDATION.

GENERAL NOTES

- 1. MULTIPLE POST SIGNS MUST BE PROTECTED BY GUARDRAIL OR OTHER POSITIVE BARRIER, UNLESS BREAKAWAY MOUNTED.
- 2. THE MINIMUM HORIZONTAL CLEARANCE TO THE NEAR EDGE OF THE SIGN OF ANY MULTIPLE POST NON-BREAKAWAY MOUNT SIGN SHALL BE 7'-O" MIN. FROM FACE OF BEAM GUARDRAIL. OTHER TYPES OF GUARDRAIL OR BARRIER MAY REQUIRE A DIFFERENT OFFSET.
- 3. ALL HARDWARE SHALL BE STAINLESS STEEL UNLESS OTHERWISE NOTED.



CONCRETE BASE

GALVANIZED STEEL TUBE

2 - 7/16" HOLES

— 4-1/4" INSIDE DIA.

<u>SIDE VIEW</u>

CONCRETE BASE NOTES:

3/4" CHAMFER


- 1. GALVANIZED STEEL TUBE 4-1/4" I.D. X 4'-2"
- 2. CONCRETE CLASS B.
- 3. TOP SHALL HAVE TROWEL FINISH.
- 4. USE 5/16" x 5-1/2" LONG STAINLESS STEEL BOLT WITH STAINLESS STEEL NYLON INSERT NUT FOR SECURING POST.
- 5. ALUMINUM CAP SHALL BE INSTALLED ON THE TOP OF THE SIGN POST WITH THIS INSTALLATION.

SIGNING STANDARD

ALUMINUM TUBING DETAILS

- DETERMINE VALUES FOR W, H, & L AS INDICATED IN DRAWING
 - W = MAXIMUM WIDTH OF REQUIRED SIGN
 - H = MAXIMUM HEIGHT OF REQUIRED SIGN INCLUDING AUXILIARY SIGNS AND SERVICE SYMBOLS.
 - L = MAXIMUM DISTANCE BETWEEN TOP OF FOOTING AND BOTTOM OF REQUIRED SIGN.
 (SEE GENERAL NOTE NO. 4)
- FOR SIGN SIZES BETWEEN THOSE VALUES IN THE TABLE, USE NEXT HIGHEST FOOT VALUE.
- ENTER TABLE WITH MAXIMUM VALUE OF "L" AND REQUIRED VALUES OF "W" AND "H" FOR SELECTION OF APPROPRIATE BEAM SELECTION.

| | | | | | 2 | POS | ST SI | GN | | | | | |
|----------|-----|----------|----------|--------|---------|---------|--------|---------|--------|--------|--------|--------|--------|
| 10/ | | | | | | | Н | | | | | | |
| W | L | 4' | 5' | 6' | 7' | 8' | 9' | 10' | 11' | 12' | 13' | 14' | 15' |
| | 8' | S4x7.7 | S4x7.7 | S4x7.7 | S4x7.7 | W6x9 | W6x9 | W6x9 | W6x12 | W6x12 | W6x12 | W6x15 | W6x15 |
| 6' | 10' | S4x7.7 | S4x7.7 | S4x7.7 | W6x9 | W6x9 | W6x9 | W6x12 | W6x12 | W6x15 | W6x15 | W6x15 | W6x15 |
| | 12' | S4x7.7 | S4x7.7 | W6x9 | W6x9 | W6x9 | W6x12 | W6x12 | W6x15 | W6x15 | W6x15 | W8x18 | W8x18 |
| | 8' | S4x7.7 | S4x7.7 | W6x9 | W6x9 | W6x9 | W6x12 | W6x12 | W6x15 | W6x15 | W6x15 | W8x18 | W8x18 |
| 8' | 10' | S4x7.7 | W6x9 | W6x9 | W6x9 | W6x12 | W6x12 | W6x15 | W6x15 | W6x15 | W8x18 | W8x18 | W8x18 |
| | 12' | S4x7.7 | W6x9 | W6x9 | W6x12 | W6x12 | W6x15 | W6x15 | W6x15 | W8x18 | W8x18 | W8x18 | W8x18 |
| | 8' | S4x7.7 | W6x9 | W6x9 | W6x12 | W6x12 | W6x15 | W6x15 | W6x15 | W8x18 | W8x18 | W8x18 | W8x18 |
| | 10' | W6x9 | W6x9 | W6x12 | W6x12 | W6x15 | W6x15 | W6x15 | W8x18 | W8x18 | W8x18 | W8x18 | W8x18 |
| 10' | 12' | W6x9 | W6x9 | W6x12 | W6x12 | W6x15 | W6x15 | W8x18 | W8x18 | W8x18 | W8x18 | W8x18 | W8x18 |
| | 14' | W6x9 | W6x12 | W6x12 | W6x15 | W6x15 | W8x18 | W8x18 | W8x18 | W8x18 | W8x18 | W8x18 | W8x21 |
| | 16' | W6x9 | W6x12 | W6x15 | W6x15 | W8x18 | W8x18 | W8x18 | W8x18 | W8x18 | W8x18 | W8x21 | W8x21 |
| | 8' | W6x9 | W6x9 | W6x12 | W6x12 | W6x15 | W6x15 | W8x18 | W8x18 | W8x18 | W8x18 | W8x18 | W8x18 |
| | 10' | W6x9 | W6x9 | W6x12 | W6x15 | W6x15 | W8x18 | W8x18 | W8x18 | W8x18 | W8x18 | W8x18 | W8x21 |
| 12' | 12' | W6x9 | W6x12 | W6x15 | W6x15 | W8x18 | W8x18 | W8x18 | W8x18 | W8x18 | W8x18 | W8x21 | W8x21 |
| | 14' | W6x12 | W6x12 | W6x15 | W6x15 | W8x18 | W8x18 | W8x18 | W8x18 | W8x18 | W8x21 | W8x21 | W10x22 |
| | 16' | W6x12 | W6x15 | W6x15 | W8x18 | W8x18 | W8x18 | W8x18 | W8x18 | W8x21 | W8x21 | W10x22 | W10x22 |
| | 8' | W6x12 | W6x15 | W6x15 | W8x18 | W8x18 | W8x18 | W8x18 | W8x18 | W8x18 | W8x21 | W8x21 | W10x22 |
| | 10' | W6x12 | W6x15 | W6x15 | W8x18 | W8x18 | W8x18 | W8x18 | W8x18 | W8x21 | W8x21 | W10x22 | W10x22 |
| 14' | 12' | W6x15 | W6x15 | W8x18 | W8x18 | W8x18 | W8x18 | W8x18 | W8x21 | W8x21 | W10x22 | W10x22 | W10x26 |
| | 14' | W6x15 | W8x18 | W8x18 | W8x18 | W8x18 | W8x18 | W8x21 | W8x21 | W10x22 | W10x22 | W10x26 | W10x26 |
| | 16' | W6x15 | W8x18 | W8x18 | W8x18 | W8x18 | W8x21 | W8x21 | W10x22 | W10x22 | W10x26 | W10x26 | W10x26 |
| | 8' | W6x12 | W6x15 | W6x15 | W8x18 | W8x18 | W8x18 | W8x18 | W8x18 | W8x21 | W8x21 | W10x22 | W10x22 |
| | 10' | W6x15 | W6x15 | W8x18 | W8x18 | W8x18 | W8x18 | W8x18 | W8x21 | W10x22 | W10x22 | W10x22 | W10x26 |
| | 12' | W6x15 | W8x18 | W8x18 | W8x18 | W8x18 | W8x18 | W8x21 | W10x22 | W10x22 | W10x22 | W10x26 | W10x26 |
| 16' | 14' | W6x15 | W8x18 | W8x18 | W8x18 | W8x18 | W8x21 | W10x22 | W10x22 | W10x22 | W10x26 | W10x26 | W12x26 |
| | 16' | W8x18 | W8x18 | W8x18 | W8x18 | W8x21 | W8x21 | W10x22 | W10x22 | W10x26 | W10x26 | W12x26 | W12x26 |
| | 18' | W8x18 | W8x18 | W8x18 | W8x21 | W8x21 | W10x22 | W10x22 | W10x26 | W10x26 | W12x26 | W12x26 | W12x26 |
| | 8' | W6x12 | W6x15 | W8x18 | W8x18 | W8x18 | W8x18 | W8x18 | W8x21 | W10x22 | W10x22 | W10x22 | W10x26 |
| | 10' | W6x15 | W6x15 | W8x18 | W8x18 | W8x18 | W8x18 | W8x21 | W10x22 | W10x22 | W10x22 | W10x26 | W10x26 |
| 401 | 12' | W6x15 | W8x18 | W8x18 | W8x18 | W8x18 | W8x21 | W10x22 | W10x22 | W10x22 | W10x26 | W10x26 | W12x26 |
| 18' | 14' | W8x18 | W8x18 | W8x18 | W8x18 | W8x21 | W10x22 | W10x22 | W10x22 | W10x26 | W10x26 | W12x26 | W12x26 |
| | 16' | W8x18 | W8x18 | W8x18 | W8x21 | W8x21 | W10x22 | W10x22 | W10x26 | W10x26 | W12x26 | W12x26 | W12x26 |
| | 18' | W8x18 | W8x18 | W8x18 | W8x21 | W10x22 | W10x22 | W10x26 | W10x26 | W12x26 | W12x26 | W12x26 | - |
| | 8' | W6x15 | W6x15 | W8x18 | W8x18 | W8x18 | W8x18 | W8x21 | W10x22 | W10x22 | W10x22 | W10x26 | W10x26 |
| | 10' | W6x15 | W8x18 | W8x18 | W8x18 | W8x18 | W8x21 | W10x22 | W10x22 | W10x26 | W10x26 | W10x26 | W12x26 |
| <u> </u> | 12' | W8x18 | W8x18 | W8x18 | W8x18 | W8x21 | W10x22 | W10x22 | W10x26 | W10x26 | W12x26 | W12x26 | W12x26 |
| 20' | 14' | W8x18 | W8x18 | W8x18 | W8x21 | W8x21 | W10x22 | W10x26 | W10x26 | W12x26 | W12x26 | W12x26 | _ |
| | 16' | W8x18 | W8x18 | W8x18 | W8x21 | W10x22 | W10x22 | W10x26 | W10x26 | W12x26 | W12x26 | _ | _ |
| | 18' | W8x18 | W8x18 | W8x21 | W10x22 | W10x22 | W10x26 | W10x26 | W12x26 | W12x26 | W12x26 | _ | _ |
| | 20' | W8x18 | W8x18 | W8x21 | W10x22 | W10x26 | W10x26 | W12x26 | W12x26 | W12x26 | | | |
| | | 1,100,10 | <u> </u> | 110021 | 7710022 | 1110020 | | 1112020 | | | | | |



POST SPACING DETAIL

STEEL BEAM TO DRAIN AT POST CONCRETE CLASS B DIAMETER VARIES (SEE CHART)

MATCH ADJACENT CUT OR FILL

FOOTING DETAIL

| POST | F00 | TING |
|--------|-------|----------|
| SIZE | DEPTH | DIAMETER |
| S4×7.7 | 6′ | 24" |
| W6×9 | 6′ | 24" |
| W6×12 | 6′ | 24" |
| W6×15 | 7′-6″ | 24" |
| W8×18 | 7′-6″ | 30″ |
| W8×21 | 8′-6″ | 30" |
| W10×22 | 8′-6″ | 36" |
| W10×26 | 8′-6″ | 36" |
| W12×26 | 8′-6″ | 36″ |

GENERAL NOTES

- 1. SIGNS SHALL BE PROVIDED FOR LOCATIONS SPECIFIED ON THE PLANS OR AS DIRECTED BY THE ENGINEER. SEE SIGN TEXT LAYOUT SHEETS AND PLANS FOR SIGN SIZES AND APPROXIMATE LOCATIONS.
- 2. DIMENSIONS, ELEVATIONS, SLOPES, AND SITUATIONS SHOWN ARE FOR ILLUSTRATIVE PURPOSES ONLY. ACTUAL CASES WILL DEPEND ON FIELD CONDITIONS.
- 3. WHEN TWO OR MORE INDEPENDENT SIGNS ARE MOUNTED AS A SINGLE INSTALLATION, THE POST SUPPORTS SHALL BE CALCULATED WITH THE TOTAL AREA OF THE SIGNS BEING CONSIDERED AS ONE UNIT, INCLUDING AN ALLOWANCE FOR A 6" VERTICAL SPACE BETWEEN THE SIGNS.
- 4. POST LENGTH TO BE DETERMINED BY SIGN SIZE AND LOCATION. EXACT FIELD LOCATION TO BE DETERMINED BY THE ENGINEER.
- 5. THE MINIMUM HORIZONTAL CLEARANCE TO THE NEAR EDGE OF THE SIGN OF ANY MULTIPLE POST NON-BREAKAWAY MOUNT SIGN SHALL BE 7'-O" MIN. FROM FACE OF BEAM GUARDRAIL. OTHER TYPES OF GUARDRAIL OR BARRIER MAY REQUIRE A DIFFERENT OFFSET.
- 6. SEE STANDARD NO. PS-1 & PS-2 FOR ADDITIONAL INFORMATION.

SIGNING STANDARD

STEEL BEAM DETAILS
NON-BREAKAWAY

STANDARD NO. PS-5 REVISION DATE 07-13-2001

02-26-2010


*.DGN FILE NAME PS-5

STANDARD PL/

Wew Hampshire
Denortment of Transportation

- DETERMINE VALUES FOR W, H, & L AS INDICATED IN DRAWING
 - W = MAXIMUM WIDTH OF REQUIRED SIGN
 - H = MAXIMUM HEIGHT OF REQUIRED SIGN INCLUDING AUXILIARY SIGNS AND SERVICE SYMBOLS.
 - L = MAXIMUM DISTANCE BETWEEN TOP OF FOOTING AND BOTTOM OF REQUIRED SIGN.
 (SEE GENERAL NOTE NO. 4)
- FOR SIGN SIZES BETWEEN THOSE VALUES IN THE TABLE, USE NEXT HIGHEST FOOT VALUE.
- ENTER TABLE WITH MAXIMUM VALUE OF "L" AND REQUIRED VALUES OF "W" AND "H" FOR SELECTION OF APPROPRIATE BEAM SELECTION.


| | | | | | 3 | POS | ST SI | GN | | | | | |
|-----|-----|-------|-------|--------|--------|--------|--------|-----------|------------------|------------------|--------|--------|--------|
| | | | | | | | | ———— Н | | | | | |
| W | L | 4′ | 5′ | 6′ | 7′ | 8′ | 9′ | 10′ | 11′ | 12′ | 13′ | 14′ | 15′ |
| | 8' | W6x12 | W6x12 | W6x15 | W6x15 | W8x18 | W8x18 | W8x18 | W8x18 | W8x18 | W8x21 | W8x21 | W10x22 |
| | 10' | W6x12 | W6x15 | W6x15 | W8x18 | W8x18 | W8x18 | W8x18 | W8x18 | W8x21 | W10x22 | W10x22 | W10x22 |
| | 12' | W6x12 | W6x15 | W8x18 | W8x18 | W8x18 | W8x18 | W8x18 | W8x21 | W10x22 | W10x22 | W10x22 | W10x26 |
| | 14' | W6x15 | W8x18 | W8x18 | W8x18 | W8x18 | W8x18 | W8x21 | W10x22 | W10x22 | W10x22 | W10x26 | W10x26 |
| 22' | 16' | W6x15 | W8x18 | W8x18 | W8x18 | W8x18 | W8x21 | W10x22 | W10x22 | W10x22 | W10x26 | W10x26 | W12x26 |
| | 18' | W6x15 | W8x18 | W8x18 | W8x18 | W8x21 | W8x21 | W10x22 | W10x22 | W10x26 | W10x26 | W12x26 | W12x26 |
| | 20' | W8x18 | W8x18 | W8x18 | W8x18 | W8x21 | W10x22 | W10x22 | W10x26 | W10x26 | W12x26 | W12x26 | W12x26 |
| | 22' | W8x18 | W8x18 | W8x18 | W8x21 | W8x21 | W10x22 | W10x22 | W10x26 | W10x26 | W12x26 | W12x26 | W12x26 |
| | 8' | W6x12 | W6x12 | W6x15 | W8x18 | W8x18 | W8x18 | W8x18 | W8x18 | W8x21 | W8x21 | W10x22 | W10x22 |
| | 10' | W6x12 | W6x15 | W8x18 | W8x18 | W8x18 | W8x18 | W8x18 | W8x21 | W10x22 | W10x22 | W10x22 | W10x26 |
| | 12' | W6x15 | W6x15 | W8x18 | W8x18 | W8x18 | W8x18 | W8x21 | W10x22 | W10x22 | W10x22 | W10x26 | W10x26 |
| | 14' | W6x15 | W8x18 | W8x18 | W8x18 | W8x18 | W8x21 | W8x21 | W10x22 | W10x22 | W10x26 | W10x26 | W12x26 |
| 24' | 16' | W6x15 | W8x18 | W8x18 | W8x18 | W8x21 | W8x21 | W10x22 | W10x22 W10x22 | W10x22 W10x26 | W10x26 | W12x26 | W12x26 |
| | 18' | W8x18 | W8x18 | W8x18 | W8x18 | W8x21 | W10x22 | W10x22 | W10x26 | W10x26 | W10x26 | W12x26 | W12x26 |
| | | | | | | | | | | | | | |
| | 20' | W8x18 | W8x18 | W8x18 | W8x21 | W8x21 | W10x22 | W10x26 | W10x26 | W12x26 | W12x26 | W12x26 | |
| | 22' | W8x18 | W8x18 | W8x18 | W8x21 | W10x22 | W10x22 | W10x26 | W10x26 | W12x26 | W12x26 | W12x26 | |
| | 8' | W6x12 | W6x15 | W6x15 | W8x18 | W8x18 | W8x18 | W8x18 | W8x21 | W8x21 | W10x22 | W10x22 | W10x26 |
| - | 10' | W6x12 | W6x15 | W8x18 | W8x18 | W8x18 | W8x18 | W8x21 | W8x21 | W10x22 | W10x22 | W10x26 | W10x26 |
| | 12' | W6x15 | W8x18 | W8x18 | W8x18 | W8x18 | W8x21 | W8x21 | W10x22 | W10x22 | W10x26 | W10x26 | W12x26 |
| | 14' | W6x15 | W8x18 | W8x18 | W8x18 | W8x18 | W8x21 | W10x22 | W10x22 | W10x26 | W10x26 | W12x26 | W12x26 |
| 26' | 16' | W8x18 | W8x18 | W8x18 | W8x18 | W8x21 | W10x22 | W10x22 | W10x26 | W10x26 | W12x26 | W12x26 | W12x26 |
| | 18' | W8x18 | W8x18 | W8x18 | W8x21 | W8x21 | W10x22 | W10x26 | W10x26 | W12x26 | W12x26 | W12x26 | |
| | 20' | W8x18 | W8x18 | W8x18 | W8x21 | W10x22 | W10x22 | W10x26 | W10x26 | W12x26 | W12x26 | _ | |
| | 22' | W8x18 | W8x18 | W8x21 | W10x22 | W10x22 | W10x26 | W10x26 | W12x26 | W12x26 | W12x26 | - | - |
| | 24' | W8x18 | W8x18 | W8x21 | W10x22 | W10x22 | W10x26 | W12x26 | W12x26 | W12x26 | | _ | |
| | 8' | W6x12 | W6x15 | W8x18 | W8x18 | W8x18 | W8x18 | W8x18 | W8x21 | W10x22 | W10x22 | W10x26 | W10x26 |
| | 10' | W6x15 | W6x15 | W8x18 | W8x18 | W8x18 | W8x18 | W8x21 | W10x22 | W10x22 | W10x26 | W10x26 | W12x26 |
| | 12' | W6x15 | W8x18 | W8x18 | W8x18 | W8x18 | W8x21 | W10x22 | W10x22 | W10x26 | W10x26 | W12x26 | W12x26 |
| | 14' | W6x15 | W8x18 | W8x18 | W8x18 | W8x21 | W10x22 | W10x22 | W10x26 | W10x26 | W12x26 | W12x26 | W12x26 |
| 28' | 16' | W8x18 | W8x18 | W8x18 | W8x21 | W8x21 | W10x22 | W10x22 | W10x26 | W12x26 | W12x26 | W12x26 | |
| | 18' | W8x18 | W8x18 | W8x18 | W8x21 | W10x22 | W10x22 | W10x26 | W10x26 | W12x26 | W12x26 | _ | |
| | 20' | W8x18 | W8x18 | W8x21 | W8x21 | W10x22 | W10x26 | W10x26 | W12x26 | W12x26 | | _ | |
| | 22' | W8x18 | W8x18 | W8x21 | W10x22 | W10x22 | W10x26 | W12x26 | W12x26 | W12x26 | - | _ | |
| | 24' | W8x18 | W8x18 | W8x21 | W10x22 | W10x26 | W10x26 | W12x26 | W12x26 | | | _ | |
| | 8' | W6x12 | W6x15 | W8x18 | W8x18 | W8x18 | W8x18 | W8x21 | W8x21 | W10x22 | W10x22 | W10x26 | W10x26 |
| | 10' | W6x15 | W8x18 | W8x18 | W8x18 | W8x18 | W8x21 | W8x21 | W10x22 | W10x22 | W10x26 | W10x26 | W12x26 |
| | 12' | W6x15 | W8x18 | W8x18 | W8x18 | W8x21 | W8x21 | W10x22 | W10x22 | W10x26 | W10x26 | W12x26 | W12x26 |
| | 14' | W8x18 | W8x18 | W8x18 | W8x18 | W8x21 | W10x22 | W10x22 | W10x26 | W10x26 | W12x26 | W12x26 | |
| 30' | 16' | W8x18 | W8x18 | W8x18 | W8x21 | W10x22 | W10x22 | W10x26 | W10x26 | W12x26 | W12x26 | _ | |
| | 18' | W8x18 | W8x18 | W8x21 | W8x21 | W10x22 | W10x26 | W10x26 | W12x26 | W12x26 | W12x26 | _ | _ |
| | 20' | W8x18 | W8x18 | W8x21 | W10x22 | W10x22 | W10x26 | W12x26 | W12x26 | W12x26 | | _ | |
| | 22' | W8x18 | W8x18 | W8x21 | W10x22 | W10x26 | W10x26 | W12x26 | W12x26 | | | _ | |
| | 24' | W8x18 | W8x21 | W10x22 | W10x22 | W10x26 | W12x26 | W12x26 | _ | | | | |



POST SPACING DETAIL

GENERAL NOTES

- 1. SIGNS SHALL BE PROVIDED FOR LOCATIONS SPECIFIED ON THE PLANS OR AS DIRECTED BY THE ENGINEER. SEE SIGN TEXT LAYOUT SHEETS AND PLANS FOR SIGN SIZES AND APPROXIMATE LOCATIONS.
- 2. DIMENSIONS, ELEVATIONS, SLOPES, AND SITUATIONS SHOWN ARE FOR ILLUSTRATIVE PURPOSES ONLY. ACTUAL CASES WILL DEPEND ON FIELD CONDITIONS.
- 3. WHEN TWO OR MORE INDEPENDENT SIGNS ARE MOUNTED AS A SINGLE INSTALLATION, THE POST SUPPORTS SHALL BE CALCULATED WITH THE TOTAL AREA OF THE SIGNS BEING CONSIDERED AS ONE UNIT, INCLUDING AN ALLOWANCE FOR A 6" VERTICAL SPACE BETWEEN THE SIGNS.
- 4. POST LENGTH TO BE DETERMINED BY SIGN SIZE AND LOCATION. EXACT FIELD LOCATION TO BE DETERMINED BY THE ENGINEER.
- 5. THE MINIMUM HORIZONTAL CLEARANCE TO THE NEAR EDGE OF THE SIGN OF ANY MULTIPLE POST NON-BREAKAWAY MOUNT SIGN SHALL BE 7'-O" MIN. FROM FACE OF BEAM GUARDRAIL. OTHER TYPES OF GUARDRAIL OR BARRIER MAY REQUIRE A DIFFERENT OFFSET.
- 6. SEE STANDARD NO. PS-1 & PS-2 FOR ADDITIONAL INFORMATION.



FOOTING DETAIL

| POST | F00 | TING |
|--------|-------|----------|
| SIZE | DEPTH | DIAMETER |
| S4×7.7 | 6′ | 24" |
| W6×9 | 6′ | 24" |
| W6×12 | 6′ | 24" |
| W6×15 | 7′-6″ | 24" |
| W8×18 | 7′-6″ | 30" |
| W8×21 | 8′-6″ | 30" |
| W10×22 | 8′-6″ | 36″ |
| W10×26 | 8′-6″ | 36" |
| W12×26 | 8′-6″ | 36" |

SIGNING STANDARD

STEEL BEAM DETAILS
NON-BREAKAWAY

STANDARD NO. PS-6

REVISION DATE
07-13-2001
02-26-2010


*.DGN FILE NAME PS-6

DARD PLANS


Hew Hampshire
Department of Transportation

- DETERMINE VALUES FOR W, H, & L AS INDICATED IN DRAWING
 - W = MAXIMUM WIDTH OF REQUIRED SIGN
 - H = MAXIMUM HEIGHT OF REQUIRED SIGN INCLUDING AUXILIARY SIGNS AND SERVICE SYMBOLS.
 - L = MAXIMUM DISTANCE BETWEEN TOP OF FOOTING AND BOTTOM OF REQUIRED SIGN.
 (SEE GENERAL NOTE NO. 4)
- FOR SIGN SIZES BETWEEN THOSE VALUES IN THE TABLE, USE NEXT HIGHEST FOOT VALUE.
- ENTER TABLE WITH MAXIMUM VALUE OF "L" AND REQUIRED VALUES OF "W" AND "H" FOR SELECTION OF APPROPRIATE BEAM SELECTION.

| | | | | | | | | Н | | | | | |
|-----|-----|-------|-------|--------|--------|--------|--------|--------|--------|--------|--------|--------|--------|
| W | L | 4' | 5' | 6' | 7' | 8' | 9' | 10' | 11' | 12' | 13' | 14' | 15' |
| | 8' | W6x9 | W6x9 | W6x9 | W6x9 | W6x9 | W6x9 | W6x9 | W6x9 | W6x12 | W6x12 | W8x18 | W8x18 |
| | 10' | W6x9 | W6x9 | W6x9 | W6x9 | W6x12 | W6x12 | W6x12 | W6x15 | W6x15 | W8x18 | W8x18 | W8x18 |
| 6' | 12' | W6x9 | W6x12 | W6x12 | W6x12 | W6x15 | W6x15 | W6x15 | W6x15 | W8x18 | W8x18 | W8x18 | W8x18 |
| | 14' | W6x12 | W6x12 | W6x12 | W6x15 | W6x15 | W6x15 | W6x15 | W8x18 | W8x18 | W8x18 | W8x18 | W8x21 |
| | 16' | W6x12 | W6x15 | W6x15 | W6x15 | W6x15 | W6x15 | W8x18 | W8x18 | W8x18 | W8x21 | W8x21 | W8x21 |
| | 8' | W6x9 | W6x9 | W6x9 | W6x9 | W6x9 | W6x9 | W6x12 | W6x12 | W6x12 | W6x15 | W8x18 | W8x18 |
| | 10' | W6x9 | W6x9 | W6x12 | W6x12 | W6x12 | W6x12 | W6x15 | W8x18 | W8x18 | W8x18 | W8x18 | W8x18 |
| 8' | 12' | W6x12 | W6x12 | W6x15 | W6x15 | W6x15 | W6x15 | W8x18 | W8x18 | W8x18 | W8x18 | W8x18 | W8x21 |
| | 14' | W6x12 | W6x15 | W6x15 | W6x15 | W6x15 | W8x18 | W8x18 | W8x18 | W8x18 | W8x21 | W8x21 | W8x21 |
| | 16' | W6x15 | W6x15 | W6x15 | W8x18 | W8x18 | W8x18 | W8x21 | W8x21 | W8x21 | W8x21 | W10x26 | W10x26 |
| | 8' | W6x9 | W6x9 | W6x9 | W6x9 | W6x12 | W6x12 | W6x12 | W6x15 | W8x18 | W8x18 | W8x18 | W10x22 |
| | 10' | W6x9 | W6x12 | W6x12 | W6x12 | W6x15 | W6x15 | W8x18 | W8x18 | W8x18 | W8x18 | W8x18 | W10x22 |
| 10' | 12' | W6x12 | W6x12 | W6x15 | W6x15 | W8x18 | W8x18 | W8x18 | W8x18 | W8x18 | W8x21 | W8x21 | W10x22 |
| | 14' | W6x15 | W6x15 | W6x15 | W8x18 | W8x18 | W8x18 | W8x21 | W8x21 | W8x21 | W8x21 | W10x26 | W10x26 |
| | 16' | W6x15 | W6x15 | W8x18 | W8x18 | W8x21 | W8x21 | W8x21 | W8x21 | W10x26 | W10x26 | W10x26 | W10x26 |
| | 8' | W6x9 | W6x9 | W6x9 | W6x12 | W6x12 | W6x15 | W8x18 | W8x18 | W8x18 | W8x18 | W10x22 | W12x26 |
| | 10' | W6x9 | W6x12 | W6x12 | W6x15 | W6x15 | W8x18 | W8x18 | W8x18 | W8x18 | W10x22 | W10x22 | W12x26 |
| 12' | 12' | W6x12 | W6x12 | W6x15 | W8x18 | W8x18 | W8x18 | W8x18 | W8x21 | W8x21 | W10x22 | W10x22 | W12x26 |
| | 14' | W6x15 | W6x15 | W8x18 | W8x18 | W8x18 | W8x21 | W8x21 | W10x22 | W10x26 | W10x26 | W10x26 | W12x26 |
| | 16' | W6x15 | W8x18 | W8x18 | W8x21 | W8x21 | W8x21 | W10x26 | W10x26 | W10x26 | W10x26 | W12x26 | W12x26 |
| | 8' | W6x9 | W6x9 | W6x12 | W6x12 | W6x15 | W8x18 | W8x18 | W8x18 | W8x18 | W8x21 | W12x26 | W14x30 |
| | 10' | W6x12 | W6x12 | W6x15 | W6x15 | W8x18 | W8x18 | W8x18 | W8x18 | W10x22 | W12x26 | W12x26 | W14x30 |
| 14' | 12' | W6x12 | W6x15 | W8x18 | W8x18 | W8x18 | W8x21 | W8x21 | W8x21 | W10x22 | W12x26 | W12x26 | W14x30 |
| | 14' | W6x15 | W6x15 | W8x18 | W8x18 | W8x21 | W8x21 | W10x22 | W10x26 | W10x26 | W12x26 | W12x26 | W14x30 |
| | 16' | W6x15 | W8x18 | W8x21 | W8x21 | W10x22 | W10x26 | W10x26 | W10x26 | W12x26 | W14x30 | | |
| | 8' | W6x9 | W6x9 | W6x12 | W6x12 | W8x18 | W8x18 | W8x18 | W8x18 | W8x18 | W10x22 | W14x30 | |
| | 10' | W6x12 | W6x12 | W6x15 | W8x18 | W8x18 | W8x18 | W8x18 | W10x22 | W10x26 | W12x26 | W14x30 | |
| 16' | 12' | W6x15 | W6x15 | W8x18 | W8x18 | W8x21 | W8x21 | W8x21 | W10x26 | W10x26 | W12x26 | W14x30 | |
| | 14' | W6x15 | W8x18 | W8x18 | W8x21 | W8x21 | W10x26 | W10x26 | W10x26 | W10x26 | W12x26 | W14x30 | |
| | 16' | W8x18 | W8x18 | W8x21 | W8x21 | W10x26 | W10x26 | W10x26 | W12x26 | | _ | | |
| | 8' | W6x9 | W6x12 | W6x12 | W6x15 | W8x18 | W8x18 | W8x18 | W8x18 | W10x22 | W12x26 | | |
| | 10' | W6x12 | W6x15 | W6x15 | W8x18 | W8x18 | W8x18 | W8x21 | W10x22 | W12x26 | W14x30 | | |
| 18' | 12' | W6x15 | W6x15 | W8x18 | W8x18 | W8x21 | W8x21 | W10x26 | W10x26 | W12x26 | W14x30 | | |
| | 14' | W6x15 | W8x18 | W8x21 | W8x21 | W10x22 | W10x26 | W10x26 | W10x26 | W12x26 | _ | | |
| | 16' | W8x18 | W8x21 | W8x21 | W10x26 | W10x26 | W10x26 | W12x26 | | | _ | | |
| | 8' | W6x9 | W6x12 | W6x15 | W8x18 | W8x18 | W8x18 | W8x18 | W10x22 | W10x26 | W12x26 | | |
| | 10' | W6x12 | W6x15 | W8x18 | W8x18 | W8x18 | W8x18 | W10x22 | W12x26 | W14x30 | _ | | |
| 20' | 12' | W6x15 | W6x15 | W8x18 | W8x21 | W8x21 | W10x22 | W10x26 | W12x26 | W14x30 | _ | | |
| | 14' | W8x18 | W8x18 | W8x21 | W8x21 | W10x26 | W10x26 | W10x26 | W12x26 | | _ | | |
| | 16' | W8x18 | W8x21 | W10x26 | W10x26 | W10x26 | W12x26 | | | | | | |



POST SPACING DETAIL




MAXIMUM BREAKAWAY STUB HEIGHT

BREAKAWAY SUPPORTS PLACED ON ROADSIDE SLOPES SHALL NOT ALLOW IMPACTING VEHICLES TO SNAG ON EITHER THE FOUNDATION OR ANY SUBSTANTIAL REMAINS OF THE SUPPORT. SURROUNDING TERRAIN SHALL BE GRADED TO PERMIT VEHICLES TO PASS OVER ANY NON-BREAKAWAY PORTION OF THE SIGN INSTALLATION WHICH REMAINS IN THE GROUND OR RIGIDLY ATTACHED TO THE FOUNDATION.

GENERAL NOTES

- 1. SIGNS SHALL BE PROVIDED FOR LOCATIONS SPECIFIED ON THE PLANS OR AS DIRECTED BY THE ENGINEER. SEE SIGN TEXT LAYOUT SHEETS AND PLANS FOR SIGN SIZES AND APPROXIMATE LOCATIONS.
- 2. DIMENSIONS, ELEVATIONS, SLOPES, AND SITUATIONS SHOWN ARE FOR ILLUSTRATIVE PURPOSES ONLY. ACTUAL CASES WILL DEPEND ON FIELD CONDITIONS.
- 3. WHEN TWO OR MORE INDEPENDENT SIGNS ARE MOUNTED AS A SINGLE INSTALLATION, THE POST SUPPORTS SHALL BE CALCULATED WITH THE TOTAL AREA OF THE SIGNS BEING CONSIDERED AS ONE UNIT, INCLUDING AN ALLOWANCE FOR A 6" VERTICAL SPACE BETWEEN THE SIGNS.
- 4. POST LENGTH TO BE DETERMINED BY SIGN SIZE AND LOCATION. EXACT FIELD LOCATION TO BE DETERMINED BY THE ENGINEER.
- 5. THE MINIMUM HORIZONTAL CLEARANCE TO THE NEAR EDGE OF THE SIGN OF ANY MULTIPLE POST NON-BREAKAWAY MOUNT SIGN SHALL BE 7'-0" MIN. FROM FACE OF BEAM GUARDRAIL. OTHER TYPES OF GUARDRAIL OR BARRIER MAY REQUIRE A DIFFERENT OFFSET.
- 6. SEE STANDARD NO. PS-1 & PS-2 FOR ADDITIONAL INFORMATION.



FOOTING DETAIL

| F00 | TING |
|-------|--------------------------------------------------|
| DEPTH | DIAMETER |
| 6′ | 24" |
| 6′ | 24" |
| 7′-6″ | 24" |
| 7′-6″ | 30" |
| 8′-6″ | 30" |
| 8′-6″ | 36" |
| 8′-6″ | 36" |
| 8′-6″ | 36" |
| 9′ | 36" |
| | DEPTH 6' 6' 7'-6" 7'-6" 8'-6" 8'-6" 8'-6" |

SIGNING STANDARD

STEEL BEAM DETAILS
BREAKAWAY

STANDARD NO. PS-7

REVISION DATE
07-13-2001
02-26-2010

*.DGN FILE NAME PS-7

STANDARD PLAN


New Hampshire
Department of Transportation

- DETERMINE VALUES FOR W, H, & L AS INDICATED IN DRAWING
 - W = MAXIMUM WIDTH OF REQUIRED SIGN
 - H = MAXIMUM HEIGHT OF REQUIRED SIGN
 - L = MAXIMUM DISTANCE BETWEEN TOP OF FOOTING AND BOTTOM OF REQUIRED SIGN.
- FOR SIGN SIZES BETWEEN THOSE VALUES IN THE TABLE, USE NEXT HIGHEST
- ENTER TABLE WITH MAXIMUM VALUE OF "L" AND REQUIRED VALUES OF "W" AND "H" FOR SELECTION OF APPROPRIATE BEAM SELECTION.


GENERAL NOTES

- 1. SIGNS SHALL BE PROVIDED FOR LOCATIONS SPECIFIED ON THE PLANS OR AS DIRECTED BY THE ENGINEER. SEE SIGN TEXT LAYOUT SHEETS AND PLANS FOR SIGN SIZES AND APPROXIMATE LOCATIONS.
- 2. DIMENSIONS, ELEVATIONS, SLOPES, AND SITUATIONS SHOWN ARE FOR ILLUSTRATIVE PURPOSES ONLY. ACTUAL CASES WILL DEPEND ON FIELD CONDITIONS.
- 3. WHEN TWO OR MORE INDEPENDENT SIGNS ARE MOUNTED AS A SINGLE INSTALLATION, THE POST SUPPORTS SHALL BE CALCULATED WITH THE TOTAL AREA OF THE SIGNS BEING CONSIDERED AS ONE UNIT, INCLUDING AN ALLOWANCE FOR A 6" VERTICAL SPACE BETWEEN THE SIGNS.
- 4. POST LENGTH TO BE DETERMINED BY SIGN SIZE AND LOCATION. EXACT FIELD LOCATION TO BE DETERMINED BY THE ENGINEER.
- 5. THE MINIMUM HORIZONTAL CLEARANCE TO THE NEAR EDGE OF THE SIGN OF ANY MULTIPLE POST NON-BREAKAWAY MOUNT SIGN SHALL BE 7'-O" MINFROM FACE OF BEAM GUARDRAIL. OTHER TYPES OF GUARDRAIL OR BARRIER MAY REQUIRE A DIFFERENT OFFSET.
- 6. SEE STANDARD NO. PS-1 & PS-2 FOR ADDITIONAL INFORMATION.

| | | | | | 3 | POS | ST SIG | GN | | | | | |
|-----|-----|-------|-------|--------|--------|--------|--------|-------------|----------------------------------------------------------|--------|--------|--------|-----|
| 107 | | | | | | | ŀ | | | | | | |
| W | L | 4' | 5' | 6' | 7' | 8' | 9' | 10' | 11' | 12' | 13' | 14' | 15' |
| | 8' | W6x9 | W6x9 | W6x12 | W6x12 | W6x15 | W8x18 | W8x18 | W8x18 | W8x18 | W10x22 | W14x30 | _ |
| | 10' | W6x12 | W6x12 | W6x15 | W6x15 | W8x18 | W8x18 | W8x18 | W8x21 | W10x22 | W12x26 | W14x30 | |
| 22' | 12' | W6x12 | W6x15 | W8x18 | W8x18 | W8x18 | W8x21 | W8x21 | W8x21 | W10x26 | W12x26 | W14x30 | - |
| | 14' | W6x15 | W8x18 | W8x18 | W8x21 | W8x21 | W8x21 | W10x26 | W10x26 | W10x26 | W12x26 | W14x30 | - |
| | 16' | W8x18 | W8x18 | W8x21 | W8x21 | W10x26 | W10x26 | W10x26 | W12x26 | W12x26 | _ | - | |
| | 8' | W6x9 | W6x9 | W6x12 | W6x12 | W8x18 | W8x18 | W8x18 | W8x18 | W8x21 | W10x22 | W14x30 | - |
| | 10' | W6x12 | W6x12 | W6x15 | W8x18 | W8x18 | W8x18 | W8x18 | W10x22 | W10x26 | W12x26 | W14x30 | - |
| 24' | 12' | W6x15 | W6x15 | W8x18 | W8x18 | W8x21 | W8x21 | W8x21 | W10x26 | W10x26 | W12x26 | W14x30 | |
| | 14' | W6x15 | W8x18 | W8x18 | W8x21 | W8x21 | W10x26 | W10x26 | W10x26 | W10x26 | W12x26 | W14x30 | _ |
| | 16' | W8x18 | W8x18 | W8x21 | W8x21 | W10x26 | W10x26 | W10x26 | W12x26 | | | _ | |
| | 8' | W6x9 | W6x12 | W6x12 | W6x12 | W8x18 | W8x18 | W8x18 | W8x18 | W10x22 | W12x26 | _ | _ |
| | 10' | W6x12 | W6x15 | W6x15 | W8x18 | W8x18 | W8x18 | W8x21 | W10x22 | W12x26 | W14x30 | _ | - |
| 26' | 12' | W6x15 | W6x15 | W8x18 | W8x18 | W8x21 | W8x21 | W8x21 | W10x26 | W12x26 | W14x30 | _ | _ |
| | 14' | W6x15 | W8x21 | W8x21 | W8x21 | W8x21 | W10x26 | W10x26 | x21 W10x22 W12x26 W14x30 - x21 W10x26 W12x26 W14x30 - | _ | - | | |
| | 16' | W8x18 | W8x21 | W8x21 | W10x26 | W10x26 | W10x26 | W12x26 | W14x30 | | | _ | - |
| | 8' | W6x9 | W6x12 | W6x12 | W8x18 | W8x18 | W8x18 | W8x18 | W8x18 | W10x22 | W12x26 | _ | - |
| | 10' | W6x12 | W6x15 | W8x18 | W8x18 | W8x18 | W8x18 | W10x22 | W10x22 | W12x26 | W14x30 | _ | _ |
| 28' | 12' | W6x15 | W6x15 | W8x18 | W8x18 | W8x21 | W8x21 | W10x26 | W10x26 | W12x26 | W14x30 | _ | - |
| | 14' | W8x18 | W8x18 | W8x21 | W10x26 | W10x26 | W10x26 | W10x26 | W12x26 | W12x26 | - | _ | |
| | 16' | W8x18 | W8x21 | W8x21 | W10x26 | W10x26 | W10x26 | W12x26 | | _ | _ | _ | - |
| | 8' | W6x9 | W6x12 | W6x15 | W8x18 | W8x18 | W8x18 | W8x18 | W10x22 | W10x26 | W12x26 | - | - |
| | 10' | W6x12 | W6x15 | W8x18 | W8x18 | W8x18 | W8x18 | W10x22 | W12x26 | W14x30 | _ | _ | |
| 30' | 12' | W6x15 | W8x18 | W8x18 | W8x21 | W8x21 | W10x22 | W10x26 | W12x26 | W14x30 | _ | - | _ |
| | 14' | W8x18 | W8x18 | W8x21 | W8x21 | W10x26 | W10x26 | W10x26 | W12x26 | | _ | - | - |
| | 16' | W8x18 | W8x21 | W10x26 | W10x26 | W10x26 | W12x26 | | | | | _ | |







FOOTING DETAIL

| POST | F00 | TING |
|--------|-------|----------|
| SIZE | DEPTH | DIAMETER |
| W6×9 | 6′ | 24" |
| W6×12 | 6′ | 24" |
| W6×15 | 7′-6″ | 24" |
| W8×18 | 7′-6″ | 30" |
| W8×21 | 8′-6″ | 30" |
| W10×22 | 8′-6″ | 36″ |
| W10×26 | 8′-6″ | 36″ |
| W12×26 | 8′-6″ | 36" |
| W14×30 | 9′ | 36" |

SIGNING STANDARD

STEEL BEAM DETAILS
BREAKAWAY

NO. PS-8


REVISION DATE
07-13-2001
02-26-2010

*.DGN FILE NAME
PS-8

STANDARD


STANDARD PLANS





STANDARD NO. PS-9

BREAKAWAY MOUNTS



ANCHOR INSTALLATION & BRACKET SELECTION

TRAFFIC

A = LATERAL SPACING OF ANCHORS

3" FOR B-525 USED ON 6" & 8" WIDE FLANGE POSTS

4" FOR B-650 USED ON 10", 12" & 14" WIDE FLANGE POSTS

4-1/4" FOR AI6 USED ON W6x9 WIDE FLANGE POSTS

3-1/4" FOR AP \times 4-1/2" USED ON 4" DIAMETER ALUMINUM TUBE.

B = LONGITUDINAL SPACING OF ANCHORS

* BRACKET #1 - DEPTH OF POST SECTION PLUS 7-15/16"

* BRACKET #2 - DEPTH OF POST SECTION PLUS 8-1/16"

* BRACKET #3 - DEPTH OF POST SECTION PLUS 8-1/8"

DEPTH OF POST SECTION PLUS 3-3/4" FOR AI6

* FOR B-525 & B-650 MOUNTS, SEE BRACKET TABLES

PLAN VIEW OF FOOTINGS

(SEE PS-3, PS-5A, OR PS-5B FOR FOOTING SIZES)

13

<u> 10" POST</u>

POST LENGTH = L+ H(FT)


10 | 11 | 12 | 13 | 14 | 15 | 16 | 17 | 18 | 19 | 20 | 21 | 22 | 23 | 24 | 25

6" POST

POST LENGTH = L + H(FT)

10 | 11 | 12 | 13 | 14 | 15 | 16 | 17 | 18 | 19 | 20 | 21 | 22 | 23 | 24 | 25

<u>8" POST</u>



BRACKET TABLES FOR B-525-LP MOUNTS

<u> 12" POST</u>

| | | | | | | PO | ST l | LENG | TH | = L | + H | (FT |) | | | |
|----|----|----|----|----|----|----|------|------|----|-----|-----|-----|----|----|----|----|
| | 10 | 11 | 12 | 13 | 14 | 15 | 16 | 17 | 18 | 19 | 20 | 21 | 22 | 23 | 24 | 25 |
| 3 | | | | | | | | | | | | | | | | |
| 4 | | | | | | | | | | | | | | | | |
| 5 | | | | | | | | | | | | | | 1 | | |
| 6 | | | | | | | | | | | | | | | | |
| 7 | | | | | | | | | | | | | | | | |
| 8 | | | | | | | | | 2 | | | | | | | |
| 9 | | | | | | | | | | | | | | | | |
| 10 | | | | | | | | | | | | | | | | |
| 11 | | | | | | | | | | | | | | | | |
| 12 | | | | 3 | | | | | | | | | | | | |
| 13 | | | | | | | | | | | | | | | | |
| 14 | | | | | | | | | | | | | | | | |
| 15 | | | | | | | | | | | | | | | | |

BRACKET TABLES FOR B-650-LP MOUNTS

SELECT CORRECT BRACKET NUMBER BY LOCATING THE INTERSECTION OF SIGN HEIGHT AND POST LENGTH IN THE BRACKET SELECTION MATRIX. THE INTERSECTION WILL BE EITHER ZONE 1, 2, OR 3 WHICH CORRESPONDS TO BRACKET NUMBERS 1, 2, OR 3.


4" MAX.

GROUND LINE

5'

MAXIMUM BREAKAWAY STUB HEIGHT


BREAKAWAY SUPPORTS PLACED ON ROADSIDE SLOPES SHALL NOT ALLOW IMPACTING VEHICLES TO SNAG ON EITHER THE FOUNDATION OR ANY SUBSTANTIAL REMAINS OF THE SUPPORT. SURROUNDING TERRAIN SHALL BE GRADED TO PERMIT VEHICLES TO PASS OVER ANY NON-BREAKAWAY PORTION OF THE SIGN INSTALLATION WHICH REMAINS IN THE GROUND OR RIGIDLY ATTACHED TO THE FOUNDATION.



<u> 14" POST</u>

POST LENGTH = L+ H(FT)

10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25



SIGNING STANDARD

BREAKAWAY MOUNTS

07-13-2001 02-26-2010

STANDARD

NO. PS-10


*.DGN FILE NAME PS-10


STANDARD PLANS

Hew Hampshire
Department of Transportation

*.DGN FILE NAME

STANDARD






N.H. TURNPIKE ROUTE MARKERS


(FOR GUIDE SIGN USE)


| | DIMENSIONS (inches)/LETTER FONTS | | | | | | | | | | | | | |
|----|----------------------------------|---------|-------|-------|-----|-------|-------|-----|------|-----|--|--|--|--|
| А | В | C | D | Е | F | G | I | 7 | L | М | | | | |
| 15 | 18 | 2 1/4 C | 4 1/2 | 3/4 | 1/2 | 1 | 123/4 | 3/8 | 71/2 | 12 | | | | |
| 20 | 2 4 | 3 C | 6 | 1 | 3/4 | 1 1/4 | 17 | 1/2 | 10 | 16 | | | | |
| 30 | 36 | 4 1/2 C | 9 | 1 1/2 | 1 | 2 | 251/2 | 3/4 | 15 | 2 4 | | | | |



(RADIUS)


M1-6a





| | SIGN | DI | MENSIO | NS (inch | es)/LET | TER FON | TS |
|---|-------|-----|--------|----------|---------|---------|-----|
| | | Α | В | С | D | E | F |
| 1 | DIGIT | 18 | 18 | 10E | _ | 8 D | 4 B |
| 2 | DIGIT | 18 | 18 | 1 O C | 4 D | 8 D | 4 B |
| 3 | DIGIT | 18 | 18 | 10B | 4 D | 8 B | 4 B |
| 1 | DIGIT | 2 4 | 2 4 | 14E | _ | 11D | 6 B |
| 2 | DIGIT | 2 4 | 2 4 | 14C | 6 D | 11D | 6 B |
| 3 | DIGIT | 2 4 | 2 4 | 12B | 6 D | 11B | 6 B |
| 1 | DIGIT | 36 | 36 | 18E | _ | 16D | 8 B |
| 2 | DIGIT | 36 | 36 | 18C | 8 D | 16D | 8 B |
| 3 | DIGIT | 36 | 36 | 18B | 8 D | 16B | 8 B |
| 1 | DIGIT | 48 | 48 | 24E | _ | 20D | 11B |
| 2 | DIGIT | 48 | 4 8 | 24C | 12D | 20D | 11B |
| 3 | DIGIT | 48 | 48 | 24B | 12D | 20B | 11B |

NH STATE ROUTE MARKER PATTERN FOR GUIDE SIGN USE



NOTES:

- 1. OPTICALLY PLACE NUMERALS WITHIN SHIELD.
- 2. ANY 2 DIGIT ROUTE WITH ONE OR MORE #1's IN THE COPY WILL BE A "D" SERIES.
- 3. ANY 3 DIGIT ROUTE WITH TWO #1's IN THE COPY WILL BE WILL BE A "C" SERIES.
- 4. ANY 3 DIGIT ROUTE WITH THREE #1's IN THE COPY WILL BE WILL BE A "D" SERIES.

(FOR INDEPENDENT USE)

M1-5a

M1-5

<u>M1-5c</u>

| | DIMENSIONS (inches)/LETTER FONTS | | | | | | | | | | |
|------------|----------------------------------|-----|-----|-----|-------|-------|-----|-----|-----|--|--|
| SIGN | А | В | С | D | E | F | G | Н | I | | |
| 1,2 DIGITS | 2 4 | 2 4 | 12D | 1/2 | 1 1/2 | 9 D | 6 D | 5 B | 1/2 | | |
| 3 DIGITS | 2 4 | 2 4 | 12B | 1/2 | 1 1/2 | 9 C | 6 D | 5 B | 1/2 | | |
| 1,2 DIGITS | 36 | 36 | 18D | 3/4 | 21/4 | 1 4 D | 9 D | 9 B | 3/4 | | |
| 3 DIGITS | 36 | 36 | 18B | 3/4 | 21/4 | 14C | 9 D | 9 B | 3/4 | | |

N.H. STATE ROUTE MARKER

* OPTICALLY PLACE NUMERALS WITHIN SHIELD

GENERAL NOTES

- 1. BACKGROUND FOR ALL SHIELDS FOR C & CC SIGNS SHALL BE WHITE TYPE III. BACKGROUND FOR ALL SHIELDS ON OVERHEAD STRUCTURES SHALL BE TYPE VII, VIII, IX OR X.
- 2. SHEET ALUMINUM USED FOR DEMOUNTABLE ROUTE MARKERS SHALL CONFORM TO THE OUTLINE OF THE SHIELD.
- 3. NEW HAMPSHIRE STATE ROUTE MARKERS SHALL UTILIZE "THE OLD MAN" IMAGE OR OUTLINE AS FOLLOWS:
 - INDEPENDENT ROUTE MARKERS SHALL HAVE BLACK TEXT INSIDE A BLACK "OLD MAN" IMAGE AS SHOWN ABOVE.
 - GUIDE SIGN ROUTE MARKERS SHALL HAVE BLACK TEXT ON A CUT OUT WHITE "OLD MAN" OUTLINE AS SHOWN LEFT.
- 4. NEW HAMPSHIRE TURNPIKE ROUTE MARKERS SHALL UTILIZE THE FOLLOWING DESIGN:
 - SPAULDING TURNPIKE GUIDE SIGN ROUTE MARKERS SHALL HAVE BLUE TEXT, BORDER, AND DISK ON A WHITE BACKGROUND,
 - EVERETT TURNPIKE GUIDE SIGN ROUTE MARKERS SHALL HAVE GREEN TEXT, BORDER, AND DISK ON A WHITE BACKGROUND.
- 5. INTERSTATE AND U.S. ROUTE MARKERS SHALL CONFORM TO THE MUTCD AND STANDARD HIGHWAY SIGNS MANUAL.
- 6. DIMENSIONS OF ROUTE MARKERS NOT SHOWN ON THIS SHEET SHALL BE DIRECTLY PROPORTIONAL TO THOSE SHOWN.

SIGNING STANDARD

ROUTE MARKER DETAILS


M1-5b



NO. SG-2

REVISION DATE 07-13-2001 02-26-2010

*.DGN FILE NAME



1.88" RADIUS, 0.50" BORDER, 0.50" INDENT BLACK ON WHITE, "YIELD", "TO" & SHIELD BORDER ARE RED.

<u>R1-2B1</u>


| DIMENSIONS (inches)/LETTER FONTS | | | | | | | | | |
|----------------------------------|----|-------|-------|-------|------|------|------|------|-------|
| А | В | С | D | E | F | G | Н | I | J |
| 30 | 4B | 233/4 | 191/2 | 171/2 | 51/4 | 31/8 | 21/2 | 31/2 | 21/2B |

REGULATORY SIGN

NHDOT STANDARD PLANS

YIELD TO PEDESTRAINS

| REV. | DATE | PLATE |
|------------|------|----------|
| 07-13-2001 | | 1 |
| 02-26-2010 | | STANDARD |
| | | SG-2 |



1.50" RADIUS, 0.50" BORDER, 0.50" INDENT BLACK ON WHITE


R3-3LB1

| | | D | IMENS | IONS | (inch | nes)/L | ETTER | FON1 | ΓS | | | | |
|----|----|----|-------|------|-------|--------|-------|------|------|----|------|-------------------------------|------|
| Α | В | С | D | E | F | G | H | I | J | K | L | M | N |
| 24 | 18 | 5C | 4C | 3 | 31/4 | 21/2 | 41/4 | 61/4 | 61/2 | 11 | 93/4 | 2 ⁵ / ₈ | 91/8 |

REGULATORY SIGN

NHDOT STANDARD PLANS

| REV. | DATE | PLATE |
|------------|------|----------|
| 07-13-2001 | | 2 |
| 02-26-2010 | | STANDARD |
| | | SG-2 |



1.50" RADIUS, 0.50" BORDER, 0.50" INDENT BLACK ON WHITE


R3-3RB1


| | | D | IMENS | IONS | (inch | ies)/L | ETTEF | R FONT | ΓS | | |
|----|----|----|-------|------|-------|--------|-------|--------|------|----|------|
| А | В | С | D | E | F | G | Н | I | J | K | L |
| 24 | 18 | 5C | 4C | 21/4 | 31/4 | 21/2 | 41/4 | 61/4 | 61/2 | 11 | 93/4 |


REGULATORY SIGN


| NHDOT STANDARD PLANS | REV. | DATE | PLATE |
|----------------------|------------|------|----------|
| | 07-13-2001 | | 3 |
| NO RIGHT TURN | 02-26-2010 | | STANDARD |
| | | | SG-2 |


<u>R3-8 SERIES</u> <u>LANE USE CONTROL SIGNS</u>
























EXAMPLE: R3-8(12)




MODIFY THE R3-8 SIGN TO REFLECT THE ACTUAL LANE USE COMBINATIONS


| NHDOT STANDARD PLANS | |
|-----------------------|--|
| | |
| ANE USE CONTROL SIGNS | |

| | ANDARD | IGNING STA | SI |
|----------|--------|------------|----|
| PLATE | DATE | REV. | |
| 4 | | 07-13-2001 | |
| STANDARD | | 02-26-2010 | |
| T ≤C-2 | | | |

New 1




2.0" RADIUS, NO BORDER, WHITE; "BRIDGE" BLACK C 85% SPACING; "C-1" BLACK C 75% SPACING; "POSTING" BLACK C 30% SPACING




R4-5dB1

2.0" RADIUS, NO BORDER, WHITE; "BRIDGE" BLACK C 85% SPACING; "E-1" BLACK C 100% SPACING; "POSTING" BLACK C 30% SPACING




2.0" RADIUS, NO BORDER, WHITE; "BRIDGE" BLACK C 85% SPACING; "C-2" BLACK C 65% SPACING; "POSTING" BLACK C 30% SPACING



<u>R4-5eB1</u>

2.0" RADIUS, NO BORDER, WHITE; "BRIDGE" BLACK C 85% SPACING; "E-2" BLACK C 100% SPACING; "POSTING" BLACK C 30% SPACING



2.0" RADIUS, NO BORDER, WHITE; "BRIDGE" BLACK C 85% SPACING; "C-3" BLACK C 65% SPACING; "POSTING" BLACK C 30% SPACING

| DIMENSIONS (inches)/LETTER FONTS | | | | | | | | | |
|----------------------------------|----|-------|-------|---------|-----------|-------------|--|--|--|
| Α | В | С | D | E | F | G | | | |
| 15 | 18 | 31/2C | 6C | 13 | 1 | 9 | | | |
| | Α | A B | A B C | A B C D | A B C D E | A B C D E F | | | |

| DIMENSIONS (inches)/ LETTER FONTS | | | | | | | | |
|-----------------------------------|------|--------------------------------|-------|--|--|--|--|--|
| Н | I | J | K | | | | | |
| 3 | 11/4 | 10 ⁵ / ₈ | 23/16 | | | | | |

REGULATORY SIGN

| | υ |
|-----|------------|
| | |
| | - |
| F A | |

| DIMENSIONS (inches)/LETTER FONTS | | | | | | | | | | |
|----------------------------------|----|----|----|--------------------------------|-------|------|-------------------|------|---|------|
| Α | В | С | D | E | F | G | Ξ | I | J | K |
| 30 | 36 | 7C | 23 | 18 ³ / ₄ | 191/2 | 31/2 | 5 ⁵ /8 | 51/4 | 3 | 41/2 |

DIMENSIONS (inches)/LETTER FONTS

DIMENSIONS (inches)/ LETTER FONTS

2

1 17/8 |

E

D

11/8

G

 $3C \mid 2C \mid 15\frac{1}{2} \mid 3\frac{1}{2} \mid 15\frac{3}{4} \mid 14\frac{1}{4} \mid 1\frac{1}{4} \mid 7\frac{1}{4}$

1.88" RADIUS, 0.75" BORDER, 0.50" INDENT, BLACK ON WHITE ARROW: 19.50" X 7.00"

R4-7B1

REGULATORY SIGN

NHDOT STANDARD PLANS ENTER HERE

В


18 24

| REV. | DATE | PLATE |
|------------|------|----------|
| 07-13-2001 | | 2 |
| 02-26-2010 | | STANDARD |
| | | SG-3 |

NHDOT STANDARD PLANS

BRIDGE RESTRICTIONS

| REV. | DATE | PLATE |
|------------|------|----------|
| 07-13-2001 | | 1 |
| 02-26-2010 | | STANDARD |
| | | SG-3 |
| | | |



1.88" RADIUS, 0.50" BORDER, 0.50" INDENT, BLACK ON WHITE

R5-10a(M)

| DIMENSIONS (inches)/LETTER FONTS | | | | | | | | | | |
|----------------------------------|----|----|------|-------------------------------|-------|-------|-------|----|------|----|
| A B C D E F G H I J K | | | | | | | | | | |
| 30 | 4D | 3C | 21/2 | 6 ³ / ₈ | 221/4 | 137/8 | 113/8 | 13 | 93/4 | 15 |

| DIMEN | ISIONS | (inch | (inches)/LETTER | | | | | |
|-------|-------------------------------|-------|-----------------|------|------|--|--|--|
| L | М | N | 0 | Р | Q | | | |
| 113/4 | 3 ⁷ / ₈ | 11/2 | 81/2 | 13/4 | 21/4 | | | |

1.50" RADIUS, 0.50" BORDER, 0.50" INDENT, BLACK ON WHITE

<u>R5-10B1</u>

REGULATORY SIGN

| HDOT STANDARD PLANS | REV. [| PLATE | |
|---------------------|------------|-------|----------|
| | 07-13-2001 | | 3 |
| NO PEDESTRIANS | 02-26-2010 | | STANDARD |
| | | | SG-3 |

REGULATORY SIGN

| N | HDOT | STANDARD PLANS | |
|--------|------|----------------|----------|
| CLOSED | TO | UNA UTHORIZED | VEHICLES |

| SI | GNING STA | ANDARD | |
|----|------------|--------|----------|
| | REV. | DATE | PLATE |
| | 07-13-2001 | | 4 |
| | 02-26-2010 | | STANDARD |
| | | | 1 SG-3 |

STANDARD NO. SG-3

S

STANDARD

NO. SG-3

REVISION DATE 07-13-2001

02-26-2010

*.DGN FILE NAME

SG-3


NO. SG-4

REVISION DATE 07-13-2001 02-26-2010

*.DGN FILE NAME SG-4



| COLOR | CHART |
|---------------|-------|
| BORDER | RED |
| | BLACK |
| | RED |
| NO PARKING | RED |
| BACKGROUND | WHITE |



1.50" RADIUS, 0.50" BORDER, 0.50" INDENT,

| | DIMENSIONS (inches)/LETTER FONTS | | | | | | | | | | | | | |
|----|----------------------------------|----|----|------|-------|-------------------------------|----|------|---|------|------|------|------|---|
| А | В | С | D | E | F | G | Н | I | J | К | L | М | N | 0 |
| 24 | 30 | 3E | 13 | 51/4 | 181/2 | 5 ³ / ₄ | 16 | 21/4 | 3 | 51/2 | 93/8 | 23/4 | 91/8 | 4 |

R7-2B1

NHDOT STANDARD PLANS

NO PARKING

| | DIMENSIONS (inches)/LETTER FONTS | | | | | | | | | | | |
|----|----------------------------------|----|----|---|-------|---|------|-------------------------------|------|------|-----|---|
| А | В | С | D | E | F | G | Н | I | J | K | | М |
| 18 | 24 | 3B | 10 | 5 | 143/4 | 4 | 61/2 | 1 ⁵ / ₈ | 23/8 | 21/4 | 6EM | 2 |

REGULATORY SIGN

REGULATORY SIGN


BLACK ON WHITE

<u>R10-9</u>

| REV. | DATE | PLATE | |
|------------|------|----------|--|
| 07-13-2001 | | 1 | |
| 02-26-2010 | | STANDARD | |
| | | SG-4 | |

| NHDOT STANDARD PLANS | | | | | | | | | | |
|----------------------|----|----------|----|--------|--|--|--|--|--|--|
| YIELD | TO | VEHICLES | ON | BRIDGE | | | | | | |

| REV. DATE | PLATE |
|------------|----------|
| 07-13-2001 | 2 |
| 02-26-2010 | STANDARD |
| | ☐ SG-4 |




| | DIMENSIONS (inches)/LETTER FONTS | | | | | | | | | | | | |
|-----------------------------------------|----------------------------------|--|--|--|--|--|--|--|--|--|--|--|--|
| Α | A B C D E F G H I J | | | | | | | | | | | | |
| 24 30 5E 4D 91/2 131/4 61/2 4 91/2 181/ | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |

| DIMEN | ISIONS | (inch | es)/LE | ETTER | FONTS |
|-------|--------|-------|--------|-------|-------|
| K | L | М | N | 0 | Р |
| 71/4 | 2 | 31/4 | 21/4 | 3 | 27/8 |

1.50" RADIUS, 0.50" BORDER, 0.38" INDENT, BLACK ON WHITE

R10-11A(M)



| DIMEN | NS I ONS | (inch | nes)/LE | ETTER | FONTS |
|-------|------------------|-------|---------|-------|-------|
| K | L | М | N | 0 | Р |
| 41/4 | 51 _{/8} | 31/4 | 4 | 3 | 13/4 |

DIMENSIONS (inches)/LETTER FONTS

D

24 | 30 | 5E | 4D | 4C |

G

 $8 \quad |15^{1}/_{2}| |13^{3}/_{4}| |5^{3}/_{8}| |7^{7}/_{8}$

1.50" RADIUS, 0.50" BORDER, 0.38" INDENT, BLACK ON WHITE

R10-11B1

REGULATORY SIGN

| | NHDOT S | TAND | ARD PL | ANS |
|----|---------|------|--------|-------|
| NO | TURN | ON | RED | ARROW |

| REV. | DATE | PLATE |
|------------|------|----------|
| 07-13-2001 | | 3 |
| 02-26-2010 | | STANDARD |
| | | SG-4 |
| | | |

| REGULATORY | SIGN | | | | | |
|------------|------|------|-----------|----------|----|-----|
| | | NHDC | OT STANDA | ARD PLAN | S | |
| | | NO I | RIGHT | TURN | ON | RED |


| SI | SIGNING STANDARD | | | | | | | | | | |
|----|------------------|------|----------|--|--|--|--|--|--|--|--|
| | REV. | DATE | PLATE | | | | | | | | |
| | 07-13-2001 | | 4 | | | | | | | | |
| | 02-26-2010 | | STANDARD | | | | | | | | |
| | | | SG-4 | | | | | | | | |



NO. SG-5

REVISION DATE 07-13-2001 02-26-2010

*.DGN FILE NAME SG-5



P1 R1 P1 R1 N1

| DIMENSIONS (inches)/LETTER FONTS | | | | | | | | | | | | | | | | | |
|----------------------------------|----|----|----|------|--------------------------------|------|------|--------------------------------|------|------|--------------------|-------------------------------|--------------------------------|-------------------------------|-------------------------------|--------------------------------|--------------------------------|
| Α | В | С | D | E | F | G | Ξ | I | J | K | L | М | N | 0 | Р | Q | R |
| 60 | 48 | 6C | 5B | 11/2 | 42 ³ / ₈ | 37/8 | 1 | 95/8 | 31/8 | 43/4 | 20 ⁷ ⁄8 | 5 ³ / ₄ | 12 ³ ⁄8 | 53/4 | 5 ³ / ₄ | 19 ³ ⁄ ₈ | 23 ³ ⁄8 |
| 84 | 60 | 8D | 6B | 2 | 61 | 51/8 | 11/2 | 13 ³ / ₈ | 3 | 51/4 | 321/4 | 61/4 | 19 ³ / ₄ | 6 ³ / ₈ | 87/8 | 24 ³ / ₈ | 37 ³ / ₄ |

| | DIMENSIONS (inches)/LETTER FONTS | | | | | | | | | | | | | | | | | | |
|------|----------------------------------|-------------------|-------|-------|-------|-------------------|--------------------------------|-------|-------------------|------|-------------------|-------------------|--------------------|------|----|------|------|-------|--------------------|
| S | Т | U | ٧ | W | X | Y | Z | A1 | B1 | C1 | D1 | E1 | F1 | G1 | H1 | I 1 | J1 | K1 | L1 |
| 6 | 7 ⁵ /8 | 3 ⁵ /8 | 237/8 | 28 | 81/8 | 3 ⁵ /8 | 11 ³ / ₄ | 83/4 | 5 ³ ⁄8 | 1 | 5 ³ /8 | 7 ³ /8 | 12 ¹ /8 | 83/8 | 3 | 21/2 | 2 | 17 | 11/2 |
| 61/8 | 121/4 | 31/2 | 32 | 407/8 | 111/8 | 3 ⁵ /8 | 15 ³ / ₄ | 121/2 | 5 ³ /8 | 21/4 | 5 ³ /8 | 7 ⁵ /8 | 191/2 | 11 | 5 | 2 | 31/2 | 211/2 | 2 ⁵ /16 |

| ĺ | DIMEN | SIONS | (inc | hes)/ | LETTE | R FON | ITS |
|-----|-------------------|--------------------------------|-------------------|--------------------------------|-------|-------|-----|
| M1 | N1 | 01 | P1 | Q1 | R1 | S1 | T1 |
| 1 | 1 ³ ⁄8 | 17 ⁵ ⁄8 | 3 ⁵ /8 | 131/4 | 73/4 | 31/2 | 18 |
| 7/8 | 41/2 | 21 ³ / ₄ | 6 | 16 ¹ / ₄ | 91/2 | 3 | 24 |

60" × 48"

Symbol RG015; 1.25" RADIUS, 0.75" BORDER, 0.75" INDENT, BLACK ON WHITE "RSA 256:107-a" Triumvirate Compressed; "COMMON SENSE FOR ALL", WHITE ON BLUE

84" × 60"

Symbol RG015; 1.25" RADIUS, 0.75" BORDER, 0.75" INDENT, BLACK ON WHITE "RSA 256:107-a" Triumvirate Compressed; "COMMON SENSE FOR ALL", WHITE ON BLUE

REGULATORY SIGN

R16-1B1

NHDOT STANDARD PLANS NH LAW BUCKLE UP

REV. DATE PLATE 07-13-2001 STANDARD 02-26-2010 SG-5

RSA 265:6 | B1 |C1| D1 | G1 I1 X F1

P1 |

N1

| | DIMENSIONS (inches)/LETTER FONTS | | | | | | | | | | | | | | | | | | | | | | |
|----|----------------------------------|----|----|------|------|----|------|------|--------------------------------|--------------------|------|-------|----|------|--------------------------------|--------------------------------|-------------------|--------------------------------|------|----|-------|------|------|
| А | В | С | D | E | F | G | Н | I | J | K | L | М | N | 0 | Р | Q | R | S | Т | U | V | W | Х |
| 48 | 36 | 4D | 5D | 11/2 | 3 | 15 | 33/8 | 31/4 | 6 ³ / ₄ | 12 ³ ⁄8 | 31/4 | 18 | 27 | 3 | 18 ¹ / ₂ | 12 ³ / ₄ | 11/2 | 113/4 | 31/2 | 21 | 21 | 6 | 31/2 |
| 72 | 48 | 5D | 7D | 11/2 | 41/4 | 23 | 6 | 6 | 10 ⁵ / ₈ | 171/2 | 41/4 | 273/4 | 40 | 41/4 | 28 ⁷ ⁄8 | 173/4 | 4 ⁵ /8 | 16 ¹ / ₄ | 5 | 32 | 311/2 | 81/2 | 5 |

| | DIMENSIONS (inches)/LETTER FONTS | | | | | | | | | | | | | | | | | | | |
|-------|----------------------------------|--------------------------------|------|------|-------------------|--------------------------------|--------------------------------|------|-----|-------------------|------|------|----|----|-----|------|--------------------------------|------|------|------|
| Υ | Z | Α1 | В1 | C1 | D1 | E1 | F1 | G1 | H1 | I 1 | J1 | K 1 | L1 | M1 | N1 | 01 | P1 | Q1 | R1 | S1 |
| 12 | 11/4 | 113/4 | 11/8 | 2 | 11/4 | 11 ³ / ₄ | 35 ¹ / ₂ | 33/4 | 5/8 | 4 ⁵ /8 | 23/8 | 11/2 | 3 | 17 | 1/2 | 63/8 | 13 ¹ / ₈ | 11/2 | 11/2 | 23/8 |
| 163/4 | 33/4 | 16 ⁷ / ₈ | 31/4 | 21/2 | 3 ⁵ /8 | 15 ⁷ / ₈ | 54 | 41/4 | 1 | 4 | 2 | 11/2 | 4 | 26 | 3/4 | 7 | 16 | 21/2 | 23/4 | 4 |

48" x 36"
Symbol RG015; 1.25" RADIUS, 0.75" BORDER, 0.75" INDENT, BLACK ON WHITE
"RSA 265:6" Triumvirate Compressed;
BB GRADE PLYWOOD

 $72'' \times 48''$ Symbol RG015; 1.25" RADIUS, 0.75" BORDER, 0.75" INDENT, BLACK ON WHITE "RSA 265:6" Triumvirate Compressed; BB GRADE PLYWOOD

REGULATORY SIGN

SIGNING STANDARD NHDOT STANDARD PLANS REV. DATE PLATE 2 07-13-2001 NH WORK ZONE SPEEDING STANDARD 02-26-2010 SG-5

<u>R50-1</u>



S

STANDARD


NO. SG-6

STANDARD

NO. SG-6

REVISION DATE 07-13-2001 02-26-2010

*.DGN FILE NAME SG-6



1.50" RADIUS. 0.68" BORDER, 0.375" INDENT, BLACK ON WHITE; BB GRADE PLYWOOD SIGN

| DIMENSIONS (inches)/LETTER FONTS | | | | | | | | | | | | |
|----------------------------------|-----------------------|----|----|--------------------------------|-------|--------------------------------|------|-------|------|------|--|--|
| Α | A B C D E F G H I J K | | | | | | | | | | | |
| 48 | 24 | 5D | 4D | 39 ³ / ₄ | 241/2 | 37 ¹ / ₂ | 41/8 | 123/4 | 51/4 | 21/2 | | |

<u>R200-S</u>

NHDOT STANDARD PLANS

UNAUTHORIZED TRAVEL

REGULATORY SIGN

REV. DATE 07-13-2001 STANDARD 02-26-2010 SG-6

1.50" RADIUS. 0.50" BORDER, 0.375" INDENT, BLACK ON YELLOW;


RIGHT / LEFT LANE ENDS

NHDOT STANDARD PLANS

TWO WAY TRAFFIC

<u>W4-2a(R)</u>

| | DIME | ENSION | NS (in | nches |)/LET | TER F | ONTS | |
|----|------|--------|--------|-------|-------|-------|------|---------|
| Α | В | С | D | E | F | G | Н | I |
| 24 | 24 | 5C | 16 | 14 | 4 | 5 | 23/4 | 13/4 |
| | | | | | | | NHI | OOT STA |



1.50" RADIUS. 0.50" BORDER, 0.375" INDENT, BLACK ON YELLOW;

W4-2a(L)

| DIMENSIONS (inches)/LETTER FONTS | | | | | | | | | |
|----------------------------------|----|----|----|----|------|---|-------------------------------|------|--|
| Α | В | С | D | E | F | G | Н | I | |
| 24 | 24 | 5C | 13 | 14 | 51/2 | 5 | 2 ³ / ₄ | 13/4 | |

WARNING SIGN

PLATE 2 REV. DATE 07-13-2001 STANDARD 02-26-2010 SG-6

1.50" RADIUS. 0.50" BORDER, 0.375" INDENT, BLACK ON YELLOW;

<u>W5-B2</u>

| | DIMENSIONS (inches)/LETTER FONTS | | | | | | | | | | | |
|----|----------------------------------|----|----|-------|----|------|------|------|---|--|--|--|
| Α | В | С | D | E | F | G | Н | I | J | | | |
| 24 | 24 | 5B | 19 | 171/2 | 13 | 21/2 | 31/4 | 51/2 | 2 | | | |

1.50" RADIUS. 0.63" BORDER, 0.375" INDENT, BLACK ON YELLOW;

<u>W6-3b</u>

| | DIMENSIONS (inches)/LETTER FONTS | | | | | | | | | | | |
|----|----------------------------------|----|----|-------|-------|-------------------------------|---|-------------------|------|------|--|--|
| А | В | С | D | E | F | G | Н | I | J | K | | |
| 24 | 18 | 4C | 8 | 81/4 | 161/2 | 1 ³ / ₈ | 4 | 33/4 | 33/4 | 21/2 | | |
| 30 | 24 | 5C | 10 | 101/2 | 203/4 | 21/4 | 5 | 4 ⁵ /8 | 5 | 4 | | |

WARNING SIGN

| SI | GNING ST | ANDARD |
|----|------------|--------|
| | REV. | DATE |
| | 07 17 2001 | |

PLATE 4 07-13-2001 STANDARD 02-26-2010 SG-6

WARNING SIGN

| NHDOT STANDARD PLANS | REV. DATE | PLATE |
|----------------------|------------|----------|
| | 07-13-2001 | 3 |
| BRIDGES FREEZE FIRST | 02-26-2010 | STANDARD |
| | | SG-6 |

S


STANDARD

NO. SG-7

REVISION DATE 07-13-2001 02-26-2010

*.DGN FILE NAME

SG-7



TON ON TELECUTY

W7-B7

| | DIMENSIONS (inches)/LETTER FONTS | | | | | | | | | | | | |
|----|----------------------------------|----|------|------|-------|-------|-------------------|------|------|-------|------|------|------|
| Α | В | С | D | E | F * | G | Н | I * | J * | K | L | М | N |
| 24 | 18 | 4C | 61/2 | 6 | 91/2 | 14 | 31/2 | 21/2 | 5 | 10 | 4 | 23/4 | 2 |
| 30 | 24 | 5C | 81/2 | 73/4 | 117/8 | 171/2 | 3 ⁵ /8 | 33/8 | 61/4 | 133/4 | 51/4 | 4 | 21/2 |


* DIMENSION VARIES WITH DIFFERENT NUMBERS

WARNING SIGN

1/4, 1/2, 3/4 MILE AHEAD

NHDOT STANDARD PLANS

| REV. | DATE | PLATE |
|------------|------|----------|
| 07-13-2001 | | 1 |
| 02-26-2010 | | STANDARD |
| | | SG-7 |




1.50" RADIUS. 0.50" BORDER, 0.375" INDENT, BLACK ON YELLOW;

W7-B2

| | | DΙ | MENSI | ONS (| inche | s)/LE | TTER | FONTS | 5 | |
|----|----|----|----------------|----------------|-------|-------------------------------|-------|-------|---|------|
| А | В | С | D * | E * | F | G * | П | I | J | K |
| 24 | 18 | 4C | 81/8 | 4 | 43/8 | 33/4 | 14 | 5 | 3 | 31/2 |
| 30 | 24 | 5C | 101/4 | 5 | 51/2 | 4 ⁵ / ₈ | 171/2 | 61/4 | 4 | 5 |

* DIMENSION VARIES WITH DIFFERENT NUMBERS

WARNING SIGN



| 1.50" | RADIUS. | 0.50" | BORDER, | 0.375" | INDENT, | |
|-------|----------|-------|---------|--------|---------|--|
| BLACK | ON YELLI | OW; | | | | |


| | DIMENSIONS (inches)/LETTER FONTS | | | | | | | | | |
|-------------------------|----------------------------------|----|---|--------------------------------|-------|------|------|----------------|------|------|
| A B C D* E F G* H I J K | | | | | | | | K * | | |
| 24 | 18 | 4C | 3 | 121/2 | 14 | 31/4 | 5 | 3 | 31/2 | 21/4 |
| 30 | 24 | 5C | 4 | 15 ¹ / ₂ | 171/2 | 37/8 | 61/4 | 4 | 5 | 23/4 |

* DIMENSION VARIES WITH DIFFERENT NUMBERS

<u>W7-B3</u>

WARNING SIGN

| DOT STANDARD PLANS | REV. DATE | PLATE |
|--------------------|------------|---------|
| | 07-13-2001 | 3 |
| X MILES AHEAD | 02-26-2010 | STANDAI |
| | | SG-7 |




3.0" RADIUS, 1.25" BORDER, 0.75" INDENT, BLACK ON YELLOW

NHDOT STANDARD PLANS

MOTORCYCLE CAUTION

THE SLIPPERY SYMBOL IS FROM W8-5

FOR SCALING PURPOSES SEE BELOW




| DIMENSIONS (inches)/ LETTER FONTS | | | | | | | |
|--------------------------------------|----|-------|-------|----|--------------------|--------------------------------|--|
| | Α | В | С | D | Е | F | |
| | 48 | 291/8 | 123/4 | 20 | 19 ⁷ ⁄8 | 12 ³ / ₄ | |

WARNING SIGN


| | | _ |
|---------|----------|---|
| SIGNING | STANDARD | |

| | ANDARD | SIGNING ST | SI |
|---------------|--------|------------|----|
| PLATE | DATE | REV. | |
| 4 | | 07-13-2001 | |
| STANDARD | | 02-26-2010 | |
| 1 5G-7 | | | |




NO. SG-8

REVISION DATE 07-13-2001



<u>W8-5F</u>

| DIMENSIONS (inches)/LETTER FONTS | | | | | | | | |
|----------------------------------|----|----|-------|--------------------------------|------|------|---|---|
| A B C D E F G H I | | | | | | | | I |
| 30 | 24 | 5B | 193/4 | 25 ¹ / ₂ | 51/8 | 21/4 | 4 | 5 |




1.50" RADIUS, 0.63" BORDER, 0.375" INDENT, BLACK ON YELLOW;

<u>W8-5G</u>

| DIMENSIONS (inches)/LETTER FONTS | | | | | | | | |
|----------------------------------|----|----|-------|--------------------------------|------|------|---|---|
| A B C D E F G H I | | | | | | | | I |
| 30 | 24 | 5B | 193/4 | 25 ³ / ₄ | 51/8 | 21/8 | 4 | 5 |

| DIMENSIONS (inches)/LETTER FONTS | | | | | | | | | |
|----------------------------------|----|----|------|-------|--------------------------------|-------|-------------------|------|-------------------------------|
| Α | В | С | D | E | F | G | Н | I | J |
| 30 | 5C | 5B | 93/4 | 243/4 | 25 ³ / ₄ | 101/8 | 2 ⁵ /8 | 21/8 | 3 ³ / ₄ |




1.88" RADIUS, 0.75 BORDER, 0.375 INDENT, BLACK ON YELLOW;

<u>W8-5H</u>

WARNING SIGN

| | WARNING | SIGN | | WARN | NING SIGN |
|----------------------|------------|----------|----------------------------|------------|-----------|
| NHDOT STANDARD PLANS | REV. DATE | PLATE | NHDOT STANDARD PLANS | REV. DATE | PLATE |
| | 07-13-2001 | 11 | | 07-13-2001 | 2 |
| $GROOVED\ PAVEMENT$ | 02-26-2010 | STANDARD | $END\ GROOVED\ CENTERLINE$ | 02-26-2010 | STANDARD |
| | | SG-8 | | | SG-8 |
| | | | | | |



<u>W11-B5</u>

NHDOT STANDARD PLANS


MOOSE CROSSING

| D: | DIMENSIONS (inches) | | | | | | | | |
|---------------|---------------------|---|--------------------------------|--------------------|--|--|--|--|--|
| /LETTER FONTS | | | | | | | | | |
| Α | В | С | D | E | | | | | |
| 36 | 6D | 4 | 14 ⁵ / ₈ | 18 ⁵ ⁄8 | | | | | |
| 48 | 8D | 5 | 20 | 25 | | | | | |
| | | | | | | | | | |

48"x 48"
3.0" RADIUS, 1.25" BORDER, 0.75" INDENT, BLACK ON YELLOW;

WARNING SIGN

| REV. | DATE | PLATE |
|------------|------|----------|
| 07-13-2001 | | 3 |
| 02-26-2010 | | STANDARI |
| | | SG-8 |



<u>W11B-6</u>

30"x 30" 1.88" RADIUS, 0.75" BORDER, 0.50" INDENT, BLACK ON YELLOW;

36"x 36" 2.25" RADIUS, 0.88" BORDER, 0.63" INDENT, BLACK ON YELLOW;

NHDOT STANDARD PLANS

DEER CROSSING

48"x 48"
3.0" RADIUS, 1.25" BORDER, 0.75" INDENT, BLACK ON YELLOW;

WARNING SIGN

| SI | GNING STANDARD |
|----|----------------|
| | REV DATE |

DIMENSIONS (inches) /LETTER FONTS

48 8C 5 20 25

D

| | SIGNING STANDARD | | | | |
|--------|------------------|------------|--|--|--|
| PLATE | DATE | REV. | | | |
| 4 | | 07-13-2001 | | | |
| | | 02-26-2010 | | | |
| 1 SG-8 | | | | | |




NO. SG-9


STANDARD

NO. SG-9

REVISION DATE 07-13-2001 02-26-2010

*.DGN FILE NAME SG-9





W14-B1

NHDOT STANDARD PLANS

TRAFFIC ENTERING

WARNING SIGN

DIMENSIONS (inches)/LETTER FONTS

5C 21 24 14¹/₂

| REV. | PLATE | |
|------------|-------|----------|
| 07-13-2001 | | 1 |
| 02-26-2010 | | STANDARD |
| | | SG-9 |


DIMENSIONS (inches)/LETTER FONTS $36 | 24|_{2} | 22|_{2} | 21 | 10|_{4} | 2^{3}_{4} | 14|_{4} | 3|_{2} | 12^{3}_{4} | 50$

| NHDOT STANDARD PLANS | | | | | |
|-----------------------------|--|--|--|--|--|
| TRUCKS TURNING AND ENTERING | | | | | |

36"x 36", 2.25" RADIUS, 0.88" BORDER, 0.63" INDENT, BLACK ON YELLOW;

| REV. DATE | | PLATE |
|------------|---|----------|
| 07-13-2001 | | 2 |
| 02-26-2010 | | STANDARD |
| | | SG-9 |
| • | • | |
| | | |

WARNING SIGN



W14-B3

| DIMENSIONS (inches)/LETTER FONTS | | | | | | ONTS |
|----------------------------------|----|-------|--------------------------------|----|------|--------------------------------|
| Α | В | С | D | E | F | G |
| 30 | 5C | 203/4 | 25 ⁵ ⁄8 | 15 | 3 | 121/2 |
| 36 | 6C | 23 | 28 ¹ / ₄ | 18 | 31/2 | 15 ¹ / ₂ |
| 48 | 8C | 26 | 40 | 25 | 4 | 19 ¹ / ₂ |


30"x 30", 1.88" RADIUS, 0.75" BORDER, 0.50" INDENT, BLACK ON YELLOW;

36"x 36", 2.25" RADIUS, 0.88" BORDER, 0.63 INDENT, BLACK ON YELLOW;

48"x 48", 3.0" RADIUS, 1.25" BORDER, 0.75" INDENT, BLACK ON YELLOW;

WARNING SIGN

| IHDOT STANDARD PLANS | REV. | DATE | PLATE |
|----------------------|------------|------|----------|
| | 07-13-2001 | | 3 |
| TRUCKS ENTERING | 02-26-2010 | | STANDARD |
| | | | SG-9 |



W14-B2

1.50" RADIUS, 0.60" BORDER, 0.375 INDENT, BLACK ON YELLOW OR BLACK ON FLUORESCENT YELLOW GREEN STANDARD ARROW CUSTOM 13.4"x 8.1" @ 210°

W16-7pL(M)

| DIMENSIONS (inches)/ LETTER FONTS | | | | | | |
|--------------------------------------|----|------|-------|-------------------------------|------|--|
| A B C D E F | | | | | | |
| 24 | 12 | 81/2 | 121/2 | 5 ³ / ₄ | 13/4 | |

DOWNWARD ARROW

WARNING SIGN


| | SIGNING STANDAR | | |
|----------------------|-----------------|--|------|
| NHDOT STANDARD PLANS | REV. DATE | | DATE |
| | | | |

| PLATE | REV. DATE | |
|----------|------------|--|
| 4 | 07-13-2001 | |
| STANDARD | 02-26-2010 | |
| 1 SG-9 | | |

NO. SG-10

REVISION DATE 07-13-2001 02-26-2010

*.DGN FILE NAME SG-10



1.50" RADIUS, 0.50" BORDER, 0.375" INDENT, BLACK ON YELLOW OR FLUORESCENT YELLOW GREEN

W16-9p(M)

| DIMENSIONS (inches)/ LETTER FONTS | | | | | |
|--------------------------------------|----|----|--------------------------------|------|------|
| Α | В | С | D | E | F |
| 36 | 12 | 7D | 30 ¹ / ₂ | 23/4 | 21/2 |

WARNING SIGN

AHEAD PLAQUE

NHDOT STANDARD PLANS

| REV. | PLATE | |
|------------|-------|----------|
| 07-13-2001 | | 1 |
| 02-26-2010 | | STANDARD |
| | | SG-10 |

F D A G E F

1.50" RADIUS, 0.38" BORDER, 0.375" INDENT, BLACK ON YELLOW, BB GRADE PLYWOOD SIGN

W16-8(M)

| DIMENSIONS (inches)/LETTER FONTS | | | | | | | | | |
|----------------------------------|---|----|---|---|---|---|---|--|--|
| Α | В | С | D | E | F | G | Н | | |
| 36 | 8 | 4C | * | * | * | 4 | 2 | | |


*VARIES DEPENDING ON LENGTH OF WORD.

NHDOT STANDARD PLANS

ADVANCE STREET NAME PLAQUE

WARNING SIGN

| PLATE | DATE | REV. | |
|-----------|------|------------|--|
| 2 | | 07-13-2001 | |
| STANDARD | | 02-26-2010 | |
| 1 SG-10 I | | | |



1.50" BORDER RADIUS, 0.38" BORDER, 0.375" INDENT, BLACK ON YELLOW; BB GRADE PLYWOOD SIGN STANDARD CUSTOM ARROW 4.0" X 4.0"

W16-8b(M)

| | DIMENSIONS (inches)/LETTER FONTS | | | | | | | | | | | |
|----|----------------------------------|--|--|--|--|--|--|--|--|--|--|--|
| А | A B C D E F G H I J K L M | | | | | | | | | | | |
| 36 | 36 | | | | | | | | | | | |

*VARIES DEPENDING ON LENGTH OF WORD.


WARNING SIGN

NHDOT STANDARD PLANS

ADVANCE STREET NASME PLAQUE

(TWO STREETS)

| REV. | DATE | PLATE |
|------------|------|----------|
| 07-13-2001 | | 3 |
| 02-26-2010 | | STANDARD |
| | | SG-10 |



1.50" RADIUS, 0.38" BORDER, 0.375" INDENT, BLACK ON YELLOW; BB GRADE PLYWOOD SIGN STANDARD CUSTOM ARROW 4.0" X 4.0"

W16-8c(M)

| DIMENSIONS (inches)/LETTER FONTS | | | | | | | | | | | | | |
|----------------------------------|----|----|---|---|---|---|---|---|---|---|---|---|---|
| Α | В | С | D | E | F | G | Н | I | J | K | L | М | N |
| 36 | 24 | 4B | * | * | * | * | * | * | * | * | 3 | * | 4 |

* VARIES DEPENDING ON LENGTH OF WORD.

NHDOT STANDARD PLANS

ADVANCE STREET NAME PLAQUE

(THREE STREETS)

WARNING SIGN

| S | | | |
|---|------------|------|----------|
| | REV. | DATE | PLATE |
| | 07-13-2001 | | 4 |
| | 02-26-2010 | | STANDARD |
| | | | SG-10 |




NO. SG-11

REVISION DATE 07-13-2001

02-26-2010

*.DGN FILE NAME

SG-11



<u>W5-3a</u>

DIMENSIONS (inches)/LETTER FONTS * VARIES G 191/4 24 23

CONSTRUCTION SIGN

REV. DATE 07-13-2001 **STANDARD** 02-26-2010 SG-11

BUSINESS


3.0" RADIUS, 0.875" BORDER, 0.625" INDENT, BLACK ON ORANGE; BB GRADE PLYWOOD SIGN

W14-B4

| | DIMENSIONS (inches)/LETTER FONTS | | | | | | | | | | | | |
|-------------------------|----------------------------------|----|--------------------------------|--------------------------------|----|------|-------------------|---|------|---|---|--|--|
| A B C D E F G H I J K L | | | | | | | | | | | | | |
| 36 | 30 | 4D | 25 ¹ / ₂ | 26 ³ / ₄ | 12 | 51/4 | 4 ⁵ /8 | 6 | 31/2 | 4 | 5 | | |

NHDOT STANDARD PLANS

BUSINESS ENTRANCE




NO BORDER, BLACK ON ORANGE; BB GRADE PLYWOOD SIGN

W14-B5

| DIMENSIONS (inches)/LETTER FONTS | | | | | | | | | | |
|----------------------------------|---|---|---|---|---|--|--|--|--|--|
| А | В | С | D | E | F | | | | | |
| 12 | 6 | 8 | 2 | 4 | 1 | | | | | |

CONSTRUCTION SIGN

| REV. | PLATE | |
|------------|-------|----------|
| 07-13-2001 | | 2 |
| 02-26-2010 | | STANDARD |
| | | SG-11 |



NHDOT STANDARD PLANS

BRIDGE WIDTH

48"x 48", 3.0" RADIUS, 1.25" BORDER, 0.75" INDENT, BLACK ON ORANGE, BB GRADE PLYWOOD SIGN


| DIMENSIONS (inches)/LETTER FONTS | | | | | | | | | | | |
|----------------------------------|----|----|-------|----|----|---|--------------------------------|--|--|--|--|
| A B C D E F G H | | | | | | | | | | | |
| 48 | 7D | 25 | 301/2 | 32 | 19 | 3 | 19 ¹ / ₂ | | | | |

CONSTRUCTION SIGN

PLATE

STANDARD SG-11

| NHDOT STANDARD PLANS | REV. DATE |
|----------------------|------------|
| BRIDGE WORK AHEAD | 07-13-2001 |
| | 02-26-2010 |
| | |



48" x 48"
3.0" RADIUS, 1.25" BORDER, 0.75" INDENT, BLACK ON ORANGE, BB GRADE PLYWOOD

NHDOT STANDARD PLANS

MOTORCYCLES USE CAUTION


DIMENSIONS (inches)/LETTER FONTS


| А | В | С | D | E | F | G | Н |
|----|----|--------------------------------|-------|----|--------------------|------|-------|
| 48 | 6C | 12 ¹ / ₈ | 271/8 | 42 | 17 ¹ /8 | 31/2 | 231/4 |

CONSTRUCTION SIGN

| SIGNING | STANDARD |
|---------|----------|
| | |

| | ANDARD | SIGNING ST |
|----------|--------|------------|
| PLATE | DATE | REV. |
| 4 | | 07-13-2001 |
| STANDARI | | 02-26-2010 |
| | | |





3.0" RADIUS, 1.25" BORDER, 0.75" INDENT, BLACK ON ORANGE, BB GRADE PLYWOOD SIGN

G20-1(M)

| DIMENSIONS (inches)/LETTER FONTS | | | | | | | | |
|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------------------|--|--|--|--|--|---|---|
| A B C D E F G H I J K L M N | | | | | | | Ν | |
| 72 36 8C 22 ¹ / ₄ 24 ¹ / ₄ 21 * 24 ³ / ₄ 8 ³ / ₄ 8 * * 7 ¹ / ₂ 5 | | | | | | | | 5 |
| | * VARIES DEPENDING ON | | | | | | | |

NHDOT STANDARD PLANS

ROAD WORK NEXT X-MILES

NUMBER OF MILES (X)

| DIGIN | | CONSII |
|----------|------|------------|
| PLATE | DATE | REV. |
| 2 | | 07-13-2001 |
| STANDARI | | 02-26-2010 |
| SG-12 | | |

DIMENSIONS (inches)/LETTER FONTS 6C 211/8 295/8 335/8 201/8 31/2 201/4


48"× 48" 3.0" RADIUS, 1.25" BORDER, 0.75" INDENT, BLACK ON ORANGE, BB GRADE PLYWOOD

NHDOT STANDARD PLANS

GROOVED PAVEMENT

<u>W20-6a</u>

| CONST | RUCTION | SIGN |
|------------|---------|----------|
| REV. | DATE | PLATE |
| 07-13-2001 | | 1 |
| 02-26-2010 | | STANDARD |
| | | SG-12 |




1.88" RADIUS, 1.25" BORDER, 0.75" INDENT, BLACK ON ORANGE, BB GRADE PLYWOOD SIGN

<u>G20-2a</u>

| DIMENSIONS (inches)/LETTER FONTS | | | | | | | | | |
|----------------------------------|----|----|--------------------------------|--------------------|-------|--------------------------------|------|---|------|
| А | В | С | D | E | F | G | Н | I | J |
| 48 | 24 | 6C | 11 ³ / ₄ | 16 ⁷ ⁄8 | 181/8 | 18 ¹ / ₈ | 31/2 | 6 | 41/4 |

CONSTRUCTION SIGN

| NHDOT STANDARD PLANS | REV. DATE | PLATE |
|----------------------|------------|----------|
| END ROAD WORK | 07-13-2001 | 3 |
| | 02-26-2010 | STANDARD |
| | | SG-12 |




1.50" RADIUS, 1.25" BORDER, 0.75" INDENT, BLACK ON ORANGE, BB GRADE PLYWOOD SIGN

<u>G20-4a</u>

| DIMENSIONS (inches)/LETTER FONTS | | | | | | | | | | | | |
|----------------------------------|----|----|-------|-------|------|----|-------|--------------------|----|---|---|------|
| Α | В | С | D | E | F | G | Н | I | J | К | L | М |
| 60 | 30 | 5C | 407/8 | 221/4 | 61/2 | 10 | 211/2 | 9 ⁹ ⁄16 | 19 | 6 | 5 | 33/4 |

CONSTRUCTION SIGN

| | SIGNING STANDARD | |
|------------------------------------|------------------|---------|
| NHDOT STANDARD PLANS | REV. DATE | PLATE |
| | 07-13-2001 | 4 |
| CONSTRUCTION VEHICLE DO NOT FOLLOW | 02-26-2010 s | TANDARD |





| | | D | IMENS | IONS | (inch | es)/L | ETTER | FONT | S | | |
|----|----|----|-------------------------------|-------------------------------|-------|-------|-------|-------|--------------------------------|-------|----|
| А | В | С | D | Е | F | G | Н | I | J | К | L |
| 30 | 24 | 3C | 6 ³ / ₄ | 1 ³ / ₈ | 3/4 C | 173/4 | 93/4 | 251/2 | 16 ¹ / ₈ | 211/8 | 24 |

| DIMENSIONS (inches)/LETTER FONTS | | | | | | | | | | | | |
|----------------------------------|------|------|-------|------|------|------|------|---|------|------|------|------|
| М | Ν | 0 | Р | Ю | R | S | Т | U | ٧ | W | X | Y |
| 41/4 | 21/2 | 21/4 | 101/2 | 33/8 | 51/2 | 17/8 | 13/4 | 1 | 33/4 | 11/8 | 11/4 | 11/2 |



| GREEN ON WHITE; |
|----------------------------------------------|
| "KEEP NEW HAMPSHIRE" 1.375" |
| AVANT GARDE MD BT, GREEN; |
| "CLEAN AND SCENIC" 5.5" BRUSH SCRIPT, GREEN; |
| "SPONSOR" C, WHITE; |
| "A HIGHWAY" C, WHITE; |
| "NHDOT' C, WHITE; |

| NHDOT STANDARD PLANS | | | | | | | | |
|----------------------|------------------|---------|--|--|--|--|--|--|
| SPONSOR | \boldsymbol{A} | HIGHWAY | | | | | | |

| REV. | DATE | PLATE |
|------------|------|----------|
| 07-13-2001 | | 3 |
| 02-26-2010 | | STANDARD |
| | | SG-13 |

SIGNING STANDARD NHDOT STANDARD PLANS REV. DATE PLATE 4 STANDARD SG-13

STANDARD

NO. SG-13

REVISION DATE 07-13-2001

02-26-2010

*.DGN FILE NAME

SG-13

WHITE TEXT

GREEN TEXT

WHITE BACKGROUND

GREEN TEXT

WHITE BACKGROUND

REV. DATE

07-13-2001

02-26-2010

GREEN BACKGROUND

S

PLATE 2

STANDARD


SG-13



NO. SG-14

REVISION DATE 07-13-2001 02-26-2010

*.DGN FILE NAME SG-14



| | DI | MENS] | ONS | (inch | nes)/ | LETTE | ER FO | NTS |
|--------------------------|----|-------|-----|----------------|-------|-------|-------|-------|
| | Α | В | С | D * | E | F | G | Н |
| 10 CHARACTERS OR LESS | 48 | 39 | 3D | 4D | 8 | 1/2" | 7" | 71/2" |
| OVER 10 CHARACTERS | 60 | 51 | 3D | _ | 8 | 1/2" | 7 " | 71/2" |

IF THE TOWN OR CITY NAME IS SMALL,

0.75" RADIUS, 0.5" BORDER WHITE ON GREEN

<u>l-20</u>

| CENTER | IHE | LIEXI | UN | IHE . | 21GN• | | |
|----------|-----|--------|-----|--------|-------|-----|------|
| * IINDER | 8 | CHARAC | TFR | 3 1151 | F 1" | FNR | VFRT |

* UNDER 8 CHARACTERS USE 1" FOR VERTICAL SPACING BETWEEN CHARACTERS.

| NHDOT STANDARD PLANS | REV. DATE | PLATE |
|-------------------------|------------|---------|
| | 07-13-2001 | 1 |
| VERTICAL TOWN/CITY LINE | 07-13-2001 | STANDAR |
| | | SG-14 |

ENTERING

1.50" RADIUS, 0.75" BORDER, WHITE ON GREEN

INTERSTATE SIGN


<u>I-21</u>

| | DIMENSIONS (inches)/LETTER FONTS | | | | | | | | | | | | | | | | |
|----|----------------------------------|----|----|-------|-------|--------------------------------|---|------|---|------|---|---|-----|------|------|---|------|
| Α | В | С | D | Е | F | G | Н | I | J | К | L | М | N | 0 | Р | Q | R |
| 36 | 24 | 40 | 3D | 133/4 | 103/4 | 18 ³ / ₄ | * | 33/4 | 4 | 83/4 | * | 3 | 1/2 | 13/4 | 21/2 | 3 | 21/4 |

* VARIES DEPENDING ON TOWN NAME

NHDOT STANDARD PLANS HORIZONTAL TOWN/CITY LINE

| REV. | DATE | PLATE |
|------------|------|----------|
| 07-13-2001 | | 2 |
| 02-26-2010 | | STANDARD |
| | | SG-14 |



| | | DIMENSIONS (inches)/LETTER FONTS | | | | | | | | | | | |
|--------------------------|----|----------------------------------|----|----|---|---|------|------|------|---|-----|------|---|
| | Α | В | С | D* | E | F | G | Н | I | J | К | L | М |
| 10 CHARACTERS OR LESS | 48 | 42 | 3D | 4D | 6 | 4 | 31/2 | 33/4 | 11/2 | 1 | 7/8 | 11/4 | 2 |
| OVER 10 CHARACTERS | 60 | 54 | 3D | _ | 6 | 4 | 31/2 | 33/4 | 11/2 | 1 | 7/8 | 11/4 | 2 |

* UNDER 8 CHARACTERS USE 1" FOR VERTICAL SPACING BETWEEN CHARACTERS.

1.50" RADIUS, 0.50" BORDER. WHITE ON GREEN, GREEN ON WHITE

<u>l-22</u>

| NHDOT STANDARD PLANS | REV. DATE | PLATE |
|--------------------------------|------------|----------|
| | 07-13-2001 | 3 |
| VERTICAL TOWN/CITY/COUNTY LINE | 02-26-2010 | STANDARD |
| | | 7 SG-14 |

SIGNING STANDARD NHDOT STANDARD PLANS REV. DATE PLATE 4 STANDARD SG-14

S


STANDARD


REVISION DATE 07-13-2001


06-16-2010

*.DGN FILE NAME SL-1

NO. SL-1








CONCRETE PULL BOX 14" x 14"

ITEM 614.511

CONCRETE PULL BOX 18" x 18"

ITEM 614.512



| | A | В | С | D | E | F | G |
|-----------------|-------|-----|-----|-----|-----|-----|----------|
| ITEM NO 614.52 | 2 24" | 13" | 26" | 15" | 31" | 22" | 16"- 18" |
| ITEM NO 614.523 | 3 30" | 17" | 32" | 19" | 39" | 26" | 26" |

MOLDED PULL BOXES

(FOR USE IN OTHER THAN PAVED AREAS)


FINISHED GRADE

PLASTIC WARNING
TAPE

A 6" LAYER OF GRANULAR BEDDING
SHALL BE PROVIDED WHERE ROCK OR
UNSUITABLE MATERIAL IS ENCOUNTERED.

NOTE: BACKFILL ABOVE CONDUIT SHALL BE IN ACCORDANCE WITH 614.

TRENCH DETAIL FOR CONDUIT INSTALLATION



90° ELBOWS - NUMBER, SIZE & TYPE AS REQUIRED IN PLANS OR SPECIAL PROVISIONS. USE STEEL ELBOWS WITH GROUNDING BUSHINGS WHEN CONDUIT RUN EXCEEDS 200'.

<u>CONDUIT ARRANGEMENT</u> <u>ALL TYPES</u>

GENERAL NOTES

- 2. ADJUST FRAMES & COVERS SO THAT DRAINAGE WILL BE AWAY FROM PULL BOX.
- 3. LOGO = SIGNAL, ITS, DRAIN OR POWER AS REQUIRED, ON CENTER OF COVER.

SIGNAL & LIGHTING STANDARD

PULL BOXES & CONDUIT TRENCH DETAIL



REVISION DATE


07-13-2001


06-16-2010

*.DGN FILE NAME

SL-2


NO. SL-2






- 1. SIZE OF FOUNDATION MAY BE CHANGED IN THE PLANS OR SPECIAL PROVISIONS, OR IN THE FIELD AS DIRECTED BY THE ENGINEER.
- 2. ALL EXPOSED EDGES SHALL BE CHAMFERED 3/4".
- 3. OPEN ENDS OF ALL CONDUITS INTO FOUNDATION SHALL BE CAPPED UNTIL CABLES ARE INSTALLED.

CONCRETE FOUNDATION FOR PEDESTALS
(TRAFFIC OR PEDESTRIAN SIGNAL)






SECTION


GENERAL NOTES

- 1. ALL LIGHT POLES, LUMINAIRES, AND WIRE TO BE FURNISHED AND INSTALLED BY THE POWER COMPANY, UNLESS OTHERWISE DIRECTED.
- 2. ANCHOR BOLTS, GROUND ROD & GROUND WIRE TO BE FURNISHED BY THE POWER COMPANY AND INSTALLED BY THE CONTRACTOR, UNLESS OTHERWISE DIRECTED.
- 3. BOLT CIRCLE DIAMETER SHALL BE VERIFIED WITH THE POWER COMPANY.
- 4. ALL BASES SHALL BE LOCATED 10'-0" (TO CENTER) FROM FACE OF CURB OR EDGE OF PAVED SHOULDER, UNLESS OTHERWISE NOTED.
- 5. REINFORCEMENT SHALL CONFORM TO SECTION 544 OF THE STANDARD SPECIFICATIONS.
- 6. ANY ANCHOR BOLTS DAMAGED DURING INSTALLATION SHALL BE REPARIED OR REPLACED AS DIRECTED BY THE ENGINEER.
- 7. UPON INSTALLATION, ANCHOR BOLT THREADS SHALL BE CLEANED WITH A WIRE BRUSH.
- 8. TERRAIN SURROUNDING BASE MUST BE GRADED AS SHOWN IN DETAIL "A" TO PREVENT IMPACTING VEHICLES FROM SNAGGING ON BASE.



- 1. WORKMAN'S PAD MAY BE ELIMINATED IF CONTROLLER CABINET IS IN SIDEWALK SECTION.
- 2. ALL EXPOSED EDGES SHALL BE CHAMFERED 3/4".
- 3. WORKMAN'S PAD (AND CABINET DOOR) SHOULD BE ORIENTED TO PERMIT MAXIMUM VIEW OF SIGNAL INSTALLATION (AWAY FROM TRAFFIC, IF POSSIBLE).

CONCRETE FOUNDATION FOR CONTROLLER CABINET



DETAIL "A"

SIGNAL & LIGHTING STANDARD

CONCRETE FOUNDATIONS & LIGHT POLE BASE, TYPE B

Wew Humpshire
Department of Transportation

CONSTRUCTION

JOINT

9 #4A2 SPACED EVENLY (TOP)

9 #4A2 SPACED EVENLY (BOT)

END ELEVATION VIEW

CONSTRUCTION

7 #4A1 SPACED EVENLY (TOP)

7 #4A1 SPACED EVENLY (BOT)


ELEVATION VIEW

#4A2

135° BENDS

#4A1

CONCRETE FOUNDATION



STAINLESS STEEL WIRE CLOTH

SECTION A-A

Q ANCHOR ROD

SCREEN DETAIL

(VERTICAL)

(SEE NOTE NO. 6)

TRAFFIC SIGNAL STANDARD

Traffic Signal Mast Arm Foundation - Type 1A

STANDARD NO. TS-1

S

STANDARD

REVISION DATE

07-13-01

02-26-10


10-09-17

01-17-19


*.DGN FILE NAME

TS-1


NO. TS-1




TRAFFIC SIGNAL MAST ARM FOUNDATION - TYPE 1C



PLAN VIEW






END ELEVATION VIEW


NOTES

1. SEE MAST ARM FOUNDATION - TYPE 1A STANDARD PLAN TS-1, FOR TYPE 1 FOUNDATION NOTES.


| | TYPICAL QUANTITIES PER BASE | | | |
|------------------|-----------------------------|----------|--|--|
| I TEM NUMBER | ITEM | QUANTITY | | |
| 206.1* | COMMON STRUCTURE EXCAVATION | 24 CY | | |
| 209.1* | GRANULAR BACKFILL | 18.3 CY | | |
| 520.21* | CONCRETE CLASS B, FOOTINGS | 5.9 CY | | |
| 544 * | REINFORCING STEEL | 519 LB | | |

* ITEM NUMBERS ARE FOR SPECIFICATION REFERENCE ONLY.
NO SEPARATE PAYMENT WILL BE MADE FOR THESE ITEMS.





SECTION C-C



TRAFFIC SIGNAL STANDARD

Traffic Signal Mast Arm Foundations - Type 1B & 1C New Ham Department of Tr

S

STANDARD

REVISION DATE 07-13-01

02-26-10


10-09-17

01-17-19

*.DGN FILE NAME

TS-2


NO. TS-2



NO. TS-4

STANDARD NO. TS-4





** NOTE: SEE TRAFFIC SIGNAL MAST ARM LAYOUT STANDARD PLAN TS-7 FOR ATTACHMENT LAYOUTS. ATTACHMENT COMBINATIONS OTHER THAN THOSE SHOWN ON THE SPECIAL DETAIL SHALL NOT BE USED WITHOUT DESIGN APPROVAL FROM EITHER THE BUREAU OF BRIDGE DESIGN OR THE BUREAU OF TRAFFIC.

| | TYPICAL QUANTITIES I | GTH | | | | | |
|----------------------------|----------------------------------------------|------|------------------|-----|-----------------|-----|-----------------|
| I TEM NUMBER | ITEM | UNIT | QUANT I 8'-0" | | SHAFT 10'-0" | | (MIN) 12'-0" |
| ▲ 508* | STRUCTURAL FILL | СҮ | 20 | 22 | 24 | 26 | 28 |
| 520.1* OR ▲ 520.001* | CONCRETE CLASS A OR CONCRETE CLASS AAA | СҮ | 2.1 | 2.4 | 2.6 | 2.9 | 3.1 |
| 544 * | REINFORCING STEEL | LB | 342 | 384 | 455 | 556 | 608 |

REINFORCING SCHEDULE

* ITEM NUMBERS ARE FOR SPECIFICATION REFERENCE ONLY. NO SEPARATE PAYMENT WILL BE MADE FOR THESE ITEMS.

10'-0"

11'-0"

▲ DENOTES EXCAVATED HOLE METHOD OF CONSTRUCTION FOR CIRCULAR SHAFTS

| | | | | | | _ |
|-----------------|------|------|-------|--------------|------------------|--------------|
| SHAFT LENGTH | MARK | TYPE | BAR # | # OF BARS | UNBENT LENGTH | |
| 8′-0″ | F 1 | | #7 | 16 | 7′-6″ | |
| 8 -0 | F2 | G | #5 | 10 @ 10" | 9′-3″ | |
| 9′-0″ | F1 | | #7 | 16 | 8′-6″ | |
| 9 -0 | F2 | Q | #5 | 11 @ 10" | 9′-3″ | STAN 135° |
| | | | | | | 133 |

| MARK | TYPE | BAR # | BARS | LENGTH | . 2′-6″. |
|------|------|-------|----------|--------|-----------------------------|
| F 1 | | #7 | 16 | 7′-6″ | |
| F2 | G | #5 | 10 @ 10" | 9′-3″ | ("4") |
| F 1 | | #7 | 16 | 8′-6″ | |
| F2 | G | #5 | 11 @ 10" | 9′-3″ | STANDARD #5F2 135° BENDS |
| F 1 | | #7 | 16 | 9′-6″ | 133 DENUS |
| F2 | G | #5 | 15 @ 8" | 9′-3″ | |
| F 1 | | #7 | 16 | 10′-6″ | |
| F2 | G | #5 | 22 @ 6" | 9′-3″ | |
| F 1 | | #7 | 16 | 11′-6″ | |
| F2 | Q | #5 | 24 @ 6" | 9′-3″ | |

* ANCHOR RODS SHALL BE STRAIGHT RODS AND CONFORM TO ASTM F1554 GRADE 50 (MIN.). GALVANIZE THE ENITRE ROD PER ASTM A153. EACH ANCHOR ROD SHALL BE SUPPLIED WITH A MINIMUM OF THREE HEX NUTS (ASTM A563 OR ASTM A194) AND A MINIMUM OF TWO FLAT HARDENED WASHERS (ASTM F436). LOCK WASHERS SHALL NOT BE USED. THE EMBEDDED END OF THE ANCHOR ROD SHALL HAVE EITHER ONE NUT TACKED WELDED OR DOUBLE NUTS. BENT (HOOKED OR J-BOLT) ANCHOR RODS SHALL NOT BE USED.

SHAFT DIAMETER C ANCHOR ROD

* ANCHOR RODS SHALL BE


1" CHAMFER

SET ACCORDING TO

MANUFACTURER'S RECOMMENDATION

FINISHED GRADE

(SEE GENERAL NOTE 3)



 $3'' \phi$ STREET LIGHT

CONDUIT (IF REQUIRED)

SECTION F-F

 $3'' \phi CONDUIT$

1" PROJECTION

#7F1 (PLACE AS SHOWN IN SECT. F-F)

CONDUIT TO

3'-0" SUBSID.

GENERAL NOTES (TYPE 2 FOUNDATION)

- 1. THERE SHALL BE A MINIMUM OF ONE TEST BORING REQUIRED, AT THE APPROXIMATE FOUNDATION LOCATION, TO CONFIRM THE ENGINEERING PROPERTIES OF THE SOILS PROVIDING FOUNDATION SUPPORT. THE ENGINEER MAY REQUIRE ADDITIONAL BORINGS IF CONSIDERED NECESSARY.
- 2. THE CIRCULAR SHAFT FOUNDATION SHALL BE CONSTRUCTED IN EITHER A DRILLED HOLE OR IN AN EXCAVATED HOLE PER THE NOTES PROVIDED BELOW FOR EACH METHOD, CAST IN PLACE CONCRETE SHALL BE AN OPTION FOR EITHER EXCAVATION METHOD. PRECAST CONCRETE SHALL ONLY BE USED WITH THE EXCAVATED HOLE METHOD.
- 3. THE EVALUATION OF GEOTECHNICAL LATERAL CAPACITY IS BASED ON A SOIL MODEL COMPRISED OF HOMOGENEOUS GRANULAR (COHESIONLESS) SOILS HAVING A FRICTION ANGLE OF 32 DEGRESS, MAXIMUM GROUND SURFACE STEEPNESS OF 4H:1V, AND NEAR SURFACE GROUNDWATER TABLE. IF THE SOIL PROVIDING FOUNDATION SUPPORT CANNOT GENERATE AN EQUIVALENT OR GREATER LATERAL CAPACITY, AS COMPARED TO THIS SOIL MODEL, THEN THE ENGINEER WILL REVIEW THE FOUNDATION CONDITIONS WITH THE GEOTECHNICAL SECTION AND EVALUATE WHETHER A REDESIGN IS REQUIRED.
- 4. TRENCHES FOR THE CONDUITS SHALL BE HAND DUG NEAR THE PROPOSED FOUNDATION, DISTURBING AS LITTLE SOIL AS POSSIBLE IN PLACING OF THE CONDUITS (APPROXIMATELY 2.5 FT MAXIMUM DOWN FROM THE EXISTING GROUND SURFACE). THE RESULTING TRENCHES SHALL BE BACKFILLED WITH STRUCTURAL FILL CONFORMING TO SECTION 508.
- 5. WHERE BEDROCK IS ENCOUNTERED, A REDUCTION IN CIRCULAR SHAFT LENGTH MAY BE POSSIBLE FOR THE DRILLED HOLE METHOD ONLY, AS DESCRIBED IN THE DRILLED HOLE NOTES.
- 6. CAST IN PLACE CONCRETE SHALL BE CLASS A HAVING A MINIMUM 28 DAY COMPRESSIVE STRENGTH OF 3000 PSI AND BE PLACED IN CONFORMANCE WITH SECTION 520, CYLINDERS FOR STRENGTH TESTING SHALL BE TAKEN DURING CONCRETE PLACEMENT.
- 7. CONCRETE FOR A PRECAST CIRCULAR SHAFT FOUNDATION SHALL BE CLASS AAA WITH A MINIMUM 28 DAY COMPRESSIVE STRENGTH OF 5000 PSI CONSTRUCTED IN CONFORMANCE WITH SECTION 520. INSPECTION BY A DEPARTMENT REPRESENTATIVE DURING THE PRECASTING AT THE PLANT IS REQUIRED. CONTACT THE BUREAU OF MATERIALS AND RESEARCH AT 271-1656 TO ARRANGE FOR PLANT INSPECTION AT LEAST 14 DAYS PRIOR TO CASTING.
- 8. STAINLESS STEEL STD. GR. WIRE CLOTH. 1/4" MAX. OPENING WITH MIN. WIRE DIA. OF AWG NO. 16 WITH 2" LAP. SECURE WITH 3/4" STAINLESS STEEL BANDING AFTER ANCHOR RODS ARE FULLY TIGHTENED.
- 9. NO GROUT SHALL BE PLACED BETWEEN THE FOUNDATION AND BOTTOM OF THE BASE PLATE.
- 10. THE EXPOSED LENGTH OF THE ANCHOR ROD BETWEEN THE TOP OF THE FOUNDATION AND THE BOTTOM OF THE LEVELING NUT SHOULD NOT EXCEED ONE ROD DIAMETER (MAXIMUM) OR 1-INCH (PREFERRED).
- 11. FOR THE INSTALLATION, PRETENSIONING AND ULTRASONIC TESTING OF ANCHOR RODS, SEE THE SPECIAL PROVISION AMENDMENT TO SECTION 616, TRAFFIC SIGNALS.
- 12. ALL REINFORCING STEEL SHALL CONFORM TO AASHTO M31/M31M, GRADE 60 (420). ALL REINFORCING STEEL SHALL BE A MINIMUM OF 3 INCHES FROM CONCRETE SURFACES, UNLESS NOTED OTHERWISE, AND MEET THE REQUIREMENTS OF SECTION
- 13. TYPE 2 FOUNDATIONS SHALL BE PAID FOR UNDER ITEM 616.1XX.

DRILLED HOLES

- 1. THE CIRCULAR SHAFT FOUNDATION SHALL BE CONSTRUCTED OF CAST IN PLACE CONCRETE AGAINST UNDISTURBED MATERIAL USING TEMPORARY CASING IF NECESSARY, THE CONCRETE MIX SHALL BE CAPABLE OF FLOWING THROUGH THE REINFORCING CAGE TO THE EXCAVATION SIDES WITH MINIMAL USE OF VIBRATION EQUIPMENT WHETHER THE METHOD OF PLACEMENT IS FREEFALL OR UNDERWATER. THE CONTRACTOR SHALL COORDINATE WITH THE ENGINEER FOR VISUAL INSPECTION OF THE EXCAVATION, THE ARRANGEMENT OF THE REINFORCING BARS, AND THE ANCHOR BOLTS PRIOR TO CONCRETE PLACEMENT.
- 2. THE EXPOSED PORTION OF THE SHAFT AND TO A DEPTH OF AT LEAST 12 INCHES SHALL HAVE A FORMED APPEARANCE WITH THE TOP HAVING A SMOOTH LEVEL FINISH.
- 3. UNDERWATER PLACEMENT PROCEDURES (TREMIE OR PUMPING METHODS) SHALL BE REQUIRED WITHIN A DRILLED HOLE WHERE THE STANDARDS FOR A DRY EXCAVATION AND FREE FALL PLACEMENT METHOD CANNOT BE MET. THE WATER LEVEL WITHIN A DRILLED HOLE SHALL BE AT A STABILIZED, STATIC LEVEL AT THE TIME OF CONCRETE PLACEMENT.
- 4. WHERE BEDROCK IS ENCOUNTERED, THE DRILL SHALL PENETRATE THE BEDROCK A MINIMUM OF 3 FEET AND IN ALL CASES A MINIMUM SHAFT LENGTH OF 5 FEET SHALL BE OBTAINED, IT IS NOT NECESSARY TO EXTEND THE SHAFT IN BEDROCK BEYOND THE SPECIFIED SOIL-BASED LENGTH GIVEN ON THE PLANS.
- 5. WHERE FILL EMBANKMENT IS TO BE CONSTRUCTED ABOVE THE EXISTING GROUND, THE EMBANKMENT SHALL BE BUILT PRIOR TO CONSTRUCTING THE SHAFT. PLACEMENT AND COMPACTION OF THE FILL SHALL BE IN ACCORDANCE WITH SECTION 203.
- 6. IF THE DRILLED HOLE METHOD IS PERFORMED AND THE SOILS ARE FOUND TO BE UNSUITABLE, AN EXCAVATED HOLE SHALL BE COMPLETED AS APPROVED BY THE ENGINEER.

EXCAVATED HOLES

- ▲ 1. AS AN ALTERNATIVE TO A DRILLED HOLE, THE CIRCULAR SHAFT FOUNDATION CONCRETE SHALL BE CONSTRUCTED IN AN EXCAVATED HOLE, THE FOUNDATION SHALL BE CAST IN PLACE USING FORMS (WHICH MUST BE REMOVED) OR ALTERNATIVELY A PRECAST CIRCULAR SHAFT FOUNDATION SHALL BE INSTALLED.
- 2. THE EXCAVATED HOLE SHALL BE AT LEAST 3 FT CLEAR OF THE FOUNDATION SIDES AND 1 FT DEEPER THAN THE FOUNDATION
- 3. ANY BEDROCK ENCOUNTERED SHALL BE REMOVED TO THE SAME LIMITS AS DESCRIBED FOR SOIL (SEE PREVIOUS NOTE). IF THIS IS NOT POSSIBLE THEN THE ENGINEER SHALL REQUEST A REDESIGN.
- 4. THE EXCAVATED HOLE SHALL BE BACKFILLED TO THE LIMITS OF EXCAVATION WITH STRUCTURAL FILL ACCORDING TO SECTION 508. NO PAYMENT SHALL BE MADE FOR STRUCTURAL FILL OR EXCAVATION.

TRAFFIC SIGNAL STANDARD


Traffic Signal Mast Arm

Foundation - Type 2

NO. TS-5

TOP OF BINDER COURSE 6" DESIREABLE 12" MAX. GRANITE 15" ± GRANULAR CURB BACKFILL (SAND) 3/4" PVC CONDUIT TO PULL BOX GRANULAR BACKFILL (SAND) SHALL CONFORM TO ITEM 209.3 (SUBSIDIARY) 15" ± BOLDLY ETCH TWO ARROWS ON TOP OF -CURB TO SHOW APPROXIMATE BOUNDARY OF THE BOX OUT <u>PLAN</u>

DETECTOR BOX OUT DETAIL STAGE 1: AT PAVING NOT TO SCALE



DETECTOR BOX OUT DETAIL STAGE 2: AT LOOP INSTALLATION NOT TO SCALE

GENERAL NOTES

1. MAXIMUM OF TWO LEAD-IN PAIRS PER 3/4" CONDUIT.

GRANITE CURB —

SECTION A-A

3/4" PVC CONDUIT


FROM BOX OUT TO

PULL BOX


(SUBSIDIARY)

- 2. TAPE TUBING 3" ON EACH SIDE OF THE SAW CUT BOX OUT BOUNDARY WITH ELECTRICAL TAPE.
- 3. AFTER TUBING IS INSTALLED, FILL CONDUIT WITH CRUMPLED PAPER AND SEAL WITH PLIABLE DUCT SEALANT.
- 4. USE ITEM 209.3 GRANULAR BACKFILL (SAND) (SUBSIDIARY) TO COVER AND SUPPORT THE VINYL PLASTIC TUBING.

TRAFFIC -BOX OUT NOTE: LOOP DIMENSIONS AS SHOWN ON SIGNALIZATION PLAN — CURB -3/4" PVC CONDUIT -PULL BOX TYPICAL WIRE LOOP DIAGRAM NOT TO SCALE LOOP LENGTH VARIES, SEE SIGNALIZATION PLAN (TYPICAL 20 TO 50 FEET) 45°



NOT TO SCALE



LOOP DETECTOR SEGMENT DETAIL NOT TO SCALE

TRAFFIC SIGNAL STANDARD

QUADRUPOLE LOOP DETECTOR 2-4-2 TURNS




NO. TS-6


REVISION DATE 07-13-01

02-26-10


01-17-19

*.DGN FILE NAME TS-6





RECTANGULAR LOOP INSTALLATION SAW CUT DETAIL NOT TO SCALE




SECTION C-C LEAD-IN SAW CUT FROM SEGMENT TO BOX OUT


SECTION D-D SEGMENT SECTION

LOOP DETECTOR SEGMENT DETAIL NOT TO SCALE

SAW CUT



DETECTOR BOX OUT DETAIL STAGE 1: AT PAVING NOT TO SCALE



DETECTOR BOX OUT DETAIL STAGE 2: AT LOOP INSTALLATION NOT TO SCALE

GENERAL NOTES


- 1. MAXIMUM OF TWO LEAD-IN PAIRS PER 3/4" CONDUIT.
- 2. TAPE TUBING 3" ON EACH SIDE OF THE SAW CUT BOX OUT BOUNDARY WITH ELECTRICAL TAPE.
- 3. AFTER TUBING IS INSTALLED, FILL CONDUIT WITH CRUMPLED PAPER AND SEAL WITH PLIABLE DUCT SEALANT.
- 4. USE ITEM 209.3 GRANULAR BACKFILL (SAND) (SUBSIDIARY) TO COVER AND SUPPORT THE VINYL PLASTIC TUBING.

TRAFFIC SIGNAL STANDARD

RECTANGULAR LOOP DETECTOR 3 TURNS



S



| ITEM NO. | DESCRIPTION | WEIGHT (LBS.) | AREA (SQ. FT.) | SURFACE AREA |
|-------------|-----------------------------------|------------------|-------------------|--------------|
| 1 | 4-SECTION HEAD | 90 | 11.0 | 40.0 |
| 2 | 250 WATT LIMINAIRE | 30 | 3.3 | 3.5 |
| 3 | STROBE | 5 | 1.0 | N/A |
| 4 | SIGN | 3.0 LB/SF | 5.0 | N/A |
| (5) | PREEMPTION RECEIVER | 5 | 1.0 | N/A |
| 6 | SIGN | AS | SHOWN | VARIES |
| 7 | PEDESTRIAN SIGNAL | 80 | 8.0 | N/A |
| 8 | VIDEO DETECTION | 40 | 3.0 | VARIES |
| 9 | MITIGATION DEVICE 60"×16"×1/8" | 3.5 LB/SF | | |

FOUNDATION



NO. TS-7 30 29 26 24 23 21 19 14 **REVISION DATE** 35 34 31 29 27 25 23 14 01-17-19 *.DGN FILE NAME TS-7 NH-30 OR NH-30L NH-35 OR NH-35L L = MAST ARM WITH LUMINAIRE 40'-0" OR 45'-0" 32 30 27.5 16.5 37 36 34.5 29 23.5 12.5 STREET SIGN 96"X36" NH-40 OR NH-40L NH-45 OR NH-45L L = MAST ARM WITH LUMINAIRE 50'-0" OR 55'-0" 16.5 14 27.5 23.5 21 34.5 12.5 STREET SIGN 96"x36" NH-50 OR NH-50L NH-55 OR NH-55L L = MAST ARM WITH LUMINAIRE

30'-0" OR 35'-0"

STREET SIGN 60"X36"

40 39 36

45 44 41

40.5

46 43 | 38.5

55 54 51 48 45.5

GENERAL NOTES

NH-20

NH-20L

NH-25

NH-25L

NH-30

NH-30L

NH-35

NH-35L

NH-40

NH-40L

NH-45

NH-45L

NH-50

NH-50L

NH-55

NH-55L

NH-60

NH-60L

20

20

25

25

30

30

35

35

40

40

45

50

50

55

55

60

60

1 A

1 A

1 A

1 A

1B

1 C

1 B

1 C

1B

1 C

1 D

1 D

1 E

1 E

NOTES FOR TRAFFIC SIGNAL POLES, MAST ARMS AND PEDESTALS

1. TRAFFIC SIGNAL STRUCTURES SHALL BE DESIGNED IN ACCORDANCE WITH THE CURRENT EDITION OF THE AASHTO" STANDARD SPECIFICATIONS FOR STRUCTURAL SUPPORTS FOR HIGHWAY SIGNS. LUMINAIRES AND TRAFFIC SIGNALS "INCLUDING ALL INTERIMS EXCEPT AS MODIFIED HEREIN. TRAFFIC SIGNAL STRUCTURES SHALL BE DESIGNED TO SUPPORT FIXED SIGNALS, VIDEO DETECTION EQUIPMENT, EMERGENCY PREEMPTION EQUIPMENT AND LUMINAIRES AS SHOWN ON THE PLANS. MINIMUM CLEARANCE TO THE BOTTOM OF THE OVERHEAD SIGNAL HOUSING SHALL BE 16.0 FT. TRAFFIC SIGNAL STRUCTURES SHALL BE DESIGNED BASED ON THE SPECIAL PROVISION FOR SECTION 616.

8'- 0"

9'-0"

9'-0"

10'-0"

10'-0"

10'-0"

10'-0"

10'- 0"

10'- 0"

11'- 0"

11'- 0"

11'- 0"

11'- 0"

11'- 0"


11'- 0"

12'- 0"

12'- 0"

12'- 0"

- 2. STEEL STRUCTURES, UNLESS OTHERWISE INDICATED, SHALL BE HOT DIP GALVANIZED IN ACCORDANCE WITH ASTM A 123.
- 3. CONCRETE FOUNDATIONS SHALL BE CONCRETE CLASS AAA OR B, AS INDICATED ON THE FOUNDATION PLANS MEETING THE REQUIREMENTS OF 520. REINFORCING STEEL SHALL MEET THE REQUIREMENTS OF 544. THE FOUNDATIONS SHALL BE AS SHOWN ON THE PLAN.
- 4. ANCHOR BOLTS SHALL CONFORM TO ASTM F1554, GRADE 55, HAVING MINIMUM YIELD STRENGTH OF 55 KSI WITH THREADED END AND HEX NUTS (2 PER BOLT), FULLY GALVANIZED IN ACCORDANCE WITH ASTM A 153. ANCHOR BOLTS SHALL BE SET ACCORDING TO MANUFACTURER'S RECOMMENDATIONS.
- 5. MAST ARM SIGNS SHALL BE INSTALLED ON THE MAST ARM ONE HALF THE SIGN WIDTH DISTANCE PLUS TWO FEET.
- 6. A MITIGATION DEVICE SHALL BE INSTALLED ON ALL MAST ARM LENGTHS GREATER THAN 50 FEET.
- 7. LAYOUTS SHOWN ARE FOR THE DESIGN OF TRAFFIC SIGNAL STRUCTURES. IF ACTUAL LOADING IS EQUAL TO OR LESS THAN THE LAYOUTS SHOWN, A STANDARD FOUNDATION MAY BE USED. IF LOADING EXCEEDS THE STANDARD DESIGNS SHOWN, A CUSTOM FOUNDATION WILL NEED TO BE DESIGNED AND APPROVED.
- 8. SEE STANDARD PLANS TS-1, TS-2, TS-3 AND TS-4 FOR STANDARD FOUNDATION PLANS.



SEE DETAIL B

TRAFFIC SIGNAL STANDARD

TRAFFIC SIGNAL MAST ARMS

STANDARD NO. TS-7

STANDARD

NOTE: Revised Standards TC-1 through TC-8 amend Part VI of the 2009 Edition of the MUTCD by superseding or supplementing certain Sections. They shall be used in conjunction with the MUTCD and the Specifications for work zone traffic control on all projects.

- 1. Section 6C.04, Table 6C-1 and Section 6H-01, Table 6H-3. "Urban (low speed)" shall be defined as those roadways with regulatory speed limits of 30 mph or less; "Urban (high speed)" shall be defined as those roadways with regulatory speed limits
- 2. Section 6F.03, Sign Placement. Add the following paragraph as a "Standard" heading:
 - O1a Actual placement of temporary traffic control signs shall be carefully considered to avoid obstructing existing signs or allowing existing signs, vegetation or other physical features to obstruct or limit visibility to temporary traffic control signs.

 Temporary traffic control signs shall also be placed at locations that avoid overwhelming motorists with information when combined with existing signs.
- 3. Section 6F.17 Positioning of Advanced Warning Signs. Add the following sentence as "Guidance" and "Option", respectively after sentence 07:

Guidance:

- When multiple operations are occurring in the same area, duplication of the advance warning signs, e.g. ROAD WORK AHEAD, ROAD WORK ½ MILE, etc., should be avoided.

 Option:
- In cases where room for advance warning signage is severely limited, some of the general advanced warning signs (e.g. ROAD WORK AHEAD) may be eliminated in order to provide adequate space for driver to see and comprehend the warning signs requiring driver action, e.g. LANE ENDS MERGE LEFT, FLAGGER AHEAD, etc.
- 4. Section 6F.64, Cones. Add the following to the "Standard":
 - 01a Cones shall not be used at night as the primary channelization device, except during work hours.
- 5. Section 6F.65, Tubular Markers. Replace paragraphs 01 and 02 of the "Standard" section with the following:
 - Tubular markers shall be predominately orange and shall not be less than 42 inches high and 3 inches wide when facing road users. They shall be made of material that can be struck without causing damage to the impacting vehicle. Refer to MUTCD 6F-65 Paragrah 3 for delineation color and type.
- 6. Section 6F.67, Drums. Add the following sentences after Sentence number 01:

Standard:

01a Drums shall be the primary delineation device on divided highways for all tapers and tangents.

Option:

- O1b Cones or tubular markers may be used, only in the tangent sections of the lane closure, when inadequate width, geometric constraints or the duration of the operation (short-duration or mobile, see 6G.02 for Work Duration definitions) necessitates the use of a narrower or more easily moved channelizing device.
- 7. Section 6F.78 Temporary Markings. Add to the "Standard" the follow sentences:
 - 05a All temporary markings on divided highways shall be 4-inch removable tape or paint conforming to MUTCD Chapter 3, Section 3A.
 - 05b All temporary markings shall be offset 1-foot from the final striping location.
 - 05c All temporary white broken-line pavement markings for traffic moving in the same direction shall be retroreflectorized paint or tape. Temporary paint or tape markings shall have a cycle length of 40 feet long with minimum 4-foot long skip and 36-foot long gap. Temporary tape shall be removed prior to any overlays and after permanent pavement markings have been applied.
 - 05d Stop lines shall be installed during temporary conditions and shall be retroreflectorized paint or tape.

Replace "Guidance" paragraph 03 with:

- Edge lines, channelizing lines, lane reduction transitions, gore markings, and non-longitudinal lines (e.g., railroad crossings, crosswalks, words, symbols, etc.) are usually not required for temporary situations. Their use should be evaluated on a project by project basis based on field conditions, relative traffic speeds and volumes, and the use of other traffic control devices. When used, temporary markings for these types of longitudinal and non-longitudinal lines shall be retroreflectorized paint or tape and conform to MUTCD Part 3 Chapters 3A and 3B.
- 8. Section 6F.85 Temporary Traffic Barriers. Add the following to the "Standard" paragraph 06:
 - Temporary end treatments in the form of sand barrels and water filled arrays shall not be used from November 1st through April 15th unless they are greater than ten feet from the travelway (measured to the face) or specifically approved in writing by the Engineer. If approved by the Engineer for winter use, the sand or water shall be treated in accordance with the manufacturer's recommendations to prevent freezing.
 - 06b Impact attenuators shall be marked with a Type 3 Object Marker per Section 2C.63 Object Marker Design and Placement Height paragraph 02.
- 9 Section 6G.05 Work Affecting Pedestrian and Bicycle Facilities. Add the following to the "Support" paragraph 01:
 - 01a R4-11 (Bike May Use Full Lane) sign should be used when the clear width of a single lane and shoulder is less than 14', except when the existing lane and shoulder in the general vicinity of the work provides less than 14' clear. This sign is optional where operational controls are used, and during mobile, short duration, and short term stationary work durations as defined by Section 6G.02. This sign shall not be used when the speed limit is over 40 mph.
- 10 Section 6H.01, Typical Applications. Add the following paragraph to the Option heading:
 - Many diagrams show ROAD WORK (W20-1), ROAD WORK NEXT XX MILES (G20-1), and END ROAD WORK (G20-2a) signs being used for the activities. These signs may be omitted if the activity is being performed within the limits of a larger project and the Advance Warning and/or Termination Signs for the larger project provide reasonable warning to the motorist for the activity.
- Section 6H.01, Figure 6H-14. The diagram for the unsignalized crossing of a Haul Road shows interim tape and a NO PASSING ZONE (W-14-3) sign to deter passing maneuvers. In lieu of interim tape, cones may be placed along the centerline, using a maximum spacing of 40-feet.
 - In both diagrams, add a TRUCK CROSSING (W8-6) sign at a distance "B" in advance of the DO NOT PASS (R4-1) sign. Show the ROAD WORK AHEAD (W20-1a) sign at a distance "C" in advance of the TRUCK CROSSING sign. (See Table 6H-3 for distance
- 12 Section 6H.01, Figure 6H-36. Make the following revisions:
 - a. Use REVERSE CURVE (W1-4 series) signs which show side-by-side arrows, one arrow for each open lane, at each location that the sign is shown.

NO. TC-1

STANDARD

08/03/2004 03/16/2017 11/28/2018 05/17/2019 04/20/2022

*.DGN FILE NAME TC-1

STANDARD PLANS

New Hampshive

Department of Transportation

WORK ZONE TRAFFIC CONTROL

AMENDMENTS TO PART VI MUTCD (2009)

STANDARD NO. TC-1 Examples of traffic control operations where Uniformed Officers and flaggers are typically not needed:

- 1. Shoulder work.
- 2. Work behind barrier.

Examples of traffic control operations where flaggers should be used include:

- Alternating 1-way traffic (stop/slow paddles must be used).
- 2. Directing traffic through low volume intersections.
- 3. Assisting trucks and equipment in and out of work areas.
- 4. Providing coverage at side roads and driveways during mobile operations (e.g. paving, striping, etc.).
- 5. Directing pedestrians and bicyclists through the work zone.

Examples of traffic control operations where Uniformed Officers may be used include:

- 1. Directing traffic through complex intersections, especially where signals are being overridden.
- 2. Assisting construction vehicles and equipment in and out of work areas on high speed(> 45 mph), high volume facilities(> 15000 vpd). Note: If an access area is anticipated to be in place for an extended period of time and it is determined that assistance is required for the safe exit and entry of construction vehicles, then a cost analysis should be completed to determine if stationary measures (e.g. signals) would be more cost effective than officers or flaggers.
- 3. Rolling roadblock operations on interstate and turnpike facilities and other multi-lane L.A.R.O.W. highways.
- 4. If a uniformed officer is already on site for other needs (enforcement or presence), then the officer may be asked to supplement these duties by providing limited duration traffic control that would otherwise be covered by a flagger. However, the officer must be adequately trained for the flagger operation to be performed and must use appropriate equipment and techniques (which may include the use of stop/slow paddles).
- 5. If approved, officers may be hired as a speed deterrent and/or to increase driver awareness through a work zone under the following conditions:
 - a. The work zone has a posted speed of 45 mph or higher and an average daily traffic (ADT) volume of 15,000 vpd or greater; and
 - b. The work zone presents a unique safety issue, such as a high rate of crashes, vehicles traveling at excessive speeds, poor highway geometrics, excessive East-West sun glare; workers exposed to traffic; and/or construction equipment frequently entering and exiting the work zone.
- 6. In rare cases, a presence officer may be approved for use on low speed (< 45 mph) or low volume (< 15,000 vpd) roads if a unique safety issue exists and other speed deterrent or driver awareness measures are proven ineffective.
- 7. The use of law enforcement may be considered for nighttime operations. When used at night the use of the blue lights and positioning should be carefully considered. Excessive use of police vehicles with lights at night, or inappropriate positioning of these vehicles may actually detract from the positive guidance the work zone traffic control devices provide. When used for nighttime work, blue lights should be dimmed and headlights should be off.

See complete Flagger and Uniformed Officer guidelines at this link:

http://www.nh.gov/dot/org/projectdevelopment/construction/documents/FlaggerPoliceUseGuidelines.pdf

UNIFORMED OFFICER PLACEMENT IN THE WORK ZONE

If Uniformed Officer with Vehicle use has been approved for presence, cruiser placement is recommended as follows:

- 1. Park in the shoulder or median, not in the travel lane.
- 2. Do not park behind the Truck Mounted Attenuator (TMA).
- 3. Do not park in the buffer zone. If buffer zone presence is needed, then consideration should be given to installing a truck TMA instead.
- 4. Do not park in the taper.
- 5. Locate the police cruiser between the 1st and 2nd signs (from the taper).
 - a. Urban (Low </= 30 mph) 150' from the taper.
 - b. Urban (High >/= 35 mph) 525' from the taper.
 - c. Rural = 750' from the taper.
 - d. Expressway/Freeway = 1750' from the taper.
- 6. Consider having the cruiser face traffic for stationary operations.
 - a. Recommended cruiser positioning for moving operations:
 - I. Less than 5 mph face traffic (e.g. crack seal).
 - II. Greater than 5 mph face work (e.g. striping, rumble strips).
- 7. Stay ¼ mile in front of queue.
- 8. If a second Officer is used for enforcement, and there is no queue, the enforcement officer should be immediately after the work zone. If there is a traffic queue then the enforcement officer should be several miles before the backup queue and presence Officer.
- 9. Hands free and cell phone use should be only for work zone activity.
- 10. Headlights off, dim blue lights at night if possible.

WORK ZONE TRAFFIC CONTROL

UNIFORMED OFFICERS
AND FLAGGERS

*.DGN FILE NAME TC-2


STANDARD

NO. TC-2


REVISION DATE

03/16/2017

STANDARD PLANS



STANDARD NO. TC-2



TYPICAL APPLICATION

| RECOMMENDED ADVANCE WARNING SIGN MINIMUM SPACING TABLE 6-1C FROM MUTCD (2009 EDITION) | | | | | | |
|---------------------------------------------------------------------------------------|------------------------|-------|-------|--|--|--|
| ROAD TYPE | DISTANCE BETWEEN SIGNS | | | | | |
| ROAD TIPE | А | В | С | | | |
| URBAN (≤ 30 MPH) | 100′ | 100′ | 100′ | | | |
| URBAN (≥35 MPH) | 350′ | 350′ | 350′ | | | |
| RURAL | 500′ | 500′ | 500′ | | | |
| EXPRESSWAY / FREEWAY | 1000′ | 1500′ | 2640′ | | | |


TWO WAY TRAFFIC LANE SHIFT

REVISION DATE 08/03/2004 03/16/2017 11/28/2018 05/17/2019 04/20/2022

STANDARD

NO. TC-4

*.DGN FILE NAME



W1-4R

NOT TO SCALE

GENERAL NOTES

W20-1a ★

- ★ SEE AMENDMENT NO. 10 ON TC-1.
- 1. FOR OPERATIONS WHERE TWO-WAY TRAFFIC LANE SHIFT CAN BE MAINTAINED ON TWO 10' MIN. CLEAR WIDTH LANES.
- 2. FOR LONG-TERM STATIONARY OR INTERMEDIATE-TERM STATIONARY WORK, PAVEMENT MARKINGS INDICATING NO PASSING SHALL BE USED. DO NOT PASS SIGNS (R4-1) MAY BE REQUIRED.
- 3. FOR TAPER LENGTH (L) CRITERIA, SEE MUTCD TABLES 6C-3 AND 6C-4.
- 4. FOR SPEEDS > 50 MPH, LENGTH = L. FOR SPEEDS ≤ 50 MPH LENGTH = 1/2L.
- 5. FOR BUFFER SPACE CRITERIA, SEE STOPPING SIGHT DISTANCE, MUTCD TABLE 6C-2.

R4-11

(SEE NOTE 6)

- 6. INSTALL ON ALL APPROACHES IF THE CRITERIA IN AMENDMENT NO. 9 ON TC-1 APPLIES.
- 7. THE SPACE BETWEEN THE TRUCK MOUNTED ATTENUATOR (TMA) AND THE WORK SPACE SHALL BE PER MANUFACTURER'S RECOMMENDATIONS.

<u>LEGEND</u> CHANNELIZING DEVICES

TMA (OPTIONAL)

WORK ZONE TRAFFIC CONTROL


G20-2a ★

(IF REQUIRED)

TWO WAY TRAFFIC LANE SHIFT



STANDARD NO. TC-4





ROAD WORK

(IF REQUIRED)

G20-2a ★

TYPICAL APPLICATION LANE CLOSURE: TWO-LANE ROAD WITH LOW TRAFFIC VOLUMES





W5-3a (IF REQUIRED)

GENERAL NOTES

- ★ SEE AMENDMENT NO. 10 ON TC-1
- ** POSTED BRIDGE WIDTH SHALL BE 1 FOOT LESS THAN ACTUAL WIDTH.
- 1. THIS TYPICAL APPLICATION SHOULD BE USED AS AN ALTERNATE TO MUTCD FIGURE TA-11 WHEN CONSTRUCTION ACTIVITIES ARE FOR A PERIOD LONGER THAN THAT CONSIDERED INTERMEDIATE-TERM WORK (SEE MUTCD SECTION 6G.02).
- 2. EXISTING PAVEMENT MARKINGS SHALL BE REMOVED AND TEMPORARY MARKINGS INSTALLED AS ORDERED.
- 3. REGULATORY SIGN PLACEMENT SHALL BE APPROVED BY BUREAU OF TRAFFIC.
- 4. HAZARD IDENTIFICATION BEACONS OR TYPE A FLASHING WARNING LIGHTS MAY BE MOUNTED WITH WARNING SIGNS, IF WARRANTED.
- 5. THE USE OF BARRIER IS ANTICIPATED FOR MOST SITUATIONS REQUIRING APPLICATION OF THIS LANE CLOSURE. REQUIRED BARRIER PROTECTION SHALL BE DETERMINED AS DESCRIBED IN THE MOST CURRENT EDITION OF THE ROADSIDE DESIGN GUIDE AS ADOPTED BY THE DEPARTMENT TAPER RATES FOR BARRIER ARE FOUND ON THE PORTABLE CONCRETE BARRIER STANDARD (GR-23).
- 6. CRASH CUSHIONS SHALL BE DELINEATED WITH TYPE 3 OBJECT MARKERS, SEE MUTCD FIGURE 2C-13.

DEPARTMENT OF TRANSPORTATION . BUREAU OF HIGHWAY DESIGN

*** * * * * ***

ROAD

AHEAD

LANE CLOSURE: TWO-LANE ROAD
WITH LOW TRAFFIC VOLUMES

STATE OF NEW HAMPSHIRE

SPECIAL DETAILS

LEGEND

YIELD LINES

PORTABLE BARRIER

IMPACT ATTENUATOR

CHANNELIZING DEVICES

REVISION DATE DGN STATE PROJECT NO. SHEET NO. TOTAL SHEETS

03-16-17 | TWINTO-LOW/OI _ 3 12


END \


G20-2a ★

ROAD WORK

(IF REQUIRED)

NOT TO SCALE





NOT TO SCALE

PAVEMENT MARKINGS AND RAISED PAVEMENT MARKER REFLECTORS BETWEEN THE

ACTIVITY AREA AND THE STOP LINES SHALL BE REMOVED.

STANDARD NO. TC-7

CONTROL WITH BARRIER

