



Information Report

EASTERN TPK STATEWIDE ITS R&R

42934

NON-FEDERAL

County: BELKNAP, CARROLL, CHESHIRE, COOS, GRAFTON, HILLSBOROUGH, MERRIMACK, ROCKINGHAM, STRAFFORD, SULLIVAN

Date Bids Open: 3/21/2024

Scope of Work: Eastern TPK Statewide ITS R&R

Location: Eastern TPK Statewide

Completion Date: 9/26/2025

Proposal Guarantee: 5% of bid amount

Item Number	Item Description	Unit	Estimated Quantity
EASTERN TPK STATEWIDE ITS R&R 42934			
ITS - 101 E 130.0			
202.7	REMOVAL OF GUARDRAIL	LF	200.00
202.82211	REMOVE DMS STRUCTURE	U	1.00
202.82221	REMOVE DMS BOARD	U	1.00
203.5525	PORTABLE CHANGEABLE MESSAGE SIGN PLATFORM	U	1.00
203.5561	EAGRT PLATFORM PREFERRED	U	1.00
606.1254	BEAM GUARDRAIL (TERMINAL UNIT TYPE EAGRT, TL 3) (STEEL POST)	U	1.00
606.1471	BEAM GUARDRAIL (TERMINAL UNIT TYPE G-2) (MASH MID-SPLICE)	U	1.00
606.18001	31" W-BEAM GUARDRAIL WITH 8" OFFSET BLOCK (STEEL POST)	LF	225.00
614.72114	2" PVC CONDUIT, SCHEDULE 40	LF	203.00
618.61	UNIFORMED OFFICERS WITH VEHICLE	\$	50,000.00
619.1	MAINTENANCE OF TRAFFIC	U	0.34
619.25	PORTABLE CHANGEABLE MESSAGE SIGN	U	2.00
619.279	AUTOMATED TRAILER-MOUNTED SPEED LIMIT SIGN	U	2.00
619.63	TRUCK-MOUNTED IMPACT ATTENUATOR, TEST LEVEL 3	U	2.00
621.2	RETROREFLECTIVE BEAM GUARDRAIL DELINEATOR	EA	10.00

621.31	SINGLE DELINEATOR WITH POST	EA	3.00
621.32	DOUBLE DELINEATOR WITH POST	EA	3.00
645.512	COMPOST SOCK FOR PERIMETER BERM	LF	225.00
646.41	TURF ESTABLISHMENT WITH MULCH, TACKIFIERS AND HUMUS	SY	582.00
677.1201	PERMANENT FIXED LOCATION DYNAMIC MESSAGE SIGN (DMS)	U	1.00
677.317	RELOCATE WIRELESS COMMUNICATIONS EQUIPMENT	U	1.00
677.54101	GROUND MOUNTED ITS EQUIPMENT CABINET	U	1.00
677.5812	1 GBPS ETHERNET SWITCH	EA	1.00
677.67201	SOLAR POWERED SYSTEM (POLE MOUNTED)	U	1.00
677.9306	3-CONDUCTOR #6 AWG CABLE	LF	90.00
692.	MOBILIZATION	U	0.34
699.	MISCELLANEOUS TEMPORARY EROSION AND SEDIMENT CONTROL	\$	5,000.00
1008.11	ALTERATIONS AND ADDITIONS AS NEEDED - UNANTICIPATED WORK	\$	20,000.00
1010.15	FUEL ADJUSTMENT	\$	5,000.00

ITS - ST N 1.0 DMS

202.7	REMOVAL OF GUARDRAIL	LF	225.00
202.82212	REMOVE DMS STRUCTURE	U	1.00
202.83222	REMOVE AND SALVAGE DMS BOARD	U	1.00
203.5561	EAGRT PLATFORM PREFERRED	U	1.00
206.1	COMMON STRUCTURE EXCAVATION	CY	190.00
206.2	ROCK STRUCTURE EXCAVATION	CY	20.00
503.201	COFFERDAMS	U	1.00
508.	STRUCTURAL FILL	CY	20.00
520.2	CONCRETE CLASS B	CY	40.00
544.1	REINFORCING STEEL (ROADWAY)	LB	3,850.00
606.1254	BEAM GUARDRAIL (TERMINAL UNIT TYPE EAGRT, TL 3) (STEEL POST)	U	1.00
606.1471	BEAM GUARDRAIL (TERMINAL UNIT TYPE G-2) (MASH MID-SPLICE)	U	1.00

606.18001	31" W-BEAM GUARDRAIL WITH 8" OFFSET BLOCK (STEEL POST)	LF	200.00
614.72114	2" PVC CONDUIT, SCHEDULE 40	LF	75.00
615.20001	CANTILEVER TRAFFIC SIGN STRUCTURE	U	1.00
619.1	MAINTENANCE OF TRAFFIC	U	0.33
645.512	COMPOST SOCK FOR PERIMETER BERM	LF	225.00
646.41	TURF ESTABLISHMENT WITH MULCH, TACKIFIERS AND HUMUS	SY	556.00
677.12101	PERMANENT FIXED LOCATION DYNAMIC MESSAGE SIGN (DMS - OHSS)	U	1.00
677.9306	3-CONDUCTOR #6 AWG CABLE	LF	40.00
692.	MOBILIZATION	U	0.33
1010.15	FUEL ADJUSTMENT	\$	5,000.00
ITS - ST S 7.7			
202.82213	REMOVE DMS STRUCTURE	U	1.00
202.82223	REMOVE DMS BOARD	U	1.00
614.72114	2" PVC CONDUIT, SCHEDULE 40	LF	75.00
619.1	MAINTENANCE OF TRAFFIC	U	0.33
645.512	COMPOST SOCK FOR PERIMETER BERM	LF	225.00
646.41	TURF ESTABLISHMENT WITH MULCH, TACKIFIERS AND HUMUS	SY	556.00
677.1202	PERMANENT FIXED LOCATION DYNAMIC MESSAGE SIGN (DMS)	U	1.00
677.317	RELOCATE WIRELESS COMMUNICATIONS EQUIPMENT	U	1.00
677.54101	GROUND MOUNTED ITS EQUIPMENT CABINET	U	1.00
677.9306	3-CONDUCTOR #6 AWG CABLE	LF	40.00
692.	MOBILIZATION	U	0.33
1010.15	FUEL ADJUSTMENT	\$	5,000.00
Alternate A - ITS - Alternate A - 95 N 0.4			
203.5561	EAGRT PLATFORM PREFERRED	U	1.00
606.1254	BEAM GUARDRAIL (TERMINAL UNIT TYPE EAGRT, TL 3) (STEEL POST)	U	1.00
606.1471	BEAM GUARDRAIL (TERMINAL UNIT TYPE G-2) (MASH MID-SPLICE)	U	1.00

606.18001	31" W-BEAM GUARDRAIL WITH 8" OFFSET BLOCK (STEEL POST)	LF	225.00
606.417	PORTABLE CONCRETE BARRIER FOR TRAFFIC CONTROL	LF	750.00
606.9522	TEMP. IMPACT ATTENUATION DEVICE (NON-REDIRECTIVE) TEST LEVEL 2	U	1.00
606.9523	TEMP. IMPACT ATTENUATION DEVICE (NON-REDIRECTIVE) TEST LEVEL 3	U	1.00
614.72114	2" PVC CONDUIT, SCHEDULE 40	LF	90.00
619.11	MAINTENANCE OF TRAFFIC	U	1.00
645.512	COMPOST SOCK FOR PERIMETER BERM	LF	225.00
646.41	TURF ESTABLISHMENT WITH MULCH, TACKIFIERS AND HUMUS	SY	556.00
677.1203	PERMANENT FIXED LOCATION DYNAMIC MESSAGE SIGN (DMS)	U	1.00
677.317	RELOCATE WIRELESS COMMUNICATIONS EQUIPMENT	U	1.00
677.54101	GROUND MOUNTED ITS EQUIPMENT CABINET	U	1.00
677.5812	1 GBPS ETHERNET SWITCH	EA	1.00
677.67201	SOLAR POWERED SYSTEM (POLE MOUNTED)	U	1.00
677.9306	3-CONDUCTOR #6 AWG CABLE	LF	40.00
692.1	MOBILIZATION	U	1.00
1010.15	FUEL ADJUSTMENT	\$	5,000.00