



# Information Report

PORTSMOUTH  
43760  
X-A005(230)

County: ROCKINGHAM  
 Date Bids Open: 5/16/2024  
 Scope of Work: Soundwalls/privacy fence along I-95 in Portsmouth  
 Location: I-95  
 Completion Date: 6/27/2025  
 Proposal Guarantee: 5% of bid amount

Item Number	Item Description	Unit	Estimated Quantity
<b>PORTSMOUTH 43760</b>			
<b>Soundwall</b>			
201.1	CLEARING AND GRUBBING (F)	A	2.40
201.881	INVASIVE SPECIES CONTROL TYPE I	SY	11,000.00
201.882	INVASIVE SPECIES CONTROL TYPE II	SY	2,700.00
202.7	REMOVAL OF GUARDRAIL	LF	3,400.00
202.8	REMOVAL OF FENCE	LF	3,250.00
202.84	REMOVAL OF LIGHT POLE BASES	EA	10.00
203.1	COMMON EXCAVATION	CY	360.00
203.11	COMMON EXCAVATION - LRS	CY	2,800.00
203.112	COMMON EXCAVATION - LRS/PFAS	CY	28.00
203.12	COMMON EXCAVATION - PFAS	CY	220.00
203.6	EMBANKMENT-IN-PLACE (F)	CY	7,500.00
206.19	COMMON STRUCTURE EXCAVATION EXPLORATORY	CY	150.00
214.	FINE GRADING	U	1.00
304.4	CRUSHED STONE (FINE GRADATION) (F)	CY	350.00
403.11943	HBP-1/2" SURFACE MIX, MACHINE METHOD, HIGH STRENGTH	TON	475.00

403.12	HBP-HAND METHOD	TON	9.00
403.16	PAVEMENT JOINT ADHESIVE	LF	3,150.00
410.22	ASPHALT EMULSION FOR TACK COAT	GAL	165.00
417.	COLD PLANING BITUMINOUS SURFACES	SY	2,700.00
504.1	COMMON BRIDGE EXCAVATION (F)	CY	832.00
508.	STRUCTURAL FILL	CY	90.00
509.1	MOBILIZATION AND DEMOBILIZATION OF DRILLED SHAFT DRILLING EQUIPMENT	U	1.00
509.2	DRILLED SHAFTS	LF	4,700.00
509.3	OBSTRUCTION REMOVAL	LF	48.00
509.4	ROCK SOCKET EXCAVATION	LF	750.00
529.6	PRECAST CONCRETE PANEL SOUND ABATEMENT WALL	SF	103,500.00
529.90480	PRECAST PRIVACY FENCE, 8'	LF	1,000.00
534.3	WATER REPELLENT (SILANE/SILOXANE)	GAL	19.00
585.2	STONE FILL, CLASS B	CY	850.00
585.5	STONE FILL, CLASS E	CY	500.00
592.31	PRECAST CONCRETE MODULAR RETAINING WALL	SF	2,108.50
593.421	GEOTEXTILE; PERM CONTROL CL.2, NON-WOVEN	SY	1,950.00
603.00218	18" R.C. PIPE, 2000D	LF	12.00
604.114	CATCH BASINS TYPE A, 4-FOOT DIAMETER	U	3.00
604.4	RECONSTRUCTING/ADJUSTING CATCH BASIN & DROP INLET	LF	3.00
605.506	6" PERF. CORR. POLYETHYLENE PIPE UNDERDRAIN	LF	3,000.00
606.18001	31" W-BEAM GUARDRAIL WITH 8" OFFSET BLOCK (STEEL POST)	LF	125.00
606.312	SINGLE FACED TRANSITION RAIL, STEEL POST	U	6.00
606.41231	TRANSITION SINGLE SLOPE CONCRETE BARRIER, PRECAST	U	6.00
606.413	SINGLE SLOPE CONCRETE MEDIAN BARRIER, PRECAST	LF	3,100.00
606.417	PORTABLE CONCRETE BARRIER FOR TRAFFIC CONTROL	LF	6,800.00
606.41741	PORTABLE CONCRETE BARRIER FOR TRAFFIC CONTROL - BRIDGE	LF	220.00

606.91	RESETTING OR SETTING GUARDRAIL	LF	300.00
606.9523	TEMP. IMPACT ATTENUATION DEVICE (NON-REDIRECTIVE) TEST LEVEL 3	U	2.00
607.360	CHAIN LINK FENCE WITH VINYL COATED STEEL FABRIC, 6' HIGH	LF	100.00
607.73610	10' OPENING DOUBLE GATE, CHAIN LINK VINYL COATED STEEL FABRIC, 6' HIGH	U	1.00
607.9360	RESET CHAIN LINK FENCE WITH VINYL COATED FABRIC, 6' HIGH	LF	2,460.00
615.013	REMOVING TRAFFIC SIGN TYPE A	U	1.00
615.014	RELOCATING TRAFFIC SIGN TYPE A	U	2.00
615.034	RELOCATING TRAFFIC SIGN, TYPE C	U	6.00
618.61	UNIFORMED OFFICERS WITH VEHICLE	\$	496,500.00
619.1	MAINTENANCE OF TRAFFIC	U	1.00
619.25	PORTABLE CHANGEABLE MESSAGE SIGN	U	4.00
619.279	AUTOMATED TRAILER-MOUNTED SPEED LIMIT SIGN	U	2.00
619.63	TRUCK-MOUNTED IMPACT ATTENUATOR, TEST LEVEL 3	U	2.00
621.1	RETROREFLECTIVE MEDIAN BARRIER DELINEATOR	EA	35.00
622.1	STEEL WITNESS MARKERS	EA	7.00
625.893	REMOVE HIGH MAST LIGHT POLE	U	3.00
628.2	SAWED BITUMINOUS PAVEMENT	LF	3,200.00
632.1106	PREFORMED RETROREFLECTIVE TAPE, TYPE I (REMOVABLE) 6" LINE	LF	2,300.00
632.1112	PREFORMED RETROREFLECTIVE TAPE, TYPE I (REMOVABLE) 12" LINE	LF	550.00
632.1308	BLACKOUT PAVEMENT MARKING TAPE, TYPE I (REMOVABLE), 8"	LF	2,000.00
632.71206	GROOVED RETROREFLECTIVE POLYUREA PAVEMENT MARKING, 6" LINE	LF	1,000.00
632.71212	GROOVED RETROREFLECTIVE POLYUREA PAVEMENT MARKING, 12" LINE	LF	650.00
643.12	FERTILIZER FOR INITIAL APPLICATION	TON	2.00
643.22	FERTILIZER FOR REFERTILIZATION	TON	2.00
645.119	MULCH WITH TACKIFIERS	A	1.00
645.3	EROSION STONE	TON	350.00
645.44	TEMPORARY SLOPE MATTING TYPE D (WILDLIFE FRIENDLY)	SY	7,000.00

645.531	SILT FENCE	LF	7,500.00
645.611	BONDED FIBER MATRIX (BFM)	LB	4,400.00
645.7	STORM WATER POLLUTION PREVENTION PLAN	U	1.00
645.71	WATER QUALITY MONITORING, INSPECTION AND REPORTING	HR	310.00
645.72	FINAL WETLAND IMPACT REPORT	U	1.00
645.75	COLD WEATHER STABILIZATION PLAN	U	1.00
646.3	TURF ESTABLISHMENT WITH MULCH AND TACKIFIERS	A	3.00
647.1	HUMUS	CY	2,800.00
660.61	DOOR FOR SOUND ABATEMENT WALL	U	3.00
670.104	TEMPORARY PORTABLE LIGHTING	U	4.00
670.1619	DISCHARGE PERMIT FOR CONTAMINATED WATER	U	1.00
692.	MOBILIZATION	U	1.00
697.11	INVASIVE SPECIES CONTROL AND MANAGEMENT PLAN	U	1.00
697.31	PROJECT OPERATIONS PLAN	U	1.00
698.12	FIELD OFFICE TYPE B	MON	26.00
699.	MISCELLANEOUS TEMPORARY EROSION AND SEDIMENT CONTROL	\$	175,000.00
1010.15	FUEL ADJUSTMENT	\$	100,000.00
1010.2	ASPHALT CEMENT ADJUSTMENT	\$	10,000.00