



Information Report

AUBURN
44167
X-A005(339)

County: ROCKINGHAM
 Date Bids Open: 3/28/2024
 Scope of Work: Replacement of 60" cmp under Route 121, located 600 ft west of Bunker Hill rd. in Auburn.
 Location: NH Route 121
 Completion Date: 11/22/2024
 Proposal Guarantee: 5% of bid amount

Item Number	Item Description	Unit	Estimated Quantity
AUBURN 44167			
Culvert Replacement			
201.881	INVASIVE SPECIES CONTROL TYPE I	SY	5.00
201.882	INVASIVE SPECIES CONTROL TYPE II	SY	30.00
202.42	REMOVAL OF EXISTING PIPE OVER 24" DIAMETER	LF	41.00
202.7	REMOVAL OF GUARDRAIL	LF	262.50
203.1	COMMON EXCAVATION	CY	130.00
203.11	COMMON EXCAVATION - LRS	CY	50.00
203.5525	PORTABLE CHANGEABLE MESSAGE SIGN PLATFORM	U	2.00
203.553	PORTABLE TRAFFIC SIGNAL PLATFORM	U	3.00
214.	FINE GRADING	U	1.00
304.32	CRUSHED GRAVEL FOR SHOULDER LEVELING	TON	20.00
304.35	CRUSHED GRAVEL FOR DRIVES	CY	5.00
304.4	CRUSHED STONE (FINE GRADATION) (F)	CY	55.00
403.11023	HBP-3/4" BINDER MIX, MACHINE METHOD	TON	50.00
403.11043	HBP-1/2" SURFACE MIX, MACHINE METHOD	TON	45.00
403.16	PAVEMENT JOINT ADHESIVE	LF	140.00

403.19	HBP-TEMPORARY	TON	60.00
410.22	ASPHALT EMULSION FOR TACK COAT	GAL	35.00
417.	COLD PLANING BITUMINOUS SURFACES	SY	120.00
503.101	WATER DIVERSION STRUCTURE	U	1.00
503.201	COFFERDAMS	U	1.00
529.001	PRECAST CONCRETE BOX CULVERT	U	1.00
585.3401	SIMULATED STREAMBED MATERIAL	CY	40.00
606.000	STEEL BEAM FOR BEAM GUARDRAIL	LF	25.00
606.012	W6X9 STEEL POST REPLACEMENTS FOR BEAM GUARDRAIL POSTS	EA	5.00
606.0122	W6X9 STEEL POST ASSEMBLIES FOR BEAM GUARDRAIL POSTS	EA	5.00
606.417	PORTABLE CONCRETE BARRIER FOR TRAFFIC CONTROL	LF	330.00
606.91	RESETTING OR SETTING GUARDRAIL	LF	262.50
606.91255	RESETTING TERMINAL UNIT (TYPE TL 2 EAGRT) (STEEL POST)	U	4.00
606.9522	TEMP. IMPACT ATTENUATION DEVICE (NON-REDIRECTIVE) TEST LEVEL 2	U	4.00
616.171	PORTABLE TRAFFIC SIGNALS (PTS) SYSTEM	U	1.00
618.61	UNIFORMED OFFICERS WITH VEHICLE	\$	16,800.00
618.7	FLAGGERS	HR	600.00
619.1	MAINTENANCE OF TRAFFIC	U	1.00
619.25	PORTABLE CHANGEABLE MESSAGE SIGN	U	2.00
622.1	STEEL WITNESS MARKERS	EA	2.00
628.2	SAWED BITUMINOUS PAVEMENT	LF	150.00
632.0104	RETROREFLECTIVE PAINT PAVE. MARKING, 4" LINE	LF	2,000.00
632.1118	PREFORMED RETROREFLECTIVE TAPE, TYPE I (REMOVABLE) 18" LINE	LF	30.00
632.911	OBLITERATE PAVE. MARKING LINE, 12" WIDE & UNDER	LF	500.00
645.0001	TURBIDITY BARRIER	LF	50.00
645.44	TEMPORARY SLOPE MATTING TYPE D (WILDLIFE FRIENDLY)	SY	1,000.00
645.512	COMPOST SOCK FOR PERIMETER BERM	LF	500.00

645.531	SILT FENCE	LF	500.00
645.71	WATER QUALITY MONITORING, INSPECTION AND REPORTING	HR	84.00
645.72	FINAL WETLAND IMPACT REPORT	U	1.00
645.73	STREAM DIVERSION PLAN	U	1.00
645.74	EROSION CONTROL PLAN	U	1.00
645.75	COLD WEATHER STABILIZATION PLAN	U	1.00
646.41	TURF ESTABLISHMENT WITH MULCH, TACKIFIERS AND HUMUS	SY	1,250.00
647.1	HUMUS	CY	50.00
670.046	CONSTRUCT AND REMOVE TEMPORARY WIDENING	U	1.00
670.066	MAILBOX SUPPORT ASSEMBLIES	EA	1.00
670.104	TEMPORARY PORTABLE LIGHTING	U	2.00
692.	MOBILIZATION	U	1.00
697.11	INVASIVE SPECIES CONTROL AND MANAGEMENT PLAN	U	1.00
697.31	PROJECT OPERATIONS PLAN	U	1.00
698.13	FIELD OFFICE TYPE C	MON	6.00
699.	MISCELLANEOUS TEMPORARY EROSION AND SEDIMENT CONTROL	\$	3,500.00
1008.251	ALTERATIONS AND ADDITIONS AS NEEDED - TEMPORARY PEDESTRIAN ACCOMMODATIONS	\$	5,000.00
1010.15	FUEL ADJUSTMENT	\$	10,000.00