



The State of New Hampshire  
**Department of Environmental Services**



**Robert R. Scott, Commissioner**

---

**WETLANDS AND NON-SITE SPECIFIC PERMIT 2018-03317**

**NOTE CONDITIONS**

**PERMITTEE:** NH DEPT OF TRANSPORTATION  
PO BOX 483  
CONCORD NH 03302

**PROJECT LOCATION:** BROWNFIELD RD OVER SNOW BROOK, EATON  
TAX MAP #ROW, LOT #ROW

**WATERBODY:** SNOW BROOK

**TIME EXTENSION:** OCTOBER 31, 2023

**APPROVAL DATE:** JANUARY 31, 2019      **EXPIRATION DATE:** JANUARY 31, 2029

---

Based upon review of permit application 2018-03317 in accordance with RSA 482-A and RSA 485-A:17, the New Hampshire Department of Environmental Services (NHDES) hereby issues this Wetlands and Non-Site Specific Permit. To validate this Permit, signatures of the Permittee and the Principal Contractor are required.

**PERMIT DESCRIPTION:**

Install a 6 in. concrete invert in a 16 ft. wide x 72 ft. long metal culvert (bridge 084/114), place riprap along the wingwalls and within the channel to protect the inlet and outlet and install a downstream fish weir to back water through the pipe during low flow periods impacting 3,686 sq. ft. (2,236 sq. ft. temporary) of riverine wetlands. NHDOT project #41864.

**THIS PERMIT IS SUBJECT TO THE FOLLOWING PROJECT-SPECIFIC CONDITIONS:**

1. All work shall be in accordance with plans by NHDOT Bureau of Bridge Maintenance dated 9/26/18 and weir detail dated 10/10/18 as received by the Department on Oct. 24, 2018.
2. Dredged material shall be placed out of the DES Wetlands Bureau jurisdiction.
3. Unconfined work within the brook, exclusive of work associated with installation of a cofferdam, shall be done during periods of low flow.
4. Cofferdams shall not be installed during periods of high flow, whether due to seasonal runoff or precipitation. Once a cofferdam is fully effective, confined work can proceed without restriction.
5. Prior to commencing work on a substructure located within surface waters, a cofferdam shall be constructed to isolate the substructure work area from the surface waters.
6. Temporary cofferdams shall be entirely removed immediately following construction.
7. Construction equipment shall not be located within surface waters.
8. Discharge from dewatering of work areas shall be to sediment basins that are: a) located in uplands; b) lined with hay bales or other acceptable sediment trapping liners; c) set back as far as possible from wetlands and surface waters, with a preferred undisturbed vegetated buffer of at least 50 feet and a minimum undisturbed vegetative buffer of 20 feet.

[www.des.nh.gov](http://www.des.nh.gov)

29 Hazen Drive • PO Box 95 • Concord, NH 03302-0095

NHDES Main Line: (603) 271-3503 • Subsurface Fax: (603) 271-6683 • Wetlands Fax: (603) 271-6588

TDD Access: Relay NH 1 (800) 735-2964

9. Appropriate turbidity controls shall be installed prior to construction, shall be maintained during construction such that no turbidity escapes the immediate dredge area, and shall remain until suspended particles have settled and the water at the work site has returned to normal clarity.
10. Within three days of the last activity in an area, all exposed soil areas, where construction activities are complete, shall be stabilized by seeding and mulching during the growing season, or if not within the growing season, by mulching with tack on slopes steeper than 3:1 or netting /matting and pinning on slopes steeper than 2:1.
11. Where construction activities have been temporarily suspended within the growing season, all exposed soil areas shall be stabilized within 14 days by seeding and mulching or if temporarily suspended outside the growing season, all exposed areas shall be stabilized within 14 days by mulching, mulching with tack on slopes steeper than 3:1 and stabilized by matting and pinning on slopes steeper than 2:1.
12. The contractor responsible for completion of the work shall utilize techniques described in the New Hampshire Stormwater Manual, Volume 3, Erosion and Sediment Controls During Construction (December 2008).
13. Extreme precautions to be taken within riparian areas to limit unnecessary removal of vegetation during road construction and areas cleared of vegetation to be revegetated as quickly as possible.
14. There shall be no further alteration to wetlands or surface waters without amendment of this permit.
15. Precautions shall be taken to prevent import or transport of soil or seed stock containing nuisance or invasive species such as Purple Loosestrife, Knotweed, or Phragmites. The contractor responsible for work shall appropriately address invasive species in accordance with the NHDOT Best Management Practices for Roadside Invasive Plants (2008).
16. To prevent the introduction of invasive plant species to the site, the permittee's contractor(s) shall clean all soils and vegetation from construction equipment and matting before such equipment is moved to the site.
17. NO EQUIPMENT shall be located in the forested area downstream of the culvert.
18. The permittee shall conduct yearly inspections in accordance with the Monitoring Plan and submit a summary report to the file by Nov. 1st for three years after project completion to assure the absence of a perched outlet.

**THIS PERMIT IS SUBJECT TO THE FOLLOWING GENERAL CONDITIONS:**

1. Pursuant to RSA 482-A:12, a copy of this permit shall be posted in a secure manner in a prominent place at the site of the approved project.
2. In accordance with Env-Wt 313.01(a)(5), and as required by RSA 482-A:11, II, work shall not infringe on the property rights or unreasonably affect the value or enjoyment of property of abutting owners.
3. In accordance with Env-Wt 314.01, a standard permit shall be signed by the permittee, and the principal contractor who will build or install the project prior to start of construction, and will not be valid until signed.
4. In accordance with Env-Wt 314.03(a), the permittee shall notify the department in writing at least one week prior to commencing any work under this permit.
5. In accordance with Env-Wt 314.08(a), the permittee shall file a completed notice of completion of work and certificate of compliance with the department within 10 working days of completing the work authorized by this permit.
6. In accordance with Env-Wt 314.06, transfer of this permit to a new owner shall require notification to, and approval of, the NHDES.
7. The permit holder shall ensure that work is done in a way that protects water quality per Env-Wt 307.03; protects fisheries and breeding areas per Env-Wt 307.04; protects against invasive species per Env-Wt 307.05; meets dredging activity conditions in Env-Wt 307.10; and meets filling activity conditions in Env-Wt 307.11.
8. This project has been screened for potential impact to known occurrences of protected species and exemplary natural communities in the immediate area. Since many areas have never been surveyed, or only cursory surveys have been performed, unidentified sensitive species or communities may be present. This permit does not absolve the permittee from due diligence in regard to state, local or federal laws regarding such communities or species. This permit does not authorize in any way the take of threatened or endangered species, as defined by RSA 212-A:2, or of any protected species or exemplary natural communities, as defined in RSA 217-A:3.
9. In accordance with Env-Wt 307.06(a) through (c), no activity shall jeopardize the continued existence of a threatened or endangered species, a species proposed for listing as threatened or endangered, or a designated or

proposed critical habitat under the Federal Endangered Species Act, 16 U.S.C. §1531 et seq.; State Endangered Species Conservation Act, RSA 212-A; or New Hampshire Native Plant Protection Act, RSA 217-A.

10. In accordance with Env-Wt 307.02, and in accordance with federal requirements, all work in areas under the jurisdiction of the U.S. Army Corps of Engineers (USACE) shall comply with all conditions of the applicable state general permit.

APPROVED:



Darlene Forst  
Administrator, Wetlands Bureau  
Land Resources Management, Water Division

**THE SIGNATURES BELOW ARE REQUIRED TO VALIDATE THIS PERMIT (Env-Wt 314.01).**

\_\_\_\_\_  
PERMITTEE SIGNATURE (required)

\_\_\_\_\_  
PRINCIPAL CONTRACTOR SIGNATURE (required)