

Appendix B
Independent Assurance / Acceptance Test
Acceptable Deviations

Type of Test	% Deviation
Sieve Analysis – All Items #4 (4.75mm) Sieve and Larger	+ 5%
Smaller than #4 (4.75mm) Sieve (Sand Portion)	+ 4%
Compaction testing – All Items	+ 2.5%
Bituminous Mix Evaluation #4 (4.75) Sieve to 3/4"	+ 3%
Smaller than #4 (4.75mm) Sieve (Total Sample)	+ 2%
Asphalt Content	+ 0.4%
Portland Cement Concrete	
Air Content	+ 0.8%
Water/Cement	0.03

Appendix C

**Sample Materials Certification for
Municipally Managed NHDOT Project**

Date:

Project Name & Number:

This is to certify that:

The results of the tests used in the acceptance program indicate that the materials incorporated in the construction work, and the construction operations controlled by the sampling and testing, were in conformity with the approved plans and specifications. Exceptions to the above statement are explained in the attachment to this certification.

Duly Authorized Municipal Official

Date

Resident Engineer

Date